



18 July 2024

Planning Officer: Brian Millard
Direct Phone: 074086 4649
Our Reference: MCU/23/0012
Your Reference: F22/21

Two Rivers Community School
C/- Freshwater Planning Pty Ltd
17 Barron View Drive
FRESHWATER QLD 4870

Dear Applicant/s

Decision Notice

Planning Act 2016

I refer to your application and advise that on 17 July 2024, Council decided to approve the application in full subject to conditions.

Details of the decision are as follows:

APPLICATION DETAILS

Application No:	MCU/23/0012
Street Address:	Chewko Road and 267 Mclver Road, Mareeba
Real Property Description:	Lot 71 on SP292140
Planning Scheme:	Mareeba Shire Council Planning Scheme 2016

DECISION DETAILS

Type of Decision:	Approval
Type of Approval:	Development Permit for Material Change of Use Educational Establishment
Date of Decision:	17 July 2024

CURRENCY PERIOD OF APPROVAL

The currency period for this development approval is six (6) years starting the day that this development approval takes effect. (Refer to Section 85 "Lapsing of approval at end of currency period" of the *Planning Act 2016*.)

INFRASTRUCTURE

Where conditions relate to the provision of infrastructure, these are non-trunk infrastructure conditions unless specifically nominated as a "**necessary infrastructure condition**" for the provision of trunk infrastructure as defined under Chapter 4 of the *Planning Act 2016*.

ASSESSMENT MANAGER CONDITIONS**(C) ASSESSMENT MANAGER'S CONDITIONS (COUNCIL)****(a) Development assessable against the Planning Scheme**

1. Development must be carried out generally in accordance with the approved plans and the facts and circumstances of the use as submitted with the application, subject to any alterations:
 - found necessary by Council's delegated officer at the time of examination of the engineering plans or during construction of the development because of particular engineering requirements; and
 - to ensure compliance with the following conditions of approval.
2. Timing of Effect
 - 2.1 The conditions of the development permit applicable to each stage must be complied with to the satisfaction of Council's delegated officer prior to the commencement of the relevant stage of the use except where specified otherwise in these conditions of approval.
 - 2.2 Prior to the commencement of each stage of the use, the applicant must notify Council that all the conditions of the development permit have been complied with, except where specified otherwise in these conditions of approval.
3. General
 - 3.1 The development approval would not have been issued if not for the conditions requiring the construction of infrastructure or the payment of infrastructure charges within the conditions of approval or the Adopted Infrastructure Charges Notice.

3.2 The applicant/developer is responsible for the cost of necessary alterations to existing public utility mains, services or installations required by works in relation to the proposed development or any works required by condition(s) of this approval.

3.3 All payments or bonds required to be made to the Council pursuant to any condition of this approval must be made prior to commencement of the use and at the rate applicable at the time of payment.

3.4 All works must be designed, constructed and carried out in accordance with FNQROC Development Manual requirements (as amended) and to the satisfaction of Council's delegated officer.

3.5 Waste Management

3.5.1 On site refuge storage area/s must be provided and be screened from view from adjoining properties and road reserve by 1 metre wide landscaped screening buffer or 1.8m high solid fence or building.

3.5.2 Where bulk bins are used and are to be serviced on site, prior to the issue of a development permit for building works, Council's delegated officer must be satisfied that internal access is of adequate design and construction to allow waste collection/delivery vehicles to enter and exit the site in a forward gear only.

3.5.3 All waste storage areas must remain covered and no food scraps disposed of on-site so as to not encourage scavenging from wildlife and birdlife.

3.6 Noise Nuisance

Refrigeration equipment, pumps, compressors and mechanical ventilation systems must be located, designed, installed and maintained to achieve a maximum noise level of 3dB(A) above background levels as measured from noise sensitive locations and a maximum noise level of 8dB(A) above background levels as measured from commercial locations.

3.6 Air Conditioner & Building Plant Screening

The applicant/developer is required to install and maintain suitable screening to all air conditioning, lift motor rooms, plant and service facilities located at the top of or on the external face of the building. The screening structures must be constructed from materials that are consistent with materials used elsewhere on the facade of the building. There are to be no individual external unscreened air conditioning units attached to the exterior building facade.

3.8 Emissions

Emissions associated with the development must not cause an 'environmental nuisance' within the meaning of the Environmental Protection Act (1994) to any sensitive receptor.

3.9 Safety fencing

A child proof fence or physical barrier is provided to prevent unintended access to the following areas, directly from indoor or outdoor areas intended to accommodate children:

- (a) Vehicle manoeuvring and parking areas;
- (b) Refuse storage and servicing areas; and
- (c) Air conditioning, refrigeration plant and mechanical plant.

The location and extent of fencing shall be determined by the applicant/developer after carrying out a risk assessment.

3.10 Student Enrolments

The total number of enrolled students shall not exceed three hundred (300), unless prior approval is granted by Council for an expansion of the existing use.

3.11 Bushfire Management

3.11.1 A Bushfire Hazard Management Plan for the site, incorporating evacuation procedures, must be prepared to the satisfaction of Council's delegated officer. The approved use must comply with the requirements of the Bushfire Hazard Management Plan at all times.

3.11.2 An on-site water supply for firefighting purposes must be provided with a minimum capacity of 5,000 litres that must comprise either:

- (a) a stand-alone tank; or
- (b) a reserve section in the bottom part of the main water supply tank; or
- (c) a dam; or
- (d) a swimming pool.

Where tank water supply is provided, the outlet must be fitted with a 50mm ball valve with a camlock fitting for connection to firefighting appliances.

3.12 Biosecurity Management Plan

A Biosecurity Management Plan must be prepared and implemented for the site.

4. Infrastructure Services and Standards

4.1 Development Access

4.1.1 The access off Chewko Road must be designed and constructed in accordance with FNQROC Development Manual standard drawing for Rural Access S1105. The width and turn radius of the seal must be determined based on swept paths of the largest vehicle that would enter and exit the site.

4.1.2 The full length of the access road from Chewko Road to the property boundary must be upgraded/constructed to provide pavement and seal of a suitable standard to accommodate expected traffic volumes accessing the school.

4.1.3 The access road must be of a suitable width to accommodate two-way traffic including two buses passing each other. Turning paths confirming that vehicles can safely navigate the bends along the access road must be provided as part of the Operational Works application.

4.1.4 The railway level crossing must be upgraded in accordance with the State Assessment and Referral Agency response dated 30 May 2024.

4.1.5 The intersection of the existing access to the neighbouring properties to the south must be formalised from the new access road.

The works described above must be undertaken prior to commencement of use of Stage 1, at no cost to Council and will require approval under an Operational Works permit.

4.2 External Works

4.2.1 Design and construct the widening of Chewko Road pavement and seal on both approaches to the access intersection to provide trafficable shoulders of a width and length in accordance with Austroads Guide to Traffic Management Part 6 and Austroads Guide to Road Design Part 4A for a Rural Basic left and right turn treatment (BAL and BAR).

The works described above must be undertaken prior to commencement of use of Stage 1, at no cost to Council and will require approval under an Operational Works permit.

4.3 Revised Traffic Impact Assessment – Stage 6

- 4.3.1 A revised Traffic Impact Assessment (TIA) report must be submitted to Council prior to Stage 6 when all facilities constructed as part of Stage 1 to 5 is in operation. The TIA should analyse the impact that the development related traffic will have on Council's road network as a result of this stage and be based on actual traffic counts at the time.

Any external works determined to be required by Council following review of the revised assessment must be undertaken at no cost to Council and will require approval under an Operational Works permit.

4.4 Car Parking/Internal Driveways

- 4.4.1 The applicant/developer must ensure the development is provided with staged on-site car parking spaces generally in accordance with the approved plans, which are available solely for the parking of vehicles associated with the use of the premises.
- 4.4.2 All car parking spaces and internal driveways must be concrete, bitumen or asphalt sealed and appropriately drained prior to the commencement of the use and to the satisfaction of Council's delegated officer.
- 4.4.3 The car park must be designed in accordance with AS2890.1 Off-Street Car Parking including parking bay dimensions, aisle widths, speed control etc. The design is to be certified by an RPEQ that the car park provisions comply with Australian standards.
- 4.4.4 An internal traffic circulation design plan demonstrating swept paths must be submitted as part of the development application for Operational Works to demonstrate that adequate provision has been made for the manoeuvring of vehicles and buses.
- 4.4.5 All parking spaces and trafficable areas must be maintained in good order and safe repair for the life of the development, to the satisfaction of Council's delegated officer.

4.5 Stormwater Management

- 4.5.1 Prior to building or operational works commencing, the applicant/developer must submit a Stormwater Management Plan and Report prepared and certified by a suitably qualified design engineer (RPEQ) that meets or exceeds the standards of design and construction set out in the Queensland Urban Drainage Manual (QUDM) and the FNQROC Development Manual to the satisfaction of Council's delegated officer. The Stormwater Management Plan must allow for the proposed staging of the development.
- 4.5.2 The Stormwater Management Plan must ensure a non-worsening effect on surrounding land as a consequence of the development, and must take all reasonable and practicable measures to ensure discharge occurs in compliance with the Queensland Urban Drainage Manual (QUDM) and the FNQROC Development Manual.
- 4.5.3 The applicant/developer must construct the stormwater drainage infrastructure for the development in accordance with the approved Stormwater Management Plan and Report.
- 4.5.4 All stormwater drainage must be collected from site and discharged to an approved legal point of discharge.

4.6 Landscaping and Fencing

- 4.6.1 Prior to the commencement of the use of the site, a landscape plan must be prepared and submitted to Council's delegated officer for consideration and approval.
- 4.6.2 The landscaping plan must incorporate the following:
- (i) A minimum 10 metre wide vegetated landscape buffer for the full length of the buffer zone shown on the approved plans.
 - (ii) A minimum 10 metre wide vegetated landscape buffer for 115 metres along the common boundary with Lot 1 on RP708284, directly to the south of the sports field/running track.
 - (iii) A 1.8 metre high colorbond (neutral colour) solid screen fence must be established along the site's common boundary with Lot 1 on RP708284 for the full length of the vegetated landscape buffers required under (i) and (ii).

- (iv) The planting of one (1) shade tree for every six (6) parking spaces.

- 4.6.3 Landscaping associated with 4.6.2 (i) and (ii) must include ground cover, shrubs and trees that will grow to form an effective buffer of no less than four (4) metres in height.
- 4.6.4 Plant species are to be generally selected from the Plant Schedule in Planning Scheme Policy 6 - Landscaping and preferred plant species.
- 4.6.5 The landscaping of the site must be carried out in accordance with the endorsed landscape plan/s, and prior to the commencement of the use, and mulched, irrigated and maintained to the satisfaction of Council's delegated officer.
- 4.6.6 All landscaping must be maintained for the life of the development.

4.7 Lighting

Where installed, external lighting must be designed and installed in accordance with *AS4282 – Control of the obtrusive effects of outdoor lighting* so as not to cause nuisance to residents or obstruct or distract pedestrian or vehicular traffic.

4.8 Non-Reticulated Water Supply

The development must be provided with a potable water supply that can satisfy the standards for drinking water set by the Australian Drinking Water Guidelines 2004 (National Health and Medical Research Council and the National Resource Management Ministerial Council). All non-potable sources of water must be sign posted "non-potable water supply".

4.9 On-Site Wastewater Management

All on site effluent disposal associated with the approved use must be in compliance with the latest version of On-Site Domestic Wastewater Management Standard (ASNZ1547) to the satisfaction of the Council's delegated officer.

Note: Any on-site wastewater treatment system with a total daily peak design capacity of at least 21 equivalent persons (EP) is an Environmentally Relevant Activity (ERA 63 - Sewerage Treatment) and an Environmental Authority is required.

4.10 Electricity Supply

The development must be connected to the electricity supply network.

4.11 Telecommunications Infrastructure

The development must be provided with a connection to the national broadband network or telecommunication services.

REFERRAL AGENCIES

The referral agencies applicable to this application are:

- Schedule 10, Part 3, Division 4, Table 3 - Clearing native vegetation
- Schedule 10, Part 9, Division 4, Table 1 – Aspect of development stated in schedule 20 (Purpose 14 – Educational establishment)

The State Assessment and Referral Agency provided its response dated 30 May 2024.

A copy of the response conditions is attached.

APPROVED PLANS

The following plans are Approved plans for the development:

Plan/Document Number	Plan/Document Title	Prepared by	Dated
162/A021 Issue 5	Existing Site - 2021	LIFE Design Consulting	24/07/2023
162/A031 Issue 9	Masterplan – Final Entire Site	LIFE Design Consulting	10/10/2023
162/A041b Issue 7	Masterplan -2041 School	LIFE Design Consulting	10/10/2023
162/A041c Issue 6	Masterplan 2041 School B&W	LIFE Design Consulting	10/10/2023
162/A111 Issue 5	Stage 1 Plan	LIFE Design Consulting	24/07/2023
162/A112 Issue 3	Stage 1 Plan – Parking and Drop-off	LIFE Design Consulting	24/07/2023
162/A121 Issue 5	Stage 2 Plan	LIFE Design Consulting	24/07/2023
162/A131 Issue 6	Stage 3 Plan	LIFE Design Consulting	24/07/2023
162/A141 Issue 4	Stage 4 Plan	LIFE Design Consulting	24/07/2023
162/A151 Issue 4	Stage 5 Plan	LIFE Design Consulting	24/07/2023
162/A161 Issue 7	Final Plan	LIFE Design Consulting	24/07/2023
162/A162 Issue 3	Final Plan – Parking and Drop-off	LIFE Design Consulting	24/07/2023
162/A901 Issue 4	3D Views - Birdseye	LIFE Design Consulting	24/07/2023

162/A902 Issue 4	3D Views - Birdseye	LIFE Design Consulting	24/07/2023
162/A903 Issue 4	3D View from Entry	LIFE Design Consulting	24/07/2023
162/A911 Issue 4	3D Views – Internal courtyard	LIFE Design Consulting	24/07/2023

ADVISORY NOTES

The following notes are included for guidance and information purposes only and do not form part of the assessment manager conditions:

(D) ASSESSMENT MANAGER'S ADVICE

- (a) An Adopted Infrastructure Charges Notice has been issued with respect to the approved development. The Adopted Infrastructure Charges Notice details the type of infrastructure charge/s, the amount of the charge/s and when the charge/s are payable.

- (b) The Adopted Infrastructure Charges Notice does not include all charges or payments that are payable with respect to the approved development. A number of other charges or payments may be payable as conditions of approval. The applicable fee is set out in Council's Fees & Charges Schedule for each respective financial year.

- (c) Compliance with applicable codes/policies

The development must be carried out to ensure compliance with the provisions of Council's Local Laws, Planning Scheme Policies, Planning Scheme and Planning Scheme Codes to the extent they have not been varied by a condition of this approval.

- (d) Compliance with Acts and Regulations

The erection and use of the building must comply with the Building Act and all other relevant Acts, Regulations and Laws, and these approval conditions.

- (e) Environmental Protection and Biodiversity Conservation Act 1999

The applicant is advised that referral may be required under the *Environmental Protection and Biodiversity Conservation Act 1999* if the proposed activities are likely to have a significant impact on a matter of national environmental significance. Further information on these matters can be obtained from www.dcceew.gov.au.

- (f) Cultural Heritage

In carrying out the activity the applicant must take all reasonable and practicable measures to ensure that no harm is done to Aboriginal cultural heritage (the "cultural heritage duty of care"). The applicant will comply with the cultural heritage duty of care if the applicant acts in accordance with gazetted cultural

heritage duty of care guidelines. An assessment of the proposed activity against the duty of care guidelines will determine whether or to what extent Aboriginal cultural heritage may be harmed by the activity. Further information on cultural heritage, together with a copy of the duty of care guidelines and cultural heritage search forms, may be obtained from www.dsdsatsip.qld.gov.au.

(g) Electric Ants

Electric ants are designated as restricted biosecurity matter under the *Biosecurity Act 2014*.

Certain restrictions and obligations are placed on persons dealing with electric ant carriers within the electric ant restricted zone. Movement restrictions apply in accordance with Sections 74–77 of the *Biosecurity Regulation 2016*. Penalties may be imposed on movement of electric ant carriers and electric ants in contravention of the legislated restrictions. It is the responsibility of the applicant to check if the nominated property lies within a restricted zone.

All persons within and outside the electric ant biosecurity zone have an obligation (a **general biosecurity obligation**) to manage biosecurity risks and threats that are under their control, they know about, or they are expected to know about. Penalties may apply for failure to comply with a general biosecurity obligation.

For more information please visit the electric ant website at [Electric ants in Queensland | Business Queensland](#) or contact Biosecurity Queensland 13 25 23.

PROPERTY NOTES

Not Applicable.

FURTHER DEVELOPMENT PERMITS REQUIRED

- Development Permit for Operational Work
- Development Permit for Building Work
- Compliance Permit for Plumbing and Drainage Work

SUBMISSIONS

There were six (6) properly made submissions about the application. In accordance with the *Planning Act 2016*, the name, residential or business address, and electronic address of the principal submitter for each properly made submission is provided below:

Name of Principal submitter	Address
1. E Maksuti	42 Catherine Atherton Drive, Mareeba QLD 4880
2. C & S Bassani	PO Box 468, Mareeba QLD 4880
3. A Islam	akilislam@gmail.com
4. M Iminov	259 Mclver Road, Mareeba QLD 4880 cynthiamurat@hotmail.com
5. A Webb	1 Owens Street, Mareeba QLD 4880 webbyfnq@gmail.com
6. M & T Tiraboschi	PO Box 867, Mareeba QLD 4880 thelimeman@bigpond.com

RIGHTS OF APPEAL


You are entitled to appeal against this decision. A copy of the relevant appeal provisions from the *Planning Act 2016* is attached.

During the appeal period, you as the applicant may suspend your appeal period and make written representations to council about the conditions contained within the development approval. If council agrees or agrees in part with the representations, a "negotiated decision notice" will be issued. Only one "negotiated decision notice" may be given. Taking this step will defer your appeal period, which will commence again from the start the day after you receive a "negotiated decision notice".

OTHER DETAILS

If you wish to obtain more information about Council's decision, electronic copies are available on line at www.msc.qld.gov.au, or at Council Offices.


Yours faithfully



BRIAN MILLARD
COORDINATOR PLANNING SERVICES

Enc: Approved Plans/Documents
Referral Agency Response
Appeal Rights
Adopted Infrastructure Charge Notice

Approved Plans/Documents




1: 4000 @ A3 Existing Site - 2021 162 / A021 2007/02/19 to 02/19		Date 24/1/2023 24/1/2023 24/1/2023 24/1/2023 24/1/2023	Name [Blank] [Blank] [Blank] [Blank] [Blank]	Title [Blank] [Blank] [Blank] [Blank] [Blank]	[Blank] [Blank] [Blank] [Blank] [Blank]
Client: Mareeba Shire Council, 14/01/2023, 14/01/2023, 14/01/2023, 14/01/2023, 14/01/2023					

Two Rivers Community School, Mareeba
267 Milver Road, Mareeba QLD 4893 (access off Chewko Road)
Lot 7.1 on SP292140, 287,300sqm, Zoned Rural

LIFE
Design
LIFE DESIGN


Document: 162/02/19
Version: 1, Version Date: 15/1/2023

18/7/2024
B. W.



<p>LIFE Design LIFE DESIGN PTY LTD</p>		<p>Two Rivers Community School, Mareeba 267 McIver Road, Mareeba QLD 4883 (access off Chewio Road) Lot 71 on SP292140, 287,300sqm, Zoned Rural</p>		<p>Masterplan - Final Entire Site 162 / A031 30/09/2023 15:35:32</p>		<p>1: 4000 @ A3</p>		<p>DATE: 30/09/2023 15:35:32 DRAWN BY: J. HARRIS CHECKED BY: J. HARRIS SCALE: 1:4000 @ A3</p>	
NO	DESCRIPTION	DATE	BY	DATE	BY	DATE	BY	DATE	BY
1	Issue for Client Review	30/09/2023	J. Harris						
2	Issue for Council Review	30/09/2023	J. Harris						
3	Issue for Council Approval	30/09/2023	J. Harris						
4	Issue for Council Approval	30/09/2023	J. Harris						
5	Issue for Council Approval	30/09/2023	J. Harris						
6	Issue for Council Approval	30/09/2023	J. Harris						
7	Issue for Council Approval	30/09/2023	J. Harris						
8	Issue for Council Approval	30/09/2023	J. Harris						
9	Issue for Council Approval	30/09/2023	J. Harris						
10	Issue for Council Approval	30/09/2023	J. Harris						

18/7/2024
B. n


[illegible]

Two Rivers Community School, Mareeba
267 Midver Road, Mareeba QLD 4883 (access off Chewink Road)
Lot 7.1 on SP292140, 287,300sqm, Zoned Rural

LIFE *Design*
CONVENT 1983

Document Serial: 0000077
Version: 1, Version Date: 05/19/2023

18/7/2024
B. n. Q




Two Rivers Community School, Mareeba
267 Mdiver Road, Mareeba QLD 4883 (access off Chewko Road)
Lot 71 on SP292140, 287,300sqm, Zoned Rural

1: 1250 @ A3
Masterplan 2041 School B&W
162 / A041c
10/10/2023 15:38:19

Rev	Comments	Issued	Drawn
1	Issued for final review	10/10/2023	10/10/2023
2	Issued for final review	10/10/2023	10/10/2023
3	Issued for final review	10/10/2023	10/10/2023
4	Issued for final review	10/10/2023	10/10/2023
5	Issued for final review	10/10/2023	10/10/2023
6	Issued for final review	10/10/2023	10/10/2023
7	Issued for final review	10/10/2023	10/10/2023
8	Issued for final review	10/10/2023	10/10/2023
9	Issued for final review	10/10/2023	10/10/2023
10	Issued for final review	10/10/2023	10/10/2023

Contact: Shire of Mareeba (07) 4061 1111, shire@mareeba.qld.gov.au, www.mareeba.qld.gov.au

18/7/2024
B. n. n. n.



Two Rivers Community School, Mareeba
267 McIver Road, Mareeba QLD 4883 (access off Chewko Road)
Lot 71 on SP292140, 287,300sqm, Zoned Rural

Document Series: 02-000-77
Version: 1, Version Date: 15/11/2023

1:750 @ A3
Stage 1 Plan


162 / A111

24/07/2023 15:01:58

Contact: Geoff Wetherington 0400553, 046056716, geoff@livedesign.com.au, www.livedesign.com.au

Rev	Description	By	Date
1	Issued for planning & consent	GW	24/07/2023
2	Issued for consent	GW	24/07/2023
3	Issued for consent	GW	24/07/2023
4	Issued for consent	GW	24/07/2023
5	Issued for consent	GW	24/07/2023
6	Issued for consent	GW	24/07/2023
7	Issued for consent	GW	24/07/2023
8	Issued for consent	GW	24/07/2023
9	Issued for consent	GW	24/07/2023
10	Issued for consent	GW	24/07/2023

18/7/2024
28. nio



LIFE
Design
CONSULTING

Two Rivers Community School, Mareeba
267 McIver Road, Mareeba QLD 4883 (access off Chewko Road)
Lot 71 on SP292140, 287,300sqm, Zoned Rural

Stage 1 Plan - Parking and Drop-off

1:500 @ A3

162 / A112

24/07/2023 15:00:00


No.	Revision	Date
1	Issue for Planning to meet	24/07/2023
2	Revised Access Point	28/07/2023
3	Parking Layout	28/07/2023

Client: Two Rivers Community School, Mareeba, QLD 4883. 267 McIver Road, Mareeba QLD 4883. 287,300sqm, Zoned Rural.

18/7/2024
R. M. O. J.



Contact: Global Waffelingen DOAG-0330, 0-60 506 710, info@globalwaffelingen.nl, www.globalwaffelingen.nl



Two Rivers Community School, Mareeba
267 Mdlver Road, Mareeba QLD 4883 (access off Chewko Road)
Lot 71 on SP282140, 287,300sqm, Zoned Rural


Document Set No: 24072023
Version: 1, Version Date: 15/11/2023

1:750 @ A3
Stage 3 Plan
162 / A131
24072023 15/09/24

No.	Description	Date	By
1	Issue of this drawing	24/07/2023	MCU
2	Revised drawing	24/07/2023	MCU
3	Issue of this drawing	24/07/2023	MCU
4	Issue of this drawing	24/07/2023	MCU

Contact: Stuart McPherson 0400 000 000, 0400 000 000, 0400 000 000, 0400 000 000

18/1/2024
B. i. d. v.




Two Rivers Community School, Mareeba
287 Midver Road, Mareeba QLD 4883 (access off Crewko Road)
Lot 71 on SP 292140, 287,300sqm, Zoned Rural

1:750 @ A3
Stage 4 Plan


Item	Quantity	Unit Price	Total Price
1. 750 @ A3	750	1.00	750.00
2. Stage 4 Plan	1	1.00	1.00
3. 152 / A141	1	1.00	1.00
4. 2427 2623 15 08 03	1	1.00	1.00


Document Specific: 2-100277
Version: 1, Version Date: 15/1/2023

18/7/2024
B. n. [Signature]



18/7/2024
B. n. Q. l.





Two Rivers Community School, Mareeba
267 Mclver Road, Mareeba QLD 4883 (access off Chewko Road)
Lot 71 on SP292140, 287,300sqm, Zoned Rural


Document Symbol: 2300-01
Version: 1, Version Date: 15/11/2023

1 : 500 @ A3
Final Plan - Parking and Drop-off
162 / A162
24/07/2023 15:09:26


1	Scale of this drawing	100m	24/7/2023
2	Prepared by	100m	24/7/2023
3	Checked by	100m	24/7/2023
4	Drawn by	100m	24/7/2023
5	Reviewed by	100m	24/7/2023
6	Approved by	100m	24/7/2023
7	Client	100m	24/7/2023
8	Date	100m	24/7/2023

Contact: 08 4611 1111 (08 4611 1111), 0461 111 111, 0461 111 111, 0461 111 111

18/7/2024
B. n. n. n.




1 Persp - Birdseye from car park




2 Persp - Birdseye from East

LIFE Design CONSULTANTS	Two Rivers Community School, Mareeba 267 McIver Road, Mareeba QLD 4883 (access off Chewio Road) Lot 71 on SP292140, 287,300sqm, Zoned Rural	@ A3 3D Views - Birdseye 152 / A301 28/07/2023 09:30:12	<div> <div>4</div> <div>5</div> <div>6</div> <div>7</div> </div> <div> <div>8</div> <div>9</div> <div>10</div> <div>11</div> </div> <div> <div>12</div> <div>13</div> <div>14</div> <div>15</div> </div> <div> <div>16</div> <div>17</div> <div>18</div> <div>19</div> </div> <div> <div>20</div> <div>21</div> <div>22</div> <div>23</div> </div> <div> <div>24</div> <div>25</div> <div>26</div> <div>27</div> </div> <div> <div>28</div> <div>29</div> <div>30</div> <div>31</div> </div> <div> <div>32</div> <div>33</div> <div>34</div> <div>35</div> </div> <div> <div>36</div> <div>37</div> <div>38</div> <div>39</div> </div> <div> <div>40</div> <div>41</div> <div>42</div> <div>43</div> </div> <div> <div>44</div> <div>45</div> <div>46</div> <div>47</div> </div> <div> <div>48</div> <div>49</div> <div>50</div> <div>51</div> </div> <div> <div>52</div> <div>53</div> <div>54</div> <div>55</div> </div> <div> <div>56</div> <div>57</div> <div>58</div> <div>59</div> </div> <div> <div>60</div> <div>61</div> <div>62</div> <div>63</div> </div> <div> <div>64</div> <div>65</div> <div>66</div> <div>67</div> </div> <div> <div>68</div> <div>69</div> <div>70</div> <div>71</div> </div> <div> <div>72</div> <div>73</div> <div>74</div> <div>75</div> </div> <div> <div>76</div> <div>77</div> <div>78</div> <div>79</div> </div> <div> <div>80</div> <div>81</div> <div>82</div> <div>83</div> </div> <div> <div>84</div> <div>85</div> <div>86</div> <div>87</div> </div> <div> <div>88</div> <div>89</div> <div>90</div> <div>91</div> </div> <div> <div>92</div> <div>93</div> <div>94</div> <div>95</div> </div> <div> <div>96</div> <div>97</div> <div>98</div> <div>99</div> </div> <div> <div>100</div> <div>101</div> <div>102</div> <div>103</div> </div> <div> <div>104</div> <div>105</div> <div>106</div> <div>107</div> </div> <div> <div>108</div> <div>109</div> <div>110</div> <div>111</div> </div> <div> <div>112</div> <div>113</div> <div>114</div> <div>115</div> </div> <div> <div>116</div> <div>117</div> <div>118</div> <div>119</div> </div> <div> <div>120</div> <div>121</div> <div>122</div> <div>123</div> </div> <div> <div>124</div> <div>125</div> <div>126</div> <div>127</div> </div> <div> <div>128</div> <div>129</div> <div>130</div> <div>131</div> </div> <div> <div>132</div> <div>133</div> <div>134</div> <div>135</div> </div> <div> <div>136</div> <div>137</div> <div>138</div> <div>139</div> </div> <div> <div>140</div> <div>141</div> <div>142</div> <div>143</div> </div> <div> <div>144</div> <div>145</div> <div>146</div> <div>147</div> </div> <div> <div>148</div> <div>149</div> <div>150</div> <div>151</div> </div> <div> <div>152</div> <div>153</div> <div>154</div> <div>155</div> </div> <div> <div>156</div> <div>157</div> <div>158</div> <div>159</div> </div> <div> <div>160</div> <div>161</div> <div>162</div> <div>163</div> </div> <div> <div>164</div> <div>165</div> <div>166</div> <div>167</div> </div> <div> <div>168</div> <div>169</div> <div>170</div> <div>171</div> </div> <div> <div>172</div> <div>173</div> <div>174</div> <div>175</div> </div> <div> <div>176</div> <div>177</div> <div>178</div> <div>179</div> </div> <div> <div>180</div> <div>181</div> <div>182</div> <div>183</div> </div> <div> <div>184</div> <div>185</div> <div>186</div> <div>187</div> </div> <div> <div>188</div> <div>189</div> <div>190</div> <div>191</div> </div> <div> <div>192</div> <div>193</div> <div>194</div> <div>195</div> </div> <div> <div>196</div> <div>197</div> <div>198</div> <div>199</div> </div> <div> <div>200</div> <div>201</div> <div>202</div> <div>203</div> </div> <div> <div>204</div> <div>205</div> <div>206</div> <div>207</div> </div> <div> <div>208</div> <div>209</div> <div>210</div> <div>211</div> </div> <div> <div>212</div> <div>213</div> <div>214</div> <div>215</div> </div> <div> <div>216</div> <div>217</div> <div>218</div> <div>219</div> </div> <div> <div>220</div> <div>221</div> <div>222</div> <div>223</div> </div> <div> <div>224</div> <div>225</div> <div>226</div> <div>227</div> </div> <div> <div>228</div> <div>229</div> <div>230</div> <div>231</div> </div> <div> <div>232</div> <div>233</div> <div>234</div> <div>235</div> </div> <div> <div>236</div> <div>237</div> <div>238</div> <div>239</div> </div> <div> <div>240</div> <div>241</div> <div>242</div> <div>243</div> </div> <div> <div>244</div> <div>245</div> <div>246</div> <div>247</div> </div> <div> <div>248</div> <div>249</div> <div>250</div> <div>251</div> </div> <div> <div>252</div> <div>253</div> <div>254</div> <div>255</div> </div> <div> <div>256</div> <div>257</div> <div>258</div> <div>259</div> </div> <div> <div>260</div> <div>261</div> <div>262</div> <div>263</div> </div> <div> <div>264</div> <div>265</div> <div>266</div> <div>267</div> </div> <div> <div>268</div> <div>269</div> <div>270</div> <div>271</div> </div> <div> <div>272</div> <div>273</div> <div>274</div> <div>275</div> </div> <div> <div>276</div> <div>277</div> <div>278</div> <div>279</div> </div> <div> <div>280</div> <div>281</div> <div>282</div> <div>283</div> </div> <div> <div>284</div> <div>285</div> <div>286</div> <div>287</div> </div> <div> <div>288</div> <div>289</div> <div>290</div> <div>291</div> </div> <div> <div>292</div> <div>293</div> <div>294</div> <div>295</div> </div> <div> <div>296</div> <div>297</div> <div>298</div> <div>299</div> </div> <div> <div>300</div> <div>301</div> <div>302</div> <div>303</div> </div> <div> <div>304</div> <div>305</div> <div>306</div> <div>307</div> </div> <div> <div>308</div> <div>309</div> <div>310</div> <div>311</div> </div> <div> <div>312</div> <div>313</div> <div>314</div> <div>315</div> </div> <div> <div>316</div> <div>317</div> <div>318</div> <div>319</div> </div> <div> <div>320</div> <div>321</div> <div>322</div> <div>323</div> </div> <div> <div>324</div> <div>325</div> <div>326</div> <div>327</div> </div> <div> <div>328</div> <div>329</div> <div>330</div> <div>331</div> </div> <div> <div>332</div> <div>333</div> <div>334</div> <div>335</div> </div> <div> <div>336</div> <div>337</div> <div>338</div> <div>339</div> </div> <div> <div>340</div> <div>341</div> <div>342</div> <div>343</div> </div> <div> <div>344</div> <div>345</div> <div>346</div> <div>347</div> </div> <div> <div>348</div> <div>349</div> <div>350</div> <div>351</div> </div> <div> <div>352</div> <div>353</div> <div>354</div> <div>355</div> </div> <div> <div>356</div> <div>357</div> <div>358</div> <div>359</div> </div> <div> <div>360</div> <div>361</div> <div>362</div> <div>363</div> </div> <div> <div>364</div> <div>365</div> <div>366</div> <div>367</div> </div> <div> <div>368</div> <div>369</div> <div>370</div> <div>371</div> </div> <div> <div>372</div> <div>373</div> <div>374</div> <div>375</div> </div> <div> <div>376</div> <div>377</div> <div>378</div> <div>379</div> </div> <div> <div>380</div> <div>381</div> <div>382</div> <div>383</div> </div> <div> <div>384</div> <div>385</div> <div>386</div> <div>387</div> </div> <div> <div>388</div> <div>389</div> <div>390</div> <div>391</div> </div> <div> <div>392</div> <div>393</div> <div>394</div> <div>395</div> </div> <div> <div>396</div> <div>397</div> <div>398</div> <div>399</div> </div> <div> <div>400</div> <div>401</div> <div>402</div> <div>403</div> </div> <div> <div>404</div> <div>405</div> <div>406</div> <div>407</div> </div> <div> <div>408</div> <div>409</div> <div>410</div> <div>411</div> </div> <div> <div>412</div> <div>413</div> <div>414</div> <div>415</div> </div> <div> <div>416</div> <div>417</div> <div>418</div> <div>419</div> </div> <div> <div>420</div> <div>421</div> <div>422</div> <div>423</div> </div> <div> <div>424</div> <div>425</div> <div>426</div> <div>427</div> </div> <div> <div>428</div> <div>429</div> <div>430</div> <div>431</div> </div> <div> <div>432</div> <div>433</div> <div>434</div> <div>435</div> </div> <div> <div>436</div> <div>437</div> <div>438</div> <div>439</div> </div> <div> <div>440</div> <div>441</div> <div>442</div> <div>443</div> </div> <div> <div>444</div> <div>445</div> <div>446</div> <div>447</div> </div> <div> <div>448</div> <div>449</div> <div>450</div> <div>451</div> </div> <div> <div>452</div> <div>453</div> <div>454</div> <div>455</div> </div> <div> <div>456</div> <div>457</div> <div>458</div> <div>459</div> </div> <div> <div>460</div> <div>461</div> <div>462</div> <div>463</div> </div> <div> <div>464</div> <div>465</div> <div>466</div> <div>467</div> </div> <div> <div>468</div> <div>469</div> <div>470</div> <div>471</div> </div> <div> <div>472</div> <div>473</div> <div>474</div> <div>475</div> </div> <div> <div>476</div> <div>477</div> <div>478</div> <div>479</div> </div> <div> <div>480</div> <div>481</div> <div>482</div> <div>483</div> </div> <div> <div>484</div> <div>485</div> <div>486</div> <div>487</div> </div> <div> <div>488</div> <div>489</div> <div>490</div> <div>491</div> </div> <div> <div>492</div> <div>493</div> <div>494</div> <div>495</div> </div> <div> <div>496</div> <div>497</div> <div>498</div> <div>499</div> </div> <div> <div>500</div> <div>501</div> <div>502</div> <div>503</div> </div> <div> <div>504</div> <div>505</div> <div>506</div> <div>507</div> </div> <div> <div>508</div> <div>509</div> <div>510</div> <div>511</div> </div> <div> <div>512</div> <div>513</div> <div>514</div> <div>515</div> </div> <div> <div>516</div> <div>517</div> <div>518</div> <div>519</div> </div> <div> <div>520</div> <div>521</div> <div>522</div> <div>523</div> </div> <div> <div>524</div> <div>525</div> <div>526</div> <div>527</div> </div> <div> <div>528</div> <div>529</div> <div>530</div> <div>531</div> </div> <div> <div>532</div> <div>533</div> <div>534</div> <div>535</div> </div> <div> <div>536</div> <div>537</div> <div>538</div> <div>539</div> </div> <div> <div>540</div> <div>541</div> <div>542</div> <div>543</div> </div> <div> <div>544</div> <div>545</div> <div>546</div> <div>547</div> </div> <div> <div>548</div> <div>549</div> <div>550</div> <div>551</div> </div> <div> <div>552</div> <div>553</div> <div>554</div> <div>555</div> </div> <div> <div>556</div> <div>557</div> <div>558</div> <div>559</div> </div> <div> <div>560</div> <div>561</div> <div>562</div> <div>563</div> </div> <div> <div>564</div> <div>565</div> <div>566</div> <div>567</div> </div> <div> <div>568</div> <div>569</div> <div>570</div> <div>571</div> </div> <div> <div>572</div> <div>573</div> <div>574</div> <div>575</div> </div> <div> <div>576</div> <div>577</div> <div>578</div> <div>579</div> </div> <div> <div>580</div> <div>581</div> <div>582</div> <div>583</div> </div> <div> <div>584</div> <div>585</div> <div>586</div> <div>587</div> </div> <div> <div>588</div> <div>589</div> <div>590</div> <div>591</div> </div> <div> <div>592</div> <div>593</div> <div>594</div> <div>595</div> </div> <div> <div>596</div> <div>597</div> <div>598</div> <div>599</div> </div> <div> <div>600</div> <div>601</div> <div>602</div> <div>603</div> </div> <div> <div>604</div> <div>605</div> <div>606</div> <div>607</div> </div> <div> <div>608</div> <div>609</div> <div>610</div> <div>611</div> </div> <div> <div>612</div> <div>613</div> <div>614</div> <div>615</div> </div> <div> <div>616</div> <div>617</div> <div>618</div> <div>619</div> </div> <div> <div>620</div> <div>621</div> <div>622</div> <div>623</div> </div> <div> <div>624</div> <div>625</div> <div>626</div> <div>627</div> </div> <div> <div>628</div> <div>629</div> <div>630</div> <div>631</div> </div> <div> <div>632</div> <div>633</div> <div>634</div> <div>635</div> </div> <div> <div>636</div> <div>637</div> <div>638</div> <div>639</div> </div> <div> <div>640</div> <div>641</div> <div>642</div> <div>643</div> </div> <div> <div>644</div> <div>645</div> <div>646</div> <div>647</div> </div> <div> <div>648</div> <div>649</div> <div>650</div> <div>651</div> </div> <div> <div>652</div> <div>653</div> <div>654</div> <div>655</div> </div> <div> <div>656</div> <div>657</div> <div>658</div> <div>659</div> </div> <div> <div>660</div> <div>661</div> <div>662</div> <div>663</div> </div> <div> <div>664</div> <div>665</div> <div>666</div> <div>667</div> </div> <div> <div>668</div> <div>669</div> <div>670</div> <div>671</div> </div> <div> <div>672</div> <div>673</div> <div>674</div> <div>675</div> </div> <div> <div>676</div> <div>677</div> <div>678</div> <div>679</div> </div> <div> <div>680</div> <div>681</div> <div>682</div> <div>683</div> </div> <div> <div>684</div> <div>685</div> <div>686</div> <div>687</div> </div> <div> <div>688</div> <div>689</div> <div>690</div> <div>691</div> </div> <div> <div>692</div> <div>693</div> <div>694</div> <div>695</div> </div> <div> <div>696</div> <div>697</div> <div>698</div> <div>699</div> </div> <div> <div>700</div> <div>701</div> <div>702</div> <div>703</div> </div> <div> <div>704</div> <div>705</div> <div>706</div> <div>707</div> </div> <div> <div>708</div> <div>709</div> <div>710</div> <div>711</div> </div> <div> <div>712</div> <div>713</div> <div>714</div> <div>715</div> </div> <div> <div>716</div> <div>717</div> <div>718</div> <div>719</div> </div> <div> <div>720</div> <div>721</div> <div>722</div> <div>723</div> </div> <div> <div>724</div> <div>725</div> <div>726</div> <div>727</div> </div> <div> <div>728</div> <div>729</div> <div>730</div> <div>731</div> </div> <div> <div>732</div> <div>733</div> <div>734</div> <div>735</div> </div> <div> <div>736</div> <div>737</div> <div>738</div> <div>739</div> </div> <div> <div>740</div> <div>741</div> <div>742</div> <div>743</div> </div> <div> <div>744</div> <div>745</div> <div>746</div> <div>747</div> </div> <div> <div>748</div> <div>749</div> <div>750</div> <div>751</div> </div> <div> <div>752</div> <div>753</div> <div>754</div> <div>755</div> </div> <div> <div>756</div> <div>757</div> <div>758</div> <div>759</div> </div> <div> <div>760</div> <div>761</div> <div>762</div> <div>763</div> </div> <div> <div>764</div> <div>765</div> <div>766</div> <div>767</div> </div> <div> <div>768</div> <div>769</div> <div>770</div> <div>771</div> </div> <div> <div>772</div> <div>773</div> <div>774</div> <div>775</div> </div> <div> <div>776</div> <div>777</div> <div>778</div> <div>779</div> </div> <div> <div>780</div> <div>781</div> <div>782</div> <div>783</div> </div> <div> <div>784</div> <div>785</div> <div>786</div> <div>787</div> </div> <div> <div>788</div> <div>789</div> <div>790</div> <div>791</div> </div> <div> <div>792</div> <div>793</div> <div>794</div> <div>795</div> </div> <div> <div>796</div> <div>797</div> <div>798</div> <div>799</div> </div> <div> <div>800</div> <div>801</div> <div>802</div> <div>803</div> </div> <div> <div>804</div> <div>805</div> <div>806</div> <div>807</div> </div> <div> <div>808</div> <div>809</div> <div>810</div> <div>811</div> </div> <div> <div>812</div> <div>813</div> <div>814</div> <div>815</div> </div> <div> <div>816</div> <div>817</div> <div>818</div> <div>819</div> </div> <div> <div>820</div> <div>821</div> <div>822</div> <div>823</div> </div> <div> <div>824</div> <div>825</div> <div>826</div> <div>827</div> </div> <div> <div>828</div> <div>829</div> <div>830</div> <div>831</div> </div> <div> <div>832</div> <div>833</div> <div>834</div> <div>835</div> </div> <div> <div>836</div> <div>837</div> <div>838</div> <div>839</div> </div> <div> <div>840</div> <div>841</div> <div>842</div> <div>843</div> </div> <div> <div>844</div> <div>845</div> <div>846</div> <div>847</div> </div> <div> <div>848</div> <div>849</div> <div>850</div> <div>851</div> </div> <div> <div>852</div> <div>853</div> <div>854</div> <div>855</div> </div> <div> <div>856</div> <div>857</div> <div>858</div> <div>859</div> </div> <div> <div>860</div> <div>861</div> <div>862</div> <div>863</div> </div> <div> <div>864</div> <div>865</div> <div>866</div> <div>867</div> </div> <div> <div>868</div> <div>869</div> <div>870</div> <div>871</div> </div> <div> <div>872</div> <div>873</div> <div>874</div> <div>875</div> </div> <div> <div>876</div> <div>877</div> <div>878</div> <div>879</div> </div> <div> <div>880</div> <div>881</div> <div>882</div> <div>883</div> </div> <div> <div>884</div> <div>885</div> <div>886</div> <div>887</div> </div> <div> <div>888</div> <div>889</div> <div>890</div> <div>891</div> </div> <div> <div>892</div> <div>893</div> <div>894</div> <div>895</div> </div> <div> <div>896</div> <div>897</div> <div>898</div> <div>899</div> </div> <div> <div>900</div> <div>901</div> <div>902</div> <div>903</div> </div> <div> <div>904</div> <div>905</div> <div>906</div> <div>907</div> </div> <div> <div>908</div> <div>909</div> <div>910</div> <div>911</div> </div> <div> <div>912</div> <div>913</div> <div>914</div> <div>915</div> </div> <div> <div>916</div> <div>917</div> <div>918</div> <div>919</div> </div> <div> <div>920</div> <div>921</div> <div>922</div> <div>923</div> </div> <div> <div>924</div> <div>925</div> <div>926</div> <div>927</div> </div> <div> <div>928</div> <div>929</div> <div>930</div> <div>931</div> </div> <div> <div>932</div> <div>933</div> <div>934</div> <div>935</div> </div> <div> <div>936</div> <div>937</div> <div>938</div> <div>939</div> </div> <div> <div>940</div> <div>941</div> <div>942</div> <div>943</div> </div> <div> <div>944</div> <div>945</div> <div>946</div> <div>947</div> </div> <div> <div>948</div> <div>949</div> <div>950</div> <div>951</div> </div> <div> <div>952</div> <div>953</div> <div>954</div> <div>955</div> </div> <div> <div>956</div> <div>957</div> <div>958</div> <div>959</div> </div> <div> <div>960</div> <div>961</div> <div>962</div> <div>963</div> </div> <div> <div>964</div> <div>965</div> <div>966</div> <div>967</div> </div> <div> <div>968</div> <div>969</div> <div>970</div> <div>971</div> </div> <div> <div>972</div> <div>973</div> <div>974</div> <div>975</div> </div> <div> <div>976</div> <div>977</div> <div>978</div> <div>979</div> </div> <div> <div>980</div> <div>981</div> <div>982</div> <div>983</div> </div> <div> <div>984</div> <div>985</div> <div>986</div> <div>987</div> </div> <div> <div>988</div> <div>989</div> <div>990</div> <div>991</div> </div> <div> <div>992</div> <div>993</div> <div>994</div> <div>995</div> </div> <div> <div>996</div> <div>997</div> <div>998</div> <div>999</div> </div> <div> <div>1000</div> <div>1001</div> <div>1002</div> <div>1003</div> </div> <div> <div>1004</div> <div>1005</div> <div>1006</div> <div>1007</div> </div> <div> <div>1008</div> <div>1009</div> <div>1010</div> <div>1011</div> </div> <div> <div>1012</div> <div>1013</div> <div>1014</div> <div>1015</div> </div> <div> <div>1016</div> <div>1017</div> <div>1018</div> <div>1019</div> </div> <div> <div>1020</div> <div>1021</div> <div>1022</div> <div>1023</div> </div> <div> <div>1024</div> <div>1025</div> <div>1026</div> <div>1027</div> </div> <div> <div>1028</div> <div>1029</div> <div>1030</div> <div>1031</div> </div> <div> <div>1032</div> <div>1033</div> <div>1034</div> <div>1035</div> </div> <div> <div>1036</div> <div>1037</div> <div>1038</div> <div>1039</div> </div> <div> <div>1040</div> <div>1041</div> <div>1042</div> <div>1043</div> </div> <div> <div>1044</div> <div>1045</div> <div>1046</div> <div>1047</div> </div> <div> <div>1048</div> <div>1049</div> <div>1050</div> <div>1051</div> </div> <div> <div>1052</div> <div>1053</div> <div>1054</div> <div>1055</div> </div> <div> <div>1056</div> <div>1057</div> <div>1058</div> <div>1059</div> </div> <div> <div>1060</div> <div>1061</div> <div>1062</div> <div>1063</div> </div> <div> <div>1064</div> <div>1065</div> <div>1066</div> <div>1067</div> </div> <div> <div>1068</div> <div>1069</div> <div>1070</div> <div>1071</div> </div> <div> <div>1072</div> <div>1073</div> <div>1074</div> <div>1075</div> </div> <div> <div>1076</div> <div>1077</div> <div>1078</div> <div>1079</div> </div> <div> <div>1080</div> <div>1081</div> <div>1082</div> <div>1083</div> </div> <div> <div>1084</div> <div>1085</div> <div>1086</div> <div>1087</div> </div> <div> <div>1088</div> <div>1089</div> <div>1090</div> <div>1091</div> </div> <div> <div>1092</div> <div>1093</div> <div>1094</div> <div>1095</div> </div> <div> <div>1096</div> <div>1097</div> <div>1098</div> <div>1099</div> </div> <div> <div></div></div>
--------------------------------------	--	--	---



1 Persp - Birdseye from North



2 Persp - Birdseye from South

LIFE		Decision	
Document Details			
Version: 1	Version Date: 15/11/2023		
Project Details			
Two Rivers Community School, Mareeba		3D Views - Birdseye	
267 Midler Road, Mareeba QLD 4883 (access off Crewko Road)		162 / A902	
Lot 71 on SP292140, 287,300sqm, Zoned Rural		24/07/2023 15:30:54	
Client: Mareeba Shire Council		Project Manager: [Name]	
Project Number: [Number]		Project Name: [Name]	
Project Location: [Location]		Project Status: [Status]	
Project Start Date: [Date]		Project End Date: [Date]	
Project Budget: [Budget]		Project Cost: [Cost]	
Project Risk: [Risk]		Project Quality: [Quality]	
Project Safety: [Safety]		Project Environment: [Environment]	
Project Social: [Social]		Project Cultural: [Cultural]	
Project Economic: [Economic]		Project Legal: [Legal]	
Project Political: [Political]		Project Ethical: [Ethical]	
Project Technical: [Technical]		Project Management: [Management]	
Project Communication: [Communication]		Project Stakeholder: [Stakeholder]	
Project Monitoring: [Monitoring]		Project Evaluation: [Evaluation]	
Project Reporting: [Reporting]		Project Review: [Review]	
Project Improvement: [Improvement]		Project Closure: [Closure]	

18/7/2024
B. M. [Signature]



1 Persp - Entry



2 Persp - from bridge



Two Rivers Community School, Mareeba
267 Mdiver Road, Mareeba QLD 4883 (access off Chewko Road)
Lot 71 on SP292140, 287,300sqm, Zoned Rural

@ A3
3D View from Entry
162 / A303
24/07/2023 15:11:30

Rev	Comments	Author	Date
1	Issued for the design team	ALW	24.07.2023
2	Revised for the design team	ALW	28.07.2023
3	Revised for the design team	ALW	02.08.2023
4	Revised for the design team	ALW	06.08.2023


Contact: Geoff Warrington 0406522, 0406522, geoff@lifedesign.net.au, www.lifedesign.net.au

Document Set: 162-000000
Version: 1, Version Date: 15/11/2023


18/7/2024
20.12.2024




4 Persp - Courtyard from Hall



1 Persp - Courtyard from North



2 Persp - Courtyard from South



3 Persp - Courtyard from Entry

LIFE | Two Rivers Community School, Mareeba
257 Midver Road, Mareeba QLD 4883 (access off Crewko Road)
Lot 71 on SP292140, 287,300sqm, Zoned Rural

Document Series: 488397
Version: 1, Version Date: 15/12/23

@ A3
3D Views - Internal courtyard
162 / A911
2407023 15/12/23

Item	Code	Notes	Issue	Date
1	2407023	Issue for Approval	1	15/12/23
2	2407023	Issue for Approval	2	15/12/23
3	2407023	Issue for Approval	3	15/12/23

Contact: 0488 989898, 0488 989898, 0488 989898

18/7/2024
B. [Signature]

Referral Agency Response

RA6-N



SARA reference: 2311-38006 SRA
Council reference: MCU/23/0012
Applicant reference: F22/31

30 May 2024

Chief Executive Officer
Mareeba Shire Council
PO Box 154
Mareeba QLD 4880
planning@msc.qld.gov.au

Attention: Carl Ewin

Dear Sir/Madam

SARA referral agency response

(Referral agency response given under section 56 of the *Planning Act 2016*)

The development application described below was confirmed as properly referred by the State Assessment and Referral Agency (SARA) on 21 December 2023.

Response

Outcome:	Referral agency response – with conditions
Date of response:	30 May 2024
Conditions:	The conditions in Attachment 1 must be attached to any development approval
Advice:	Advice to the applicant is in Attachment 2
Reasons:	The reasons for the referral agency response are in Attachment 3

Development details

Description:	Development permit	Material change of use - Educational Establishment
SARA role:	Referral agency	
SARA trigger:	Schedule 10, Part 3, Division 4, Table 3, Item 1 (10.3.4.3.1) of the Planning Regulation 2017 - Clearing native vegetation	

2311-38006 SRA

Schedule 10, Part 9, Division 4, Subdivision 1, Table 1, Item 1
(10.9.4.1.1.1) of the Planning Regulation 2017 - State transport
infrastructure thresholds

SARA reference: 2311-38006 SRA

Assessment manager: Mareeba Shire Council

Street address: 267 Mciver Road, Mareeba

Real property description: Lot 71 on SP292140

Applicant name: Two Rivers Community School C/- Freshwater Planning Pty Ltd

Applicant contact details: 17 Barron View Drive
Freshwater QLD 4870
freshwaterplanning@outlook.com

Human Rights Act 2019
considerations: A consideration of the 23 fundamental human rights protected under
the *Human Rights Act 2019* has been undertaken as part of this
decision. It has been determined that this decision does not limit
human rights.


Representations

An applicant may make representations to a concurrence agency, at any time before the application is decided, about changing a matter in the referral agency response (s.30 Development Assessment Rules). Copies of the relevant provisions are in Attachment 4.

A copy of this response has been sent to the applicant for their information.

For further information please contact Isley Peacey, Senior Planning Officer, on 4037 3202 or via email CairnsSARA@dsdipg.qld.gov.au who will be pleased to assist.

Yours sincerely



Brett Nancarrow
Manager (Planning)

cc Two Rivers Community School, freshwaterplanning@outlook.com

enc Attachment 1 - Referral agency conditions
Attachment 2 - Advice to the applicant
Attachment 3 - Reasons for referral agency response
Attachment 4 - Representations about a referral agency response provisions
Attachment 5 - Documents referenced in conditions

2311-38006 SRA

Attachment 1—Referral agency conditions

(Under section 58(1)(b)(i) of the *Planning Act 2016* the following conditions must be attached to any development approval relating to this application) (Copies of the documents referenced below are found at Attachment 5)

No.	Conditions	Condition timing
Material change of use – Educational Establishment		
10.3.4.3.1 – Native vegetation clearing - The chief executive administering the <i>Planning Act 2016</i> nominates the Director-General of the Department of Resources to be the enforcement authority for the development to which this development approval relates for the administration and enforcement of any matter relating to the following condition(s):		
1.	Clearing of vegetation must: (a) only occur within Area A(A1) and Area C(C1) as shown on the attached: (i) Vegetation Management Plan, prepared by Queensland Government, reference VMP 2311-38006 SRA, Sheet 1 of 1, version 1; and (ii) Attachment to Vegetation Management Plan VMP 2311-38006 SRA Derived Reference Points for GPS; (b) not exceed 3.314 hectares.	At all times
2.	Built infrastructure, other than for roads, tracks, fences and underground services, must not be established, constructed or located within Area C(C1) as shown on the attached: (i) Vegetation Management Plan, prepared by Queensland Government, reference VMP 2311-38006 SRA, Sheet 1 of 1, version 1; and (ii) Attachment to Vegetation Management Plan VMP 2311-38006 SRA Derived Reference Points for GPS.	At all times
3.	Any person(s) engaged or employed to carry out the clearing of vegetation under this development approval must be provided with a full copy of this development approval and must be made aware of the full extent of clearing authorised by this development approval.	Prior to clearing

No.	Conditions	Condition timing
Material change of use – Educational Establishment		
10.9.4.1.1.1– State transport infrastructure thresholds—The chief executive administering the <i>Planning Act 2016</i> nominates the Director-General of the Department of Transport and Main Roads to be the enforcement authority for the development to which this development approval relates for the administration and enforcement of any matter relating to the following condition(s):		
Stormwater management		
4.	(a) The stormwater management of the development must not cause a worsening to the operating performance of the railway corridor such that any works on the land must not: (i) create any new discharge points for stormwater runoff onto the railway corridor. (ii) concentrate or increase the velocity of flows to the railway corridor. (iii) interfere with and/or cause damage to the existing stormwater drainage on the railway corridor (iv) surcharge any existing culvert or drain on the railway corridor. (v) reduce the quality of stormwater discharge onto the railway	(a) At all times

2311-38006 SRA

	corridor.	
	<p>(b) Submit RPEQ certification, with supporting documentation, to the Program Delivery and Operations Unit, Far North Queensland Region (Far.North.Queensland.IDAS@tmr.qld.gov.au) within the Department of Transport and Main Roads, confirming that the development has been designed in accordance with part (a) of this condition.</p> <p>(c) Submit RPEQ certification, with supporting documentation, to the Program Delivery and Operations Unit, Far North Queensland Region (Far.North.Queensland.IDAS@tmr.qld.gov.au) within the Department of Transport and Main Roads, confirming that the development has been constructed in accordance with part (a) of this condition.</p>	<p>(b) Prior to obtaining development approval for operational work or building work, whichever occurs first, for the first stage</p> <p>(c) Within 20 business days of the completion of works, for the relevant stage</p>
Railway level crossing safety		
5.	<p>(a) The railway level crossing of the Mungana Branch Line at Chewko Road (ID: LXR_02336) must be upgraded to include the following:</p> <ul style="list-style-type: none"> (i) the road approaching the crossing is aligned to be perpendicular to the railway corridor between its intersection with Chewko Road and extending for at least 20m beyond the outer rail track (edge running rail) on the southern approach to the crossing. (ii) a road carriageway width at the level crossing that is at least 7.5m (2 x 3.75m traffic lanes), plus a 1.5m wide verge on both sides of the road. (iii) a sealed surface of asphaltic concrete, or similar material, which extends over the crossing and for a minimum distance of 10m from the outer rail track (edge running rail) on each road approach to the crossing, ensuring a maximum grade change of 6%, in accordance with the following standards: <ul style="list-style-type: none"> • 'Level crossings – Details of Sign Posting', prepared by Queensland Rail, dated 13/08/20, drawing number QR-C-S3394 and issue A. • 'Level crossings – Details of Private and Queensland Rail Maintenance Road Grading and Sign Posting', prepared by Queensland Rail, dated 13/08/20, drawing number QR-C-S3395 and issue A. • a RPEQ certified crossing foundation suitable for the proposed weight and volume of the maximum design vehicle. <p>(b) Provide written evidence from the railway manager to the Program Delivery and Operations Unit, Far North Queensland Region (Far.North.Queensland.IDAS@tmr.qld.gov.au) within the Department of Transport and Main Roads confirming that the development has been designed and constructed in accordance with part (a) of this condition.</p>	<p>(a) and (b) Prior to the commencement of operational work or building work, whichever occurs first</p>
6.	<p>(a) The railway level crossing of the Mungana Branch Line at Chewko Road (ID: LXR_02336) must be upgraded to include the following safety controls in accordance with AS1742.7:2016 <i>Manual of uniform traffic control devices, Part 7: Railway Crossings</i>, comprising the following for each road approach to the level crossing:</p> <ul style="list-style-type: none"> (i) a RX-2 assembly with R6-25 signage with two pipe posts in accordance with section 2.2.2 of AS1742.7:2016 <i>Manual of uniform traffic control devices, Part 7: Railway Crossings</i> and associated Queensland Rail's 'Standard Level 	<p>(a) and (c) Prior to the commencement of operational work or building work, whichever occurs first</p>

2311-38006 SRA

	<p>Crossings Traffic Signs for Private & QR Maintenance Level Crossings', dated 25/05/2005 and drawing number 2588;</p> <p>(ii) stop lines in accordance with section 3.3 and Figure 4.6 of AS1742.7:2016 <i>Manual of uniform traffic control devices, Part 7: Railway Crossings</i>;</p> <p>(iii) no-overtaking barrier line in accordance with Section 3.5 and Figure 4.6 of AS1742.7:2016 <i>Manual of uniform traffic control devices, Part 7: Railway Crossings</i>; and</p> <p>(iv) incident Reporting Signage (quoting crossing reference 2336) in accordance with 'Level Crossings – Incident Reporting Sign', prepared by Queensland Rail, dated 16/02/06, drawing number 2622 and Issue A</p> <p>(v) railway crossing advance warning signage on both Chewko Road approaches to the railway level crossing in accordance with Section 2.2.5 and Figure 4.10 of AS1742.7:2016 <i>Manual of uniform traffic control devices, Part 7: Railway Crossings</i></p> <p>(vi) railway crossing advance warning signage on the southern approach (Unnamed Road) to the railway level crossing in accordance with:</p> <ul style="list-style-type: none"> Section 2.2.5 and Figure 4.10 of AS1742.7:2016 <i>Manual of uniform traffic control devices, Part 7: Railway Crossings</i>; OR Figure 4.5 of AS1742.7:2016 <i>Manual of uniform traffic control devices, Part 7: Railway Crossings</i>. <p>(b) The existing safety controls at the railway level crossing of the Mungana Branch Line at Chewko Road (ID: LXR_02336) namely, the railway crossing stop assembly (RX-2) must be removed.</p> <p>(c) Provide written evidence from the railway manager to the Program Delivery and Operations Unit, Far North Queensland Region (Far.North.Queensland.IDAS@tnr.qld.gov.au) within the Department of Transport and Main Roads confirming that the development has been designed and constructed in accordance with part (a) and (b) of this condition.</p>	<p>(b) Following the completion of part (a) of this condition</p>
Public passenger transport		
7.	<p>(a) Provide a school bus setdown facility at the location shown on the Stage 1 Plan – Parking and Drop-off, prepared by Life Design, dated 24/07/2023, drawing number 162/A112 and issue 3 (as amended in red).</p> <p>(b) The school bus setdown facility must be in accordance with the <i>Disability Standards for Accessible Public Transport 2002</i> made under subsection 31(1) of the <i>Disability Discrimination Act 1992</i> and include the following components:</p> <p>(i) one (1) continuous bus zone with capacity to accommodate the setdown of 1 x single unit rigid bus of 14.5m in length in accordance with Section 5.6.3.1 and Table 5-7 of Chapter 5 of the <i>Public Transport Infrastructure Manual 2015</i>.</p> <p>(ii) bus zone line marking and bus zone signage at either end of the bus zone in accordance with AS1742.11 – <i>Manual of uniform traffic control devices, Part 11: Parking controls</i>.</p> <p>(iii) a waiting area with shelter, seats and a bin in accordance with P2.1 – P2.4, S2, Outcome 1, Table 2 of <i>Planning for Safe Transport Infrastructure at Schools</i>.</p>	<p>(a) and (b) Prior to the commencement of use for Stage 1</p>

2311-38008 SRA

8.	<p>(a) Provide a school bus setdown facility at the location shown on the Final Plan – Parking and Drop-off, prepared by Life Design, dated 24/07/2023, drawing number 162/A162 and issue 3 (as amended in red).</p> <p>(b) The school bus setdown facility must be in accordance with the <i>Disability Standards for Accessible Public Transport 2002</i> made under subsection 31(1) of the <i>Disability Discrimination Act 1992</i> and include the following components:</p> <ul style="list-style-type: none"> (i) one (1) continuous bus zone with capacity to accommodate the concurrent setdown of 3 x single unit rigid buses of 14.5m in length with independent operation in-between in accordance with Section 5.6.3.1 and Table 5-7 of Chapter 5 of the <i>Public Transport Infrastructure Manual 2015</i>. (ii) bus zone line marking and bus zone signage at either end of the bus zone in accordance with AS1742.11 – Manual of uniform traffic control devices, Part 11: Parking controls. (iii) a waiting area with shelter, seats and a bin in accordance with P2.1 – P2.4, S2, Outcome 1, Table 2 of <i>Planning for Safe Transport Infrastructure at Schools</i>. 	(a) and (b) Prior to the commencement of use for Stage 5
9.	<p>The property access and internal roadway shown on Masterplan 2041 School B&W, prepared by Life Design, dated 10/10/2023, drawing number 162/A041c and issue 6 (as amended in red) must be designed and constructed to be in accordance with the following to accommodate a single unit rigid bus of 14.5m in length:</p> <ul style="list-style-type: none"> (c) accommodate the swept path of a single unit rigid bus of 14.5m in length in accordance with Austroads Design Vehicles and Turning Path Templates; (d) include wayfinding signage to identify the separate vehicular routes to passenger loading zones, parking areas, exits and the like in accordance with the Queensland Manual of Uniform Traffic Control Devices, Part 2: Traffic Control Devices for General Use; and (e) provide priority movement to the 'bus route' over private vehicle routes by installing give way pavement marking and signage in accordance with sections 2.5 and 5.5.2 of Queensland Manual of Uniform Traffic Control Devices, Part 2: Traffic Control Devices for General Use. 	Prior to the commencement of use for the relevant stage
Pedestrian and cyclist access		
10.	<p>(a) Provide the external and internal pedestrian pathway network, generally in accordance with the Stage 1 Plan – Parking and Drop-off, prepared by Life Design, dated 24/07/2023, drawing number 162/A112 and issue 3 (as amended by SARA in red).</p> <p>(b) The active transport network in part (a) of this condition must be in accordance with Table 1: Active Transport and Schedule 1 of <i>Planning for Safe Transport Infrastructure at Schools</i>.</p>	(a) and (b) Prior to the commencement of use for the relevant stage

2311-38006 SRA

Attachment 2—Advice to the applicant and assessment manager

Advice to the applicant:

General advice	
1.	Terms and phrases used in this document are defined in the <i>Planning Act 2016</i> , its regulation or the State Development Assessment Provisions (SDAP) (version 3.0). If a word remains undefined it has its ordinary meaning.
Clearing of native vegetation	
2.	To request an electronic file of the GPS coordinates/Derived Reference Points contained in an Attachment of this decision notice, email a request to the Department of Resources at vegetation.support@resources.qld.gov.au include application reference 2311-38006 SRA.
Works on a railway corridor	
3.	<p>Pursuant to section 255 of the <i>Transport Infrastructure Act 1994</i>, the railway manager's written approval is required to carry out works in or on a railway corridor or otherwise interfere with the railway or its operations.</p> <p>All works in the railway corridor such as but not limited to pipeline crossings, service and utility connections and level crossing upgrades will require relevant approvals to be obtained from the railway manager such as a licence to enter and construct and a wayleave agreement. Please refer to Queensland Rail specification MD-20-173 – <i>Civil Non-Queensland Rail Underground Services in Queensland Rail Property</i>.</p> <p>Please note: The Department of Transport and Main Roads advise that the upgrades to the railway level crossing will be designed and constructed by the railway manager (Queensland Rail) or its approved contractor at the applicant's expense. The applicant is responsible for obtaining any necessary approvals, contract arrangements, and/or other agreements from the railway manager for the design and construction of the upgraded level crossing.</p> <p>You will also need to contact the railway manager to discuss available track closures to schedule the work, if approved.</p> <p>Please be advised that this referral agency response does not constitute an approval under section 255 of the <i>Transport Infrastructure Act 1994</i> and that such approvals need to be separately obtained from the railway manager.</p> <p>The applicant should contact the Queensland Rail property team at QRPropertyWayleaves@qr.com.au in relation to obtaining the necessary approvals.</p>

Advice to the Assessment Manager under section 56(3) of the *Planning Act 2016*:

General advice	
1.	<p>The railway level crossing of the Mungana Branch Line at Chewko Road (ID: LXR_02336) is a public level crossing and will need to be included within the Interface Agreement with Queensland Rail.</p> <p>Please contact Queensland Rail to discuss this - QRPropertyWayleaves@qr.com.au</p>

2311-38008 SRA

Attachment 3—Reasons for referral agency response

(Given under section 56(7) of the *Planning Act 2016*)

The reasons for the SARA's decision are:

The development complies with SDAP State code 6: Protection of state transport networks. Specifically, the development:

- Does not have an adverse impact on state transport infrastructure, public passenger transport infrastructure, active transport infrastructure and public passenger services
- Maintains the operating performance of the transport network;
- Ensures development enables safe and convenient access to public passenger transport
- does not create a safety hazard for users of state transport infrastructure or public passenger services
- does not result in a worsening of the physical condition or operating performance of the state transport network
- does not compromise the state's ability to cost-effectively construct, operate and maintain state transport infrastructure
- provides public passenger transport infrastructure to enable development to be serviced by public passenger transport;
- provides safe and direct access to public passenger transport infrastructure or active transport infrastructure, including access by cycling and walking.

The development complies with SDAP State code 16: Native vegetation clearing. Specifically, the development:

- clearing is minimised in order to conserve vegetation, avoid land degradation and loss of biodiversity, and maintain ecological processes;
- greenhouse gas contributions are minimised through continued ability for carbon sequestration processes to occur;
- adequate vegetation is maintained to sustainably manage the impacts of clearing on ecosystems and biodiversity, and avoids significant residual impacts upon MSES; and
- impacts on vegetation are minimised where avoidance is not possible.
- There are no notices requiring compliance, vegetation management requirements or legally secured offset areas within the development site.

Material used in the assessment of the application:

- the development application material and submitted plans
- *Planning Act 2016*
- *Planning Regulation 2017*
- the SDAP (version 3.0), as published by SARA
- the Development Assessment Rules
- SARA DA Mapping system
- State Planning Policy mapping system
- section 58 of the *Human Rights Act 2019*

Attachment 4—Representations about a referral agency response provisions

(page left intentionally blank)

2311-38008 SRA

Attachment 5—Documents referenced in conditions

(page left intentionally blank)

Development Assessment Rules—Representations about a referral agency response

The following provisions are those set out in sections 28 and 30 of the Development Assessment Rules¹ regarding representations about a referral agency response

Part 6: Changes to the application and referral agency responses

28 Concurrence agency changes its response or gives a late response

- 28.1. Despite part 2, a concurrence agency may, after its referral agency assessment period and any further period agreed ends, change its referral agency response or give a late referral agency response before the application is decided, subject to section 28.2 and 28.3.
- 28.2. A concurrence agency may change its referral agency response at any time before the application is decided if—
- (a) the change is in response to a change which the assessment manager is satisfied is a change under section 26.1; or
 - (b) the Minister has given the concurrence agency a direction under section 99 of the Act; or
 - (c) the applicant has given written agreement to the change to the referral agency response.²
- 28.3. A concurrence agency may give a late referral agency response before the application is decided, if the applicant has given written agreement to the late referral agency response.
- 28.4. If a concurrence agency proposes to change its referral agency response under section 28.2(a), the concurrence agency must—
- (a) give notice of its intention to change its referral agency response to the assessment manager and a copy to the applicant within 5 days of receiving notice of the change under section 25.1; and
 - (b) the concurrence agency has 10 days from the day of giving notice under paragraph (a), or a further period agreed between the applicant and the concurrence agency, to give an amended referral agency response to the assessment manager and a copy to the applicant.

¹ Pursuant to Section 68 of the *Planning Act 2016*


² In the instance an applicant has made representations to the concurrence agency under section 30, and the concurrence agency agrees to make the change included in the representations, section 28.2(c) is taken to have been satisfied.

Part 7: Miscellaneous

30 Representations about a referral agency response

- 30.1. An applicant may make representations to a concurrence agency at any time before the application is decided, about changing a matter in the referral agency response.³

³ An applicant may elect, under section 32, to stop the assessment manager's decision period in which to take this action. If a concurrence agency wishes to amend their response in relation to representations made under this section, they must do so in accordance with section 28.



**Attachment to Plan: 2311-38006 SRA
Derived Reference Points
Datum: GDA2020, Projection: MGA Zone 55**

Notes: Derived Reference Points are provided to assist in the location of area boundaries.
Responsibility for locating these boundaries lies solely with the landholder and delegated contractor(s).
Coordinates start at a point indicated on the accompany/ing plan and continue sequentially when sheets are not shown.

**PLANS AND DOCUMENTS
referred to in the REFERRAL
AGENCY RESPONSE**
SARA ref: 2311-38006 SRA
Date: 30 May 2024


Part ID	Unique ID	Easting	Northing	Part ID	Unique ID	Easting	Northing	Part ID	Unique ID	Easting	Northing
C1	1	32930	8117242	C1	61	32905	8117245	C1	121	329140	8117248
C1	2	329196	8117245	C1	62	329045	8117248	C1	122	329140	8117248
C1	3	329196	8117250	C1	63	329040	8117250	C1	123	329141	8117248
C1	4	329198	8117254	C1	64	329076	8117252	C1	124	329143	8117248
C1	5	329200	8117259	C1	65	329072	8117255	C1	125	329145	8117248
C1	6	329203	8117263	C1	66	329068	8117259	C1	126	329147	8117267
C1	7	329206	8117266	C1	67	329065	8117263	C1	127	329149	8117266
C1	8	329209	8117269	C1	68	329063	8117268	C1	128	329151	8117266
C1	9	329214	8117272	C1	69	329061	8117272	C1	129	329153	8117264
C1	10	329218	8117274	C1	70	329061	8117277	C1	130	329155	8117263
C1	11	329218	8117274	C1	71	329060	8117282	C1	131	329157	8117262
C1	12	329225	8117278	C1	72	329061	8117287	C1	132	329159	8117260
C1	13	329227	8117278	C1	73	329062	8117292	C1	133	329160	8117259
C1	14	329227	8117279	C1	74	329067	8117297	C1	134	329162	8117257
C1	15	329227	8117284	C1	75	329068	8117298	C1	135	329163	8117255
C1	16	329227	8117285	C1	76	329068	8117299	C1	136	329164	8117254
C1	17	329227	8117286	C1	77	329069	8117299	C1	137	329170	8117246
C1	18	329225	8117289	C1	78	329068	8117299	C1	138	329170	8117246
C1	19	329225	8117289	C1	79	329068	8117299	C1	139	329171	8117244
C1	20	329224	8117289	C1	80	329066	8117294	C1	140	329172	8117243
C1	21	329215	8117290	C1	81	329066	8117294	C1	141	329172	8117242
C1	22	329215	8117290	C1	82	329067	8117292	C1	142	329172	8117242
C1	23	329210	8117290	C1	83	329069	8117299	C1	143	329173	8117242
C1	24	329207	8117290	C1	84	329069	8117299	C1	144	329174	8117240
C1	25	329206	8117291	C1	85	329100	8117297	C1	145	329175	8117239
C1	26	329197	8117291	C1	86	329100	8117295	C1	146	329177	8117236
C1	27	329192	8117292	C1	87	329101	8117292	C1	147	329184	8117233
C1	28	329188	8117293	C1	88	329102	8117292	C1	148	329185	8117232
C1	29	329183	8117295	C1	89	329102	8117292	C1	149	329187	8117231
C1	30	329178	8117299	C1	90	329102	8117292	C1	150	329188	8117230
C1	31	329176	8117299	C1	91	329102	8117295	C1	151	329188	8117230
C1	32	329174	8117299	C1	92	329102	8117295	C1	152	329188	8117230
C1	33	329170	8117301	C1	93	329103	8117295	C1	153	329188	8117230
C1	34	329169	8117302	C1	94	329102	8117299	C1	154	329191	8117230
C1	35	329162	8117305	C1	95	329102	8117298	C1	155	329192	8117229
C1	36	329158	8117307	C1	96	329102	8117295	C1	156	329198	8117226
C1	37	329154	8117310	C1	97	329102	8117294	C1	157	329199	8117226
C1	38	329151	8117313	C1	98	329102	8117292	C1	158	329200	8117226
C1	39	329148	8117317	C1	99	329101	8117299	C1	159	329210	8117225
C1	40	329147	8117319	C1	100	329100	8117297	C1	160	329211	8117225
C1	41	329146	8117319	C1	101	329095	8117281	C1	161	329213	8117234
C1	42	329144	8117323	C1	102	329105	8117278	C1	162	329214	8117234
C1	43	329142	8117325	C1	103	329107	8117278	C1	163	329214	8117234
C1	44	329141	8117327	C1	104	329109	8117277	C1	164	329214	8117234
C1	45	329137	8117333	C1	105	329111	8117276	C1	165	329214	8117234
C1	46	329136	8117334	C1	106	329113	8117275	C1	166	329217	8117234
C1	47	329135	8117334	C1	107	329115	8117274	C1	167	329219	8117234
C1	48	329133	8117335	C1	108	329117	8117272	C1	168	329228	8117233
C1	49	329133	8117335	C1	109	329118	8117271	C1	169	329229	8117232
C1	50	329132	8117335	C1	110	329120	8117269	C1	170	329231	8117232
C1	51	329132	8117335	C1	111	329122	8117268	C1	171	329234	8117232
C1	52	329127	8117334	C1	112	329123	8117268	C1	172	329238	8117230
C1	53	329122	8117333	C1	113	329125	8117268	C1	173	329238	8117230
C1	54	329117	8117333	C1	114	329128	8117269	C1	174	329240	8117230
C1	55	329113	8117334	C1	115	329130	8117269	C1	175	329244	8117231
C1	56	329108	8117335	C1	116	329132	8117269	C1	176	329244	8117231
C1	57	329104	8117338	C1	117	329134	8117269	C1	177	329246	8117231
C1	58	329100	8117341	C1	118	329137	8117269	C1	178	329247	8117231
C1	59	329096	8117344	C1	119	329139	8117269	C1	179	329247	8117231
C1	60	329096	8117345	C1	120	329140	8117268	C1	180	329251	8117231

Attachment to Plan: 2311-38006 SRA
Derived Reference Points
Datum: GDA2020, Projection: MGA Zone 55

Notes: Derived Reference Points are provided to assist in the location of area boundaries.
Responsibility for locating these boundaries lies solely with the landholder and designated contractors.
Coordinates start at a point indicated on the accompanying plan and continue sequentially when labels are not shown.

PLANS AND DOCUMENTS
referred to in the REFERRAL
AGENCY RESPONSE
SARA ref: 2311-38006 SRA
Date: 30 May 2024

Part ID	Unique ID	Existing	Nothing	Part ID	Unique ID	Existing	Nothing	Part ID	Unique ID	Existing	Nothing
C1	181	329352	8117310	A1	241	329183	8117295				
C1	182	329353	8117308	A1	242	329188	8117293				
C1	183	329353	8117308	A1	243	329192	8117292				
C1	184	329353	8117308	A1	244	329197	8117291				
C1	185	329355	8117306	A1	245	329205	8117291				
C1	186	329356	8117305	A1	246	329207	8117290				
C1	187	329357	8117303	A1	247	329210	8117290				
C1	188	329358	8117301	A1	248	329215	8117290				
C1	189	329359	8117299	A1	249	329216	8117290				
C1	190	329360	8117295	A1	250	329224	8117289				
C1	191	329361	8117284	A1	251	329225	8117289				
C1	192	329361	8117292	A1	252	329225	8117288				
C1	193	329361	8117290	A1	253	329227	8117286				
C1	194	329362	8117288	A1	254	329227	8117285				
C1	195	329362	8117285	A1	255	329227	8117284				
C1	196	329362	8117283	A1	256	329227	8117278				
C1	197	329362	8117282	A1	257	329227	8117278				
C1	198	329361	8117275	A1	258	329226	8117278				
C1	199	329361	8117274	A1	259	329218	8117274				
C1	200	329360	8117271	A1	260	329218	8117274				
C1	201	329360	8117269	A1	261	329214	8117272				
C1	202	329359	8117267	A1	262	329209	8117269				
C1	203	329358	8117265	A1	263	329206	8117266				
C1	204	329357	8117263	A1	264	329203	8117263				
C1	205	329356	8117261	A1	265	329200	8117259				
C1	206	329355	8117259	A1	266	329199	8117254				
C1	207	329354	8117257	A1	267	329195	8117250				
C1	208	329352	8117255	A1	268	329195	8117245				
C1	209	329351	8117254	A1	269	329189	8117259				
C1	210	329349	8117252	A1	270	329068	8117411				
C1	211	329348	8117251	A1	271	329068	8117411				
C1	212	329346	8117249	A1	272	329068	8117409				
C1	213	329344	8117248	A1	273	329068	8117409				
C1	214	329342	8117247	A1	274	329068	8117408				
C1	215	329341	8117247	A1	275	329067	8117407				
C1	216	329333	8117243	A1	276	329062	8117282				
C1	217	329331	8117242	A1	277	329061	8117387				
C1	218	329330	8117242	A1	278	329060	8117382				
A1	219	329132	8117335	A1	279	329061	8117377				
A1	220	329132	8117335	A1	280	329061	8117372				
A1	221	329133	8117335	A1	281	329063	8117368				
A1	222	329133	8117335	A1	282	329065	8117363				
A1	223	329136	8117334	A1	283	329068	8117359				
A1	224	329136	8117334	A1	284	329072	8117355				
A1	225	329137	8117333	A1	285	329076	8117352				
A1	226	329141	8117327	A1	286	329080	8117350				
A1	227	329142	8117326	A1	287	329085	8117348				
A1	228	329144	8117323	A1	288	329095	8117345				
A1	229	329146	8117319	A1	289	329096	8117345				
A1	230	329147	8117319	A1	290	329096	8117344				
A1	231	329148	8117317	A1	291	329100	8117341				
A1	232	329151	8117313	A1	292	329104	8117338				
A1	233	329154	8117310	A1	293	329108	8117336				
A1	234	329158	8117307	A1	294	329113	8117334				
A1	235	329162	8117305	A1	295	329117	8117331				
A1	236	329169	8117302	A1	296	329122	8117333				
A1	237	329170	8117301	A1	297	329127	8117334				
A1	238	329174	8117299	A1	298	329132	8117335				
A1	239	329176	8117299								
A1	240	329178	8117299								




TRACK RADIUS (m)	X (mm)
STRAIGHT TRACK	1650
RADIUS = 1200m	1650
RADIUS = 800m & R = 1200m	1700
RADIUS = 600m & R = 800m	1750
RADIUS = 400m & R = 600m	1800
RADIUS = 200m & R = 400m	1845
RADIUS = 150m	1900

The diagram illustrates the track geometry and road grade. It shows a cross-section of a track with a top rail and a bottom rail. The track width is indicated as 40mm MAX. and 30mm MAX. The road grade is shown rising relative to the line of rails. The distance from the center of the track to the line of rails is labeled as X. The diagram also shows a 302mm dimension from the bottom rail to the line of rails.

NOT TO SCALE


ADDITIONAL GRADING RESTRICTIONS APPLY
WITHIN PATH SWEEP BY ROLLINGSTOCK
REFER TO ABOVE TABLE AND DIAGRAM




ROAD GRADING LIMITS AT LEVEL CROSSINGS
(TO PROVIDE UNDERBODY CLEARANCE FOR ROLLING STOCK AND ROAD VEHICLES)
SCALE 1:100

NOTE:
A CHANGE IN GRADE FROM THESE POINTS SHALL BE BY VERTICAL CURVE. THE RADIUS AND LENGTH SHALL BE DETERMINED BY DESIGN SPEED AND OTHER RELEVANT CRITERIA AS REQUIRED BY THE MAIN ROADS DEPARTMENT PLANNING AND DESIGN MANUAL AND AUSTRROADS PUBLICATIONS FOR THE DESIGN VEHICLE (ARTICULATED VEHICLE - LOW LOADER, UNLESS OTHERWISE APPROVED BY THE CIVIL MANAGER.


NOTE:
SPECIAL PURPOSE VEHICLE OUTSIDE
THESE PARAMETERS SHALL BE SUBMITTED
TO THE MANAGER CIVIL ENGINEERING FOR
ASSESSMENT



DESIGN VEHICLE
(ARTICULATED VEHICLE LOW LOADER)
SCALE 1:120




TYPICAL DRAINAGE SECTION
SCALE 1:50



SECTION

TYPICAL DETAIL OF SIGN POSTING AT
VEHICULARLY PROTECTED PRIVATE LEVEL CROSSING
& UNFENCED PRIVATE CROSSINGS.



ELEVATION - ROADWAY APPROACH

WIDTH MARKER ASSEMBLY RX-4 REQUIRED EITHER SIDE OF CROSSING IN ADDITION TO "RAILWAY CROSSING" SIGNS. REFER MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, PART 7, REFERENCE CLAUSE 2.4.2 FOR FURTHER DETAILS.

GENERAL NOTES:


1. PROPOSED LEVEL CROSSING SHALL BE SUBMITTED TO THE MANAGER CIVIL ENGINEERING FOR APPROVAL.
2. REFER CR-C-53354 FOR PLAN OF TYPICAL LEVEL CROSSINGS.
3. RESPONSIBILITIES FOR PRIVATE AND QUEENSLAND RAIL MAINTENANCE CROSSINGS ARE DETAILED IN LEVEL CROSSING SAFETY STANDARD MC-014115.
4. ROAD PAVEMENT SHALL BE 200MM MIN. COMPACTED UNBOUND ROAD BASE, BALLAST SHALL NOT BE USED AND SEALED WITH ASPHALT, 150MM ON BOTH SIDES.
5. ANY RELAXATION OF THE ROAD CROSSING LIMITS SHOWN WILL REQUIRE APPROVAL FROM THE CIVIL MANAGER ENGINEERING.
6. A CHANGE IN GRADE FROM THESE POINTS SHALL BE VERTICAL CURVE THE RADII AND LENGTH OF CURVE SHALL BE DETERMINED BY DESIGN SPEED AND OTHER RELEVANT CRITERIA AS REQUIRED BY THE MAIN ROADS DEPARTMENT PLANNING AND DESIGN MANUAL AND AUSTRADDS STANDARDS FOR THE DESIGNATION OF GRADES AND GRADE-LOW LOADER, UNLESS OTHERWISE APPROVED BY THE MANAGER CIVIL ENGINEERING.
7. DRAINAGE REQUIREMENTS TO BE DETERMINED AT THE SITE BY THE ENGINEER, AND CATCH DRAIN IS REQUIRED, NOT TO BE CONSTRUCTED CLOSER THAN 4M TO EDGE OF PAVEMENT.
8. THIS DRAWING SUPERSEDES QUEENSLAND RAIL STANDARD DRAWING NO. 2586 AND 2587.
9. FOR REMOVAL OF LEVEL CROSSING REFER TO QUEENSLAND RAIL STANDARD DRAWING NO. 2623.
10. THIS DRAWING DOES NOT COVER SIGNAL AND OPERATIONAL SYSTEM REQUIREMENTS, ADVICE IS TO BE SOUGHT FROM THE SIGNALING MANAGER.


PLANS AND DOCUMENTS
referred to in the REFERRAL
AGENCY RESPONSE


SARA ref: 2311-38006 SRA

Date: 30 May 2024



#/F No		ALTERATIONS						SCALE 1:500		Network - Civil Engineering		DRAWING NUMBER	ISSU
2078658	AS	ORIGINAL	DATE	BY	CHKD	APP'D	DESIGNED BY SCALE 1:100	APPROVED D. SUDHATHA 15/04/2017	 ACN 132 181 090	STANDARD LEVEL CROSSING	DETAILS OF PRIVATE AND QUEENSLAND RAIL MAINTENANCE ROAD GRADING AND SIGN POSTING	QR-C-S3395	A
	AS	ORIGINAL	DATE	BY	CHKD	APP'D	DESIGNED BY SCALE 1:170	APPROVED D. SUDHATHA 15/04/2017					
	AS	ORIGINAL	DATE	BY	CHKD	APP'D	DESIGNED BY SCALE 1:2250	APPROVED D. SUDHATHA 15/04/2017					
	AS	ORIGINAL	DATE	BY	CHKD	APP'D	DESIGNED BY SCALE 1:2250	APPROVED D. SUDHATHA 15/04/2017					
SCALES SHOWN AND FOR AN AT SIZE ORIGINAL CHECKED													





PLAN
SCALE 1:10

NOTE: CONTROL MEASURES AT CROSSING WILL HAVE IMPACT ON ROAD CROSSING SIGN ASSIGNMENT

INCIDENT REPORTING SIGN

CROSSING REMAINS ON ROAD SIDE

INCIDENT REPORTING SIGN

NOTE: CONTROL MEASURES AT CROSSING WILL HAVE IMPACT ON ROAD CROSSING SIGN ASSIGNMENT


INCIDENT REPORTING SIGN

CROSSING REMAINS ON ROAD SIDE

PLANS AND DOCUMENTS referred to in the REFERRAL AGENCY RESPONSE

SARA ref: 2311-38006 SRA

Date: 30 May 2024



TYPICAL CROSS SECTION
SCALE 1:10

INCIDENT REPORTING SIGN TO BE PLACED ON THE BACK OF SIGN ON THE SIDE OF ROAD (SHOULDER) PRIOR TO CROSSING


NOTE: CONTROL MEASURES AT CROSSING WILL HAVE IMPACT ON ROAD CROSSING SIGN ASSIGNMENT

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN TO BE PLACED ON THE BACK OF SIGN ON THE SIDE OF ROAD (SHOULDER) PRIOR TO CROSSING

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN TO BE PLACED ON THE BACK OF SIGN ON THE SIDE OF ROAD (SHOULDER) PRIOR TO CROSSING




TYPICAL INSTALLATION DETAIL
SCALE 1:10

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN



TYPICAL INSTALLATION DETAIL
SCALE 1:10

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN DETAIL
SCALE 1:10

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN

INCIDENT REPORTING SIGN

GENERAL NOTES:

- ALL SIGNPOSTS ARE IN COMPLIANCE WITH THE SIGNPOSTS ACT 1994.
- CONTACT MANAGED TRACK AND RAIL SYSTEMS FOR ALLOCATION OF SIGNPOSTS TO TRACKS. SIGNPOSTS SHALL BE PLACED TO THE LEFT AND RIGHT OF THE TRACKS.
- WHILE THE SIGNPOSTS ARE IN PLACE, THE SIGNPOSTS SHALL BE PLACED TO THE LEFT AND RIGHT OF THE TRACKS.
- THE SIGNPOSTS SHALL BE PLACED TO THE LEFT AND RIGHT OF THE TRACKS.

NOTE

THE PURPOSE OF THIS DRAWING IS TO PROVIDE TYPICAL STANDARD DETAILS. THE SUITABILITY OF THIS DRAWING SHALL BE DETERMINED AND CERTIFIED BY A ROPS ENGINEER FOR THE SPECIFIC PROJECT.

ALTERATIONS

NO.	DATE	BY	DESCRIPTION
1	2023/05/30	CT	ISSUED FOR COMMENT
2	2023/05/30	CT	ISSUED FOR COMMENT
3	2023/05/30	CT	ISSUED FOR COMMENT
4	2023/05/30	CT	ISSUED FOR COMMENT
5	2023/05/30	CT	ISSUED FOR COMMENT
6	2023/05/30	CT	ISSUED FOR COMMENT
7	2023/05/30	CT	ISSUED FOR COMMENT
8	2023/05/30	CT	ISSUED FOR COMMENT
9	2023/05/30	CT	ISSUED FOR COMMENT
10	2023/05/30	CT	ISSUED FOR COMMENT

QUEENSLAND RAIL - CIVIL ENGINEERING

STANDARD

LEVEL CROSSINGS

INCIDENT REPORTING SIGN

RLS: CT-2008.1

DRAWING NUMBER: 2622

SCALE: A


© QUEENSLAND RAIL, CIVIL ENGINEERING

COPIRIGHT NOTED BY THIS PUBLICATION. EXCEPT FOR PURPOSES PERMITTED BY THE COPYRIGHT ACT, REPRODUCTION BY WHATEVER MEANS IS PROHIBITED WITHOUT THE WRITTEN PERMISSION OF QRL. ENGINEERS SHOULD BE ADVISED BY QRL, ENGINEERING, 24, SPE RICE WAY, MARREEBA VIC 3267.

SCALES SHOWN ARE FOR AN A1 SIZE ORIGINAL DRAWING

DRAWING NUMBER: 2622

SCALE: A




Two Rivers Community School, Mareeba
267 McIver Road, Mareeba QLD 4883 (access off Chewko Road)
Lot 71 on SP292140, 287,300sqm, Zoned Rural

1 : 1250 @ A3
Masterplan 2041 School B&W
162 / A041c
10/10/2023 15:36:19

6	Updated Civil and Street	10/10/2023
5	Updated Parking Layout	24/01/2023
4	Revised Access Point	20/01/2023
3	Updated Drains with New Road	18/01/2023
2	Updated for Review	12/01/2022
1	Updated with Survey Data	14/01/2022
Issue	Details	Date

Contact: Stuart Warrington 0404-5335, 0493 936 716, stuart@lifedesign.net.au www.lifedesign.net.au




Two Rivers Community School, Mareeba
267 McIver Road, Mareeba QLD 4883 (access off Chewko Road)
Lot 71 on SP292140, 287,300sqm, Zoned Rural

1 : 500 @ A3
Stage 1 Plan - Parking and Drop-off
162 / A112
24/07/2023 15:09:00

Item	Details	Drawn	Check
3	Approved Parking Layout	SSW	24/07/2023
2	Revised Access Point	SSW	25/07/2023
1	Parking Layouts	SSW	25/07/2023

Contact: Stuart Withington 04045335, 0499 906 716, stuart@lifedesign.net.au, www.lifedesign.net.au



PLANS AND DOCUMENTS
referred to in the REFERRAL
AGENCY RESPONSE

SARA ref: 2311-38006 SRA
Date: 30 May 2024



Provide bus setdown
facility in accordance
with the conditions of
the SARA Referral
Agency Response

Amended in red by SARA on
30 May 2024



Two Rivers Community School, Mareeba
267 McIver Road, Mareeba QLD 4883 (access off Chewko Road)
Lot 71 on SP292140, 287,300sqm, Zoned Rural

1 : 500 @ A3
Final Plan - Parking and Drop-off

162 / A162
24/07/2023 15:09:26

3	Location Parking Layout	SWW	24/07/2023
2	Revised Access Point	SWW	24/07/2023
1	Parking Layout	SWW	24/07/2023
	Drawn	Drawn	Drawn

Contact: Stuart Wittington 0404-5335, 0489 906 716, stuart@lifedesign.com.au, www.lifedesign.com.au

Appeal Rights

PLANNING ACT 2016 & THE PLANNING REGULATION 2017

Chapter 6 Dispute resolution

Part 1 Appeal rights

229 Appeals to tribunal or P&E Court

- (1) Schedule 1 of the Planning Act 2016 states –
- (a) Matters that may be appealed to –
 - (i) either a tribunal or the P&E Court; or
 - (ii) only a tribunal; or
 - (iii) only the P&E Court; and
 - (b) The person-
 - (i) who may appeal a matter (**the appellant**); and
 - (ii) who is a respondent in an appeal of the matter; and
 - (iii) who is a co-respondent in an appeal of the matter; and
 - (iv) who may elect to be a co-respondent in an appeal of the matter.

(Refer to Schedule 1 of the Planning Act 2016)

- (2) An appellant may start an appeal within the appeal period.
- (3) The **appeal period** is –
- (a) for an appeal by a building advisory agency – 10 business days after a decision notice for the decision is given to the agency; or
 - (b) for an appeal against a deemed refusal – at any time after the deemed refusal happens; or
 - (c) for an appeal against a decision of the Minister, under chapter 7, part 4, to register premises or to renew the registration of premises – 20 business days after a notice is published under section 269(3)(a) or (4); or
 - (d) for an appeal against an infrastructure charges notice – 20 business days after the infrastructure charges notice is given to the person; or
 - (e) for an appeal about a deemed approval of a development application for which a decision notice has not been given – 30 business days after the applicant gives the deemed approval notice to the assessment manager; or
 - (f) for any other appeal – 20 business days after a notice of the decision for the matter, including an enforcement notice, is given to the person.

Note –

See the P&E Court Act for the court's power to extend the appeal period.

- (4) Each respondent and co-respondent for an appeal may be heard in the appeal.
- (5) If an appeal is only about a referral agency's response, the assessment manager may apply to the tribunal or P&E Court to withdraw from the appeal.
- (6) To remove any doubt. It is declared that an appeal against an infrastructure charges notice must not be about-

- (a) the adopted charge itself; or
- (b) for a decision about an offset or refund-
 - (i) the establishment cost of trunk infrastructure identified in a LGIP; or
 - (ii) the cost of infrastructure decided using the method included in the local government's charges resolution.

230 Notice of appeal

- (1) An appellant starts an appeal by lodging, with the registrar of the tribunal or P&E Court, a notice of appeal that-
 - (a) is in the approved form; and
 - (b) succinctly states the grounds of the appeal.
- (2) The notice of appeal must be accompanied by the required fee.
- (3) The appellant or, for an appeal to a tribunal, the registrar must, within the service period, give a copy of the notice of appeal to –
 - (a) the respondent for the appeal ; and
 - (b) each co-respondent for the appeal; and
 - (c) for an appeal about a development application under schedule 1, table 1, item 1 – each principal submitter for the development application; and
 - (d) for an appeal about a change application under schedule 1, table 1, item 2 – each principal submitter for the change application; and
 - (e) each person who may elect to become a co-respondent for the appeal, other than an eligible submitter who is not a principal submitter in an appeal under paragraph (c) or (d); and
 - (f) for an appeal to the P&E Court – the chief executive; and
 - (g) for an appeal to a tribunal under another Act – any other person who the registrar considers appropriate.
- (4) The *service period* is –
 - (a) if a submitter or advice agency started the appeal in the P&E Court – 2 business days after the appeal has started; or
 - (b) otherwise – 10 business days after the appeal is started.
- (5) A notice of appeal given to a person who may elect to be a co-respondent must state the effect of subsection (6).
- (6) A person elects to be a co-respondent by filing a notice of election, in the approved form, within 10 business days after the notice of appeal is given to the person.

231 Other appeals

- (1) Subject to this chapter, schedule 1 and the P&E Court Act, unless the Supreme Court decides a decision or other matter under this Act is affected by jurisdictional error, the decision or matter is non-appealable.
- (2) The *Judicial Review Act 1991*, part 5 applies to the decision or matter to the extent it is affected by jurisdictional error.
- (3) A person who, but for subsection (1) could have made an application under the *Judicial Review Act 1991* in relation to the decision or matter, may apply under part 4 of that Act for a statement of reasons in relation to the decision or matter.
- (4) In this section –
 - decision* includes-
 - (a) conduct engaged in for the purpose of making a decision; and

- (b) other conduct that relates to the making of a decision; and
- (c) the making of a decision or failure to make a decision; and
- (d) a purported decision ; and
- (e) a deemed refusal.

non-appealable, for a decision or matter, means the decision or matter-

- (a) is final and conclusive; and
- (b) may not be challenged, appealed against, reviewed, quashed, set aside or called into question in any other way under the Judicial Review Act 1991 or otherwise, whether by the Supreme Court, another court, a tribunal or another entity; and
- (c) is not subject to any declaratory, injunctive or other order of the Supreme Court, another court, a tribunal or another entity on any ground.

232 Rules of the P&E Court

- (1) A person who is appealing to the P&E Court must comply with the rules of the court that apply to the appeal.
- (2) However, the P&E Court may hear and decide an appeal even if the person has not complied with the rules of the P&E Court.