Your Ref:

Our Ref: F24/20 OPW

27 February, 2025

Chief Executive Officer Mareeba Shire Council PO Box 154 MAREEBA QLD 4880 RESHWATER

Attention: Carl Ewin Planning Services

Dear Sir,

RE: APPLICATION FOR OPERATIONAL WORKS – WYLANDRA ESTATE STAGE 1 LOT 224 ON SP276715, 446 RAY ROAD, MAREEBA.

This application is for an Operational Works Application over land described as Lot 224 on SP276715, situated at 446 Ray Road, Mareeba is submitted on behalf of Wylandra Properties Pty Ltd the owner of the site.

The application comprises of Application Form, Engineering Drawings, Operational Works Design Report, and this Town Planning Letter. It is understood that the proponent will provide payment of the Application Fee with the Mareeba Shire Council.


All required information is understood to be provided on the Engineering Drawings and Operational Works Design Report which are attached and can be provided over the counter by a Representative of Wylandra Properties Pty Ltd or ERSCON Consulting Engineers, if required. If you have any queries or require any further information, please do not hesitate to contact Freshwater Planning Pty Ltd.

Yours faithfully,

MATTHEW ANDREJIC

FRESHWATER PLANNING PTY LTD

CONMAT PTY. LTD. WYLANDRA ESTATE STAGE 1



Client:





PROJECT DRAWINGS LIST

-	
160-010-C101	COVER SHEET, LOCALITY PLAN AND DRAWINGS LIST
160-010-C102	GENERAL NOTES
160-010-C103	EXISTING LOT LAYOUT
160-010-C104	GENERAL LOT LAYOUT (SHEET 1 OF 2)
160-010-C105	GENERAL LOT LAYOUT (SHEET 2 OF 2)
160-010-C106	ROAD 1 LONGITUDINAL SECTION (SHEET 1 OF 2)
160-010-C107	ROAD 2 AND 3 LONGITUDINAL SECTION (SHEET 2 OF 2)
160-010-C108	TYPICAL ROAD CROSS SECTION AND DETAILS
160-010-C109	INTERSECTION SETOUT
160-010-C110	GRADING PLAN (SHEET 1 OF 2)
160-010-C111	GRADING PLAN (SHEET 2 OF 2)
160-010-C112	WATER RETICULATION PLAN (SHEET 1 OF 2)
160-010-C113	WATER RETICULATION PLAN (SHEET 2 OF 2)
160-010-C114	STORMWATER Q5 MINOR AND DRAINAGE PLAN (SHEET 1 OF 2)
160-010-C115	STORMWATER Q5 MINOR AND DRAINAGE PLAN (SHEET 2 OF 2)
160-010-C116	DRAIN LONGITUDINAL SECTION
160-010-C117	STORMWATER Q5 MINOR LONGITUDINAL SECTION
160-010-C118	EROSION SEDIMENT CONTROL PLAN (SHEET 1 OF 2)
160-010-C119	EROSION SEDIMENT CONTROL PLAN (SHEET 2 OF 2)
160-010-C120	EROSION AND SEDIMENT CONTROL NOTES
160-010-C121	ROAD 1 CROSS SECTIONS
160-010-C122	ROAD 2 AND 3 CROSS SECTIONS
160-010-C123	DRAIN 1 CROSS SECTION
160-010-C124	DRAIN 2 CROSS SECTION
160-010-C125	DRAIN 3 CROSS SECTION
160-010-C126	DETENTION BASIN PLAN
160-010-C127	DETENTION BASIN LONGITUDINAL SECTION
160-010-C128	DETENTION BASIN CROSS SECTIONS (SHEET 1 OF 2)
160-010-C129	DETENTION BASIN CROSS SECTIONS (SHEET 2 OF 2)

	•	· · · · · · · · · · · · · · · · · · ·		
NUMBER	EASTING	NORTHING	RL	LOCATION
PSM108764	332745.510	8113612.180	458.532	WYLANDRA DRIVE, MAREEBA

- EXISTING CONDITIONS HAVE BEEN BASED ON SURVEY DATA COLLECTED BY TWINE SURVEYORS NO RESPONSIBILITY IS TAKEN FOR THE ACCURACY OF THE INFORMATION SHOWN.
- 4. THE CONTRACTOR IS TO LIAISE WITH TWINE SURVEYS TO ESTABLISH SITE SURVEY CONTROLS.
 5. DETAILS OF SERVICES ARE PROVIDED FOR INFORMATION ONLY, AND NO RESPONSIBILITY IS TAKEN FOR THE ACCURACY AND COMPLETENESS OF THE INFORMATION. POSITIONS OF SERVICE CROSSINGS SHALL BE RECORDED AND CHECKED BY THE CONTRACTOR, NOT ALL CROSSINGS HAVE NECESSARILY BEEN SHOWN ON THE DRAWINGS. THE CONTRACTOR IS TO CHECK SERVICES ON SITE PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- 6. FOR ALL SPECIFICATIONS REFER TO FNQROC STANDARD SPECIFICATIONS.
- 7. INSPECTION AND TEST PLANS ARE TO BE UNDERTAKEN BY CONTRACTOR IN ACCORDANCE WITH FNOROC DEVELOPMENT MANUAL.

 8. AS CONSTRUCTED DATA TO BE PREPARED AND SUBMITTED BY THE CONTRACTOR IN ACCORDANCE
- WITH FNQROC DEVELOPMENT MANUAL.

EARTHWORKS NOTES:

- 1. ALL EARTHWORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT FNQROC DEVELOPMENT MANUAL SPECIFICATION - S1 'EARTHWORKS'.
- FNQROC SPECIFICALLY REFERENCES AS 3798 'GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS' IN RELATION TO ALL EARTHWORK OPERATIONS INCLUDING APPROPRIATE METHODS OF TESTING, FREQUENCY OF TESTING AND REPORTING PROCEDURES. GEOTECHNICAL TESTING SERVICES SHALL BE AS DETERMINED BY LEVEL 1 IN ACCORDANCE WITH AS 3798. ALL CERTIFICATION AND TEST RESULTS ARE TO BE COMPILED AND PROVIDED TO THE SUPERINTENDENT PRIOR TO WORKS ACCEPTANCE.
- ALL BATTERS SHALL BE 1 IN 3 MAX UNLESS NOTED OTHERWISE ON THE PROJECT DRAWINGS.
- FINISHED SURFACE LEVELS SHOWN ON PROJECT DRAWINGS ARE AFTER ALL EARTHWORKS ARE COMPLETE INCLUDING TOPSOILING. ALL AREAS ARE TO BE GRADED EVENLY BETWEEN FINISHED
- COMPLETE INCLUDING TOPSOILING, ALL AREAS ARE TO BE GRADED EVENLY BETWEEN FINISHED SURFACE LEVELS UNLESS NOTED OTHERWISE.

 DRY DENSITY RATIO AS REFERRED TO IN THESE NOTES IS THE RATIO DETERMINED IN ACCORDANCE WITH AS1289.5.4.1 OF COMPACTED DRY DENSITY IN ACCORDANCE WITH AS1289.5.8.1 TO THE STANDARD MAXIMUM DRY DENSITY DETERMINED IN ACCORDANCE WITH AS1259.5.1.11 (STANDARD COMPACTION).
- NO VEGETATION SHALL BE REMOVED WITHOUT PRIOR APPROVAL OF THE SUPERINTENDENT UNLESS NOTED ON THE PROJECT DRAWINGS.
- ALL VEGETAL MATTER, TOPSOIL AND OTHER UNSUITABLE MATERIAL SHALL BE STRIPPED/REMOVED FROM AREAS TO BE EXCAVATED OR FILLED. ALL VEGETAL MATTER AND UNSUITABLE MATERIAL SHALL BE DISPOSE OF OFF-SITE UNLESS ADVISED OTHERWISE BY THE SUPERINTENDENT. TOPSOIL SHALL BE STOCKPILED ON-SITE FOR REUSE. SURPLUS TOPSOIL SHALL BE DISPOSED OF OFF-SITE.
- SHOULD ANY SOFT OR UNSUITABLE MATERIAL BE IDENTIFIED, THE CONTRACTOR SHALL INFORM
- THE SUPERINTENDENT IMMEDIATELY AND SEEK THE ADVICE OF THE SUPERINTENDENT OR GITA. COMPACT FILL TO 95% DRY DENSITY RATIO IN LAYERS OF THICKNESS APPROPRIATE TO THE COMPACTION PLANT EMPLOYED BT NOT EXCEEDING 300mm.

 10. ROAD VERGE SHALL BE FULLY TURFED ON COMPLETION OF TOPSOILING. ELSEWHERE, DISTURBED
- AREAS 1:3 OR FLATTER SHALL BE GRASS SEEDED AND AREAS STEEPER THAN 1:3 SHALL BE HYDROMULCHED (UNLESS NOTED OTHERWISE).

CONCRETE NOTES:

1. ALL CONCRETE WORKS INCLUDING SUPPLY, PLACEMENT, COMPACTION, REINFORCEMENT AND FINISHING SHALL BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT FNQROC DEVELOPMENT MANUAL SPECIFICATION - S7 CONCRETE WORKS

DRAINAGE NOTES:

- ALL STORMWATER DRAINAGE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT FNQROC DEVELOPMENT MANUAL SPECIFICATION S4 'STORMWATER DRAINAGE'.
 ALL REINFORCED CONCRETE PIPES SHALL BE CLASS 2 UNLESS NOTED OTHERWISE. ALTERNATIVE MATERIAL TYPES SUCH AS HDPE OR FRC MAY BE USED SUBJECT TO SUPERINTENDENTS/COUNCIL APPROVAL.
- ALL PVC PIPES SHALL BE CLASS SN4 MINIMUM SWJ UNLESS NOTED OTHERWISE.
- EXCAVATION, BEDDING AND BACKFILL FOR CONCRETE PIPES SHALL BE CARRIED OUT IN ACCORDANCE WITH FNQROC STANDARD DRAWING \$1046.
- EXCAVATION, BEDDING AND BACKFILL FOR PVC PIPES TO BE IN ACCORDANCE WITH AS/NZS 2566,2 "BURIED FLEXIBLE PIPES - PART 2 INSTALLATION"
- ALL KERB INLET PITS TO BE CONSTRUCTED IN ACCORDANCE WITH FNQROC STD DRG'S \$1050
- 7. ALL PRECAST HEADWALLS SHALL BE PROVIDED WITH A CUT-OFF WALL IN ACCORDANCE WITH

EROSION AND SEDIMENT CONTROL NOTES:

- PRIOR TO CONSTRUCTION COMMENCING, THE CONTRACTOR MUST PREPARE AN EROSION & SEDIMENT CONTROL PLAN (ESCP) TO MANAGE THE SITE DURING CONSTRUCTION AND THE
- THE ESCP MUST BE CONSISTENT WITH THE APPROVED EROSION & SEDIMENT CONTROL STRATEGY (ESCS) AND SHALL TAKE INTO CONSIDERATION THE CONTRACTOR'S PROPOSED
- STRATEGY (ESCS) AND SHALL TAKE INTO CONSIDERATION THE CONTRACTOR'S PROPOSED CONSTRUCTION METHODOLOGY AND PROGRAM.

 AN ESCP THAT DIFFERS TO THE APPROVED ESCS MUST BE SUBMITTED TO THE SUPERINTENDENT FOR APPROVAL PRIOR TO SUBMITTING TO COUNCIL.

 NO EARTHWORKS SHALL COMMENCE ON ANY PART OF THE SITE PRIOR TO APPROPRIATE
- EROSION AND SEDIMENT CONTROL MEASURES BEING INSTALLED DOWNSTREAM OF THE SITE
- AND IN ACCORDANCE WITH THE APPROVED ESCP.
 AT ALL TIMES THE CONTRACTOR SHALL MONITOR THE PREVAILING WEATHER CONDITIONS AND
 TAKE ALL NECESSARY PRECAUTIONS TO CONTROL EROSION AND DOWNSTREAM SEDIMENTATION DURING ALL STAGES OF CONSTRUCTION.
- THE IMPACT ON THE ENVIRONMENT SHALL BE MINIMISED BY OBSERVING THE FOLLOWING CONSTRUCTION PRACTICES:
 - AREAS DISTURBED BY CONSTRUCTION TRAFFIC AND PROCEDURES SHALL BE MINIMISED.
 - MINIMISE TRAFFIC MOVEMENTS AND SPEEDS ON EXPOSED SURFACES.
 - · REVEGETATION OF DISTURBED AREAS SHALL BE CARRIED OUT SOON AFTER THE COMPLETION OF TOPSOIL PLACEMENT.
 - FLOW DIVERSION SHALL BE CARRIED OUT BY EARLY INSTALLATION OF DRAINS ALONG TOPS OF BATTERS WITH APPROPRIATE SILTATION CONTROL DEVICES.

 • SEDIMENT INTERCEPTION BY THE PLACEMENT OF SUITABLE RETENTION SYSTEMS
 - ACROSS DRAINAGE LINES AND AT INTERCEPTION POINTS FOR BOTH THE CONSTRUCTION AND STOCKPILE AREAS.
- 4. ALL ACCESS TO AND FROM THE SITE SHALL BE VIA A TEMPORARY CONSTRUCTION ENTRY/EXIT. THE CONTRACTOR SHALL NOMINATE A PROPOSED ACCESS LOCATION ON THE ESC PLAN FOR APPROVAL BY THE SUPERINTENDENT.
- STOCKPILES SHALL ONLY BE LOCATED IN AREAS NOMINATED ON THE PROJECT DRAWINGS OR APPROVED BY THE SUPERINTENDENT. ALL STOCKPILES MUST HAVE APPROPRIATE ESC MEASURES INSTALLED TO PREVENT SEDIMENT TRANSPORT. THE MAXIMUM HEIGHT OF ALL STOCKPILES MUST BE LIMITED TO 2.0m
- ALL PERMANENT AND TEMPORARY UNLINED SWALES AND DRAINS MUST HAVE APPROPRIATE TEMPORARY EROSION PROTECTION.
- ALL PARTIALLY CONSTRUCTED DRAINAGE STRUCTURES MUST BE PROTECTED AGAINST SEDIMENT
- INFILTRATION DURING CONSTRUCTION. . COMPLETED DRAINAGE STRUCTURES MUST BE PROTECTED AGAINST SEDIMENT INFILTRATION UNTIL GRASSING IS ESTABLISHED.
- THE CONTRACTOR IS RESPONSIBLE FOR THE CONTROL OF DUST EMANATING FROM THE SITE AT ALL TIMES FOR THE DURATION OF CONSTRUCTION. WET SUPPRESSION METHODS TO BE
- 10. ALL EROSION AND SEDIMENT CONTROL MEASURES MUST BE CHECKED FOR DAMAGE. CLEANED
- OUT AND FULLY REINSTATED AFTER EACH RAINFALL EVENT RESULTING IN RUNOFF 11. IF EROSION AND SEDIMENT CONTROL DEVICES HAVE BEEN FOUND TO BE DEFICIENT OR FAILED SERVICE, DUE TO UNFORESEEN CIRCUMSTANCES, CORRECTIVE ACTION IS TO BE UNDERTAKEN IMMEDIATELY WHICH MAY INCLUDE AMENDMENTS/ADDITIONS TO THE ORIGINAL
- APPROVED FROSION CONTROL PLANS. 12. THE INSTALLATION, REMOVAL, RELOCATION OR MODIFICATION TO EROSION AND SEDIMENT CONTROL DEVICES MAY BE MADE BY COUNCIL IF DEEMED NECESSARY AND RELEVANT.
- 13. EROSION AND SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE UNTIL THE TREATMENT AREA IS SUITABLY STABILISED/VEGETATED.
 THE CONTRACTOR SHALL UNDERTAKE A FORMAL COMPLIANCE AUDIT OF THE ESC AT SIX
- WEEKS INTERVALS DURING THE CONSTRUCTION PERIOD OF THE PROJECT. RECORDS OF THE AUDIT SHALL BE RETAINED ON SITE. WHERE IDENTIFIED AS PART OF THE AUDIT THE ESCP SHALL BE UPDATED AND PROVIDED TO THE SUPERINTENDENT.

WATER NOTES:

- ALL WATER RETICULATION WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT FNQROC DEVELOPMENT MANUAL SPECIFICATION — S5 'WATER RETICULATION'.
 ALL PVC AND PE PIPES SHALL BE CLASS PN16. PVC PIPES SHALL BE RUBBER RING JOINTED
- AND DUCTILE IRON COMPATIBLE.
- 3. FOR MAIN TRENCHING, BEDDING & ANCHORAGE DETAILS REFER FNQROC STD DRAWINGS \$2015 & S2016. ENSURE COVER TO WATER MAINS IS 800mm MINIMUM UNDER ROADWAYS AND 600mm MINIMUM ELSEWHERE.
- ALL WATER MAINS SHALL BE INSTALLED ON A STANDARD 2.0m OFFSET FROM THE PROPERTY BOUNDARY UNLESS NOTED OTHERWISE ON PLANS.
- BUUNDARY UNLESS NOTED OTHERWISE ON FORMS.
 WHERE NON-METALLIC PIPES ARE LAID, A CONTINUOUS STEEL WIRE, 1.6mm MIN DIAMETER, SHALL BE LAID IMMEDIATELY ABOVE THE FILL SAND TO ASSIST IN FUTURE LOCATING. THIS WIRE IS TO BE WRAPPED ONCE AROUND ALL HYDRANTS AND VALVES.
- 6 COUNCIL MUST BE CONTACTED TO PERFORM ANY DIRECT CONNECTION OR ALTERATION TO LIVE WATER MAINS. THE CONTRACTOR SHALL LODGE WITH COUNCIL THE APPROPRIATE APPLICATION FORMS AND FEES FOR THESE WORKS TO BE COMPLETED. IT MAY BE POSSIBLE FOR SOME WORKS TO BE PERFORMED BY THE CONTRACTOR UNDER SPECIAL CIRCUMSTANCES AND SUBJECT
- TO APPROPRIATE CONDITIONS AGREED TO WITH COUNCIL.
 ALL HYDRANTS AND VALVES TO BE LOCATED OPPOSITE PROPERTY BOUNDARY TRUNCATIONS AND CORNERS, UNLESS NOTED OTHERWISE ON PLANS. FOR VALVES & HYDRANT BOXES INSTALLATION DETAILS REFER FNQROC STD DRAWINGS \$2000 AND \$2005.
- HYDRANTS OR VALVES CONSTRUCTED IN CONCRETE ARE TO HAVE A COMPRESSIBLE LAYER (ABLEFLEX) INSTALLED ON THE SURROUND. REFER FNQROC STD DRAWING \$2000.
- THE MINIMUM TEST PRESSURE FOR ALL PIPES SHALL BE 1250 KPa. THE GIVE COUNCILS WATER OFFICER 24 HOURS NOTICE PRIOR TO TESTING. PERIOD. THE CONTRACT SHALL

LANDSCAPING NOTES:

- 1. ALL LANDSCAPING WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT ENGROC
- DEVELOPMENT MANUAL SPECIFICATION S8 'LANDSCAPING'.

 ALL PLANTS MUST BE ORDER SUPPLIED BY A REPUTABLE NURSERY, AND ORDERED WELL IN ADVANCE TO ENSURE AVAILABILITY
- TURF TO BE USED SHALL BE ROLLED B GRADE TURF MIX OF SPECIES 80% BUFFALO GRASS
- (AXONOPUS COMPRESSUS) AND 20% COUCH GRASS VARIETIES.
 STREET TREES SHALL BE PROVIDED WHERE INDICATED ON PLAN. FINAL LOCATION TO BE DETERMINED ON SITE FOLLOWING INSTALLATION OF DRIVEWAYS AND CONFIRMATION OF SITE
- STREET TREES FINAL LOCATION SHALL BE IN ACCORDANCE WITH THE FOLLOWING
 - a. GREATER THAN 4.0m FROM ELECTRICITY OR TELECOMMUNICATION POLES OR PILLARS.
 - b. GREATER THAN 7.5m FROM STREET LIGHTS
- c. GREATER THAN 2.0m FROM STORMWATER DRAINAGE PITS
- d. GREATER THAN 3.0m FROM DRIVEWAYS
- e A MINIMUM OF 0.8m AND A MAXIMUM OF 1.0m FROM THE BACK OF KERB TEMPORARY IRRIGATION SHALL BE INSTALLED TO ENABLE WATERING DURING THE ESTABLISHMENT

APPROVED FOR CONSTRUCTION PRINT IN COLOUR

17/06/24 INITIAL ISSUE DATE DESCRIPTION DESIGN APPROVE





CLIENT



SCALE NTS

MF IVII SIGNOFF APPROVAL

MG

MG

MF

WYLANDRA ESTATE STAGE 1 GENERAL NOTES

CONMAT PTY LTD


DESIGNED


DATE: 17/06/24 RPEQ: 05085


160-010-C102

A3 Α


ALL DIMENSIONS IN METRES UNLESS NOTED OTHERWISE







CHAINAGE	EASTING	NORTHING	BRG. IN	BRG. OUT	RADII IN	RADII OUT
0.000	332752.214	8113595.754		260°30'53.40"		
184.886	332569.856	8113565.286	260°30'53.74"	260°30'53.74"		20.000
216.296	332546.835	8113581.710	350°29'47.69"	350°29'47.69"	20.000	
420 681	332513 089	8113783 291	350°29'47 47"	350°15'18 75"		



ROAD 1 - LONGITUDINAL SECTION

PRINT IN COLOUR

APPROVED FOR CONSTRUCTION

						l
Ω						ĺ
REVISIONS						l
Æ						
	Α	17/06/24	INITIAL ISSUE			ı
	NO.	DATE	DESCRIPTION	DESIGN	APPROVED	Ì



	CLIENI
(*)	CONMAT CONSTRUCTION MATERIALS

			SC	ALE				
:2000	0	10	20 3	0 40	50	60	А3	
			HORIZ	ONTAL		_		
1:200	0		2	4		6	АЗ	
			VERT	ICAL		_		
ALL	DIMENSI	ONS IN	METRES	UNLESS	NOTED	OTHER	WISE	


DRAWN	MG		DESIGNED	MG		PROJ
DRAWN APPROVED	MF		DESIGN APPROVED	MF		DRAW
CIVIL SIGNOFF	APPROVAL					Divi
		Jal	lant:			DRAV
		0 1	DATE: 17	/06/24 RPF0	05085	

ROAD 2 - CONTROL LINE

CHAINAGE	EASTING	NORTHING	BRG. IN	BRG. OUT	RADII IN	RADII OUT
0.000	332563.511	8113565.246		193°47'12.37"		
5.014	332562.316	8113560.376	193°47'12.37"	193°47'12.37"		-50.000
21.406	332561.066	8113544.106	175°00'10.70"	175°00'10.70"	-50.000	
22.822	332561.189	8113542.695	175°00'10.70"	175°00'10.70"		
166.904	332584.845	8113400.569	170°33'00.07"			

ROAD 3 - CONTROL LINE

CHAINAGE	EASTING	NORTHING	BRG. IN	BRG. OUT	RADII IN	RADII OUT
0.000	332531.151	8113675.402		260°35'35.02"		
109 610	332423 002	9113657 649	260°35'35 02"			



ROAD 2 - LONGITUDINAL SECTION

35m VC

R = 3655.98

ROAD 3 - LONGITUDINAL SECTION

PRINT IN COLOUR

APPROVED FOR CONSTRUCTION

<u>د</u>						Ī
REVISIONS						İ
8						İ
	Α	17/06/24	INITIAL ISSUE			İ
	NO.	DATE	DESCRIPTION	DESIGN	APPROVED	Ì

CH.11.006/IP457.541

11.006m

R = 267.65

134 141 246 268 289 314

458. 458. 458. 458.

ROAD 1-

INTERSECTION

Horizontal Curve Data

Vertical Grade Length

DATUM RL451.000

CHAINAGE

Vertical Curve Length (m)

Vertical Curve Radius (m)

CUT/FILL DEPTH

DESIGN SURFACE

NATURAL SURFACE

Vertical Geometry Grade (%)

NATURAL SURFACE

2.604 %

82.075m

DESIGN SURFACE





110.581

1.647 %

71.717m

		SCA	LE		
1:1000	0	10	20	30	A3
		HORIZ	ONTAL		
1:200	0	2	4	6	A3
		VERT	ICAL		
ALL	DIMENSIONS	IN METRES	UNLESS N	NOTED OTHER	WISE

36.331m

-0.054

460.

164.797 166.904


30m VC

R = 2675.45


DRAWN	IVIO		DESIGNED	IVIO			
DRAWN APPROVED	MF		DESIGN APPROVED	MF		DRAW	INC I
CIVIL SIGNOFF A	PPROVAL					DIVA	IIVO
		$\neg I n$	1.7.				
		J***//	lanc.			DRAW	ING
			DATE: 17,	/06/24	RPEQ: 05085		

MG


PROJECT REF	CONMAT PTY LTD		
	WYLANDRA ESTATE STAGE 1		
DRAWING REF	ROAD 2 AND 3 LONGITUDINAL SECT	ION	
	(SHEET 2 OF 2)		
 DRAWING NO	160-010-C107	A3	REVISION A



TYPICAL CROSS SECTION SCALE 1:100




LAYBACK KERB AND CHANNEL



NOTE: SUBGRADE CBR RESULTS AND FINAL PAVEMENT DESIGN ARE TO BE SUBMITTED TO COUNCIL FOR APPROVAL PRIOR TO PLACEMENT OF

PAVEMENT DETAIL

N.T.S.



NOTE: SUBGRADE CBR RESULTS AND FINAL PAVEMENT DESIGN ARE TO BE SUBMITTED TO COUNCIL FOR APPROVAL PRIOR TO PLACEMENT OF

PAVEMENT DETAIL - INTERSECTIONS

PAVEMENT NOTES

- 1. THE SUB-BASE LAYER SHALL EXTEND A MINIMUM OF 300mm BEHIND THE REAR FACE OF THE KERB
- 2. THE BASE AND SURFACING SHALL EXTEND TO THE FACE OF ANY KERBING. WHERE THE TOP SURFACE OF THE SUB-BASE LAYER IS BELOW THE LEVEL OF THE UNDERSIDE OF THE KERB AND CHANNEL, THE BASE LAYER SHALL ALSO EXTEND A MINIMUM OF 150MM BEHIND THE REAR FACE OF THE KERB AND

PRINT IN COLOUR

APPROVED FOR CONSTRUCTION

17/06/24 INITIAL ISSUE DATE DESCRIPTION DESIGN APPROVED





				SCALE					
1:20	0	0.1	0.2	0.3	0.4	0.5	0.6	A3	
1:100	0	_	1		2		3	А3	

NWAS	MG		DESIGNED	MG
RAWN PPROVED	MF		DESIGN APPROVED	MF
VIL SIGNOFF /	APPROVAL			
		The	lat:	


CONMAT PTY LTD WYLANDRA ESTATE STAGE 1 TYPICAL ROAD CROSS SECTION AND DETAILS

ALL DIMENSIONS IN METRES UNLESS NOTED OTHERWISE


DATE: 17/06/24 RPEO: 05085

160-010-C108

^A3



RADIUS 20.000m ARC LENGTH 20.535m RADIUS 15.000m ARC LENGTH 14.926m (16) AREA OF 50mm ASPHALT 272m² RADIUS 15.000m ARC LENGTH 21.229m



ROAD 2 - INTERSECTION SCALE 1:400

ROAD 3 - INTERSECTION

SCALE 1:400

WYLANDRA DRIVE INTERSECTION SETOUT

POINT NO.	EASTING	NORTHING	HEIGHT
1	332751.759	8113578.165	459.209
2	332750.343	8113581.759	459.117
3	332747.964	8113584.975	459.009
4	332744.822	8113587.444	458.885
5	332741.137	8113588.997	458.775
6	332737.183	8113589.520	458.703
7	332734.707	8113589.310	458.672
8	332733.520	8113596.148	458.672
9	332737.340	8113597.318	458.680
10	332740.718	8113599.458	458.664
11	332743.410	8113602.410	458.626
12	332745.228	8113605.974	458.573
13	332746.039	8113609.892	458.513
14	332746.077	8113610.836	458.454

ROAD 2 INTERSECTION SETOUT

POINT NO.	EASTING	NORTHING	HEIGHT
15	332557.636	8113553.424	457.543
16	332557.477	8113557.418	457.571
17	332556.271	8113561.228	457.633
18	332554.099	8113564.585	457.664
19	332551.997	8113566.608	457.644
20	332556.170	8113572.157	457.638
21	332558.780	8113570.428	457.689
22	332561.831	8113569.174	457.733
23	332565.071	8113568.550	457.777
24	332568.371	8113568.582	457.820
25	332572.130	8113569.184	457.852
26	332575.757	8113569.790	457.883
27	332576.901	8113562.943	457.883
28	332573.081	8113561.773	457.833
29	332569.700	8113559.633	457.742
30	332567.014	8113556.673	457.617
31	332565.194	8113553.110	457.555
32	332564.386	8113549.224	457.582
33	332564.348	8113547.996	457.609

ROAD 3 INTERSECTION SETOUT

POINT NO.	EASTING	NORTHING	HEIGHT
33	332530.777	8113656.613	456.267
34	332529.605	8113660.434	456.192
35	332527.464	8113663.814	456.089
36	332524.506	8113666.505	455.958
37	332520.945	8113668.318	455.846
38	332517.029	8113669.129	455.789
39	332513.496	8113668.959	455.785
40	332512.301	8113675.796	455.785
41	332516.124	8113676.960	455.771
42	332519.504	8113679.094	455.767
43	332522.201	8113682.046	455.775
44	332524.023	8113685.606	455.775
45	332524.840	8113689.522	455.751
46	332524.668	8113693.105	455.710

LEGEND

STAGE BOUNDARY PROPOSED PROPERTY BOUNDARY EXISTING PROPERTY BOUNDARY FUTURE PROPERTY BOUNDARY PROPOSED MAJOR CONTOURS (0.5m INTERVAL) PROPOSED MINOR CONTOURS (0.1m INTERVAL) EXISTING MAJOR CONTOURS (1.0m INTERVAL) --- EXISTING MINOR CONTOURS (0.1m INTERVAL) PROPOSED BATTER - -- PROPOSED ROAD CENTRELINE 30mm DG14 ASPHALT 50mm DG14 ASPHALT

NOTES

1. REFER TO 160-010-C106 AND C107 FOR ROAD CONTROL LINE SETOUT.

PRINT IN COLOUR

APPROVED FOR CONSTRUCTION

(0					
REVISIONS					
×.					
22	В	19/02/25	CONTOURS AMENDED	MG	
	Α	17/06/24	INITIAL ISSUE		
	NO	DATE	DESCRIPTION	DESIGN	APPROVED









ALL DIMENSIONS IN METRES UNLESS NOTED OTHERWISE


DRAWN APPROVED	MF		DESIGN APPROVED	MF	
CIVIL SIGNOFF	APPROVAL				
		Jan	Jant: DATE: 17	/06/24	RPEQ: 05085


MG


PROJECT REF CONMAT PTY LTD		
WYLANDRA ESTATE STAGE 1		
INTERSECTION SETOUT		
160-010-C109	A3	REVISION


























<u>FABRIC:</u>
POLYPROPYLENE, POLYAMIDE, NYLON, POLYESTER, OR POLYETHYLENE WOVEN OR NON-WOVEN FABRIC, AT LEAST
700mm IN WIDTH AND A MINIMUM UNIT WEIGHT OF 140GSM. ALL FABRICS TO CONTAIN ULTRAVIOLET INHIBITORS AND STABILISERS TO PROVIDE A MINIMUM OF 6 MONTHS OF USEABLE CONSTRUCTION LIFE (ULTRAVIOLET STABILITY

FABRIC REINFORCEMENT:
WIRE OR STEEL MESH MINIMUM 14-GAUGE WITH A MAXIMUM MESH SPACING OF 200mm.

SUPPORT POSTS/STAKES:

1500mm2 (MIN) HARDWOOD, 2500mm2 (MIN) SOFTWOOD, OR 1.5kg/m (MIN) STEEL STAR PICKETS SUITABLE FOR

- 1. REFER TO APPROVED PLANS FOR LOCATION, EXTENT AND REQUIRED TYPE OF FABRIC (IF SPECIFIED). IF THERE ARE QUESTIONS OR PROBLEMS WITH THE LOCATION, EXTENT, FABRIC TYPE, OR METHOD OF INSTALLATION CONTACT THE ENGINEER OR RESPONSIBLE ON—SITE OFFICER FOR ASSISTANCE.

 2. TO THE MAXIMUM DEGREE PRACTICAL, AND WHERE THE PLANS ALLOW, ENSURE THE FENCE IS LOCATED:

 1. TOTALLY WITHIN THE PROPERTY BOUNDARIES;

 11. ALONG A LINE OF CONSTANT ELEVATION WHEREVER PRACTICAL;

 12. ALONG A LINE OF CONSTANT ELEVATION WHEREVER PRACTICAL;

- iii. AT LEAST 2m FROM THE TOE OF ANY FILLING OPERATIONS THAT MAY RESULT IN SHIFTING SOIL/FILL
- III. AT LEAST 2'M FROM THE TOE OF ANY FILLING OPERATIONS THAT MAY RESULT IN SHIFTING SOIL/FILL DAMAGING THE FENCE.

 3. INSTALL RETURNS WITHIN THE FENCE AT MAXIMUM 20m INTERVALS IF THE FENCE IS INSTALLED ALONG THE CONTOUR, OR 5 TO 10m MAXIMUM SPACING (DEPENDING ON SLOPE) IF THE FENCE IS INSTALLED AT AN ANGLE TO THE CONTOUR. THE RETURNS' SHALL CONSIST OF EITHER:

 I. V-SHAPED SECTION EXTENDING AT LEAST 1.5m UP THE SLOPE; OR
- 1. V-SHAPED SECTION EXTENDING AT LEAST 1.5m UP THE SLOPE; OR

 1i. SANDBAG OR ROCK/AGGREGATE CHECK DAM A MINIMUM 1/3 AND MAXIMUM 1/2 FENCE HEIGHT, AND EXTENDING AT LEAST 1.5m. UP THE SLOPE.

 4. ENSURE THE EXTREME ENDS OF THE FENCE ARE TURNED UP THE SLOPE AT LEAST 1.5m, OR AS NECESSARY, TO MINIMISE WATER BYPASSING AROUND THE FENCE.

 5. ENSURE THE SEDIMENT FENCE IS INSTALLED IN A MANNER THAT AVOIDS THE CONCENTRATION OF FLOW ALONG THE FENCE, AND THE UNDESIGNABLE DISCHARGE OF WATER AROUND THE ENDS OF THE FENCE.

 6. IF THE SEDIMENT FENCE IS TO BE INSTALLED ALONG THE EDGE OF EXISTING TREES, ENSURE CARE IS TAKEN TO PROTECT THE TREES AND THEIR POOT SYSTEMS DIREND, INSTALLATION, OF THE FENCE.

 7. ON THE SEDIMENT FENCE IS TO BE INSTALLED ALONG THE EDGE OF EXISTING TREES, ENSURE CARE IS TAKEN TO PROTECT THE TREES AND THEIR POOT SYSTEMS DIREND. INSTALLATION, OF THE FENCE.
- PROTECT THE TREES AND THEIR ROOT SYSTEMS DURING INSTALLATION OF THE FENCE. DO NOT ATTACH TH
- VALUES DIRECTED BY THE SITE SUPERVISOR OR THE APPROVED PLANS, EXCAVATE A 200mm WIDE BY 200mm DEEP TRENCH ALONG THE PROPOSED FENCE LINE, PLACING THE EXCAVATED MATERIAL ON THE UP-SLOPE SIDE OF THE TRENCH.
- B. ALONG THE LOWER SIDE OF THE TRENCH, APPROPRIATELY SECURE THE STAKES INTO THE GROUND SPACED NO GREATER THAN 3m IF SUPPORTED BY A TOP SUPPORT WIRE OR WEIR MESH BACKING, OTHERWISE NO GREATER
- THAN 2m.

 9. IF SPECIFIED, SECURELY ATTACH THE SUPPORT WIRE OR MESH TO THE UP-SLOPE SIDE OF THE STAKES WITH THE MESH EXTENDING AT LEAST 200mm INTO THE EXCAVATED TRENCH, ENSURE THE MESH AND FABRIC IS ATTACHED TO THE UP-SLOPE SIDE OF THE STAKES EVEN WHEN DIRECTING A FENCE AROUND A CORNER OR SHARP CHANGE
- TO THE UP-SLOPE SIDE OF THE STAKES EVEN WHEN DIRECTING A FENCE AROUND A CORNER OR SHARP CHANGE OF DIRECTION.

 10. WHEREVER POSSIBLE, CONSTRUCT THE SEDIMENT FENCE FROM A CONTINUOUS ROLL OF FABRIC. TO JOIN FABRIC EITHER:

 I. ATTACH EACH END TO TWO OVERLAPPING STAKES WITH THE FABRIC FOLDING AROUND THE ASSOCIATED STAKE ONE TURN, AND WITH THE TWO STAKES TIED TOGETHER WITH WIRE; OR

 II. OVERLAP THE FABRIC TO THE NEXT ADJACENT SUPPORT POST.

 11. SECURELY ATTACH THE FABRIC TO THE SUPPORT POSTS USING 25 X 12.5mm STAPLES, OR TIE WIRE AT MAXIMUM 1500ms SPACING.
- 150mm SPACING.

- 13. SECURELY ATTACH THE FABRIC TO THE SUPPORT WIRE/MESH (IF ANY) AT A MAXIMUM SPACING OF 1m.

 13. ENSURE THE COMPLETED SEDIMENT FENCE IS AT 450mm, BUT NOT MORE THAN 700mm HIGH. IF A SPILL—THOUGH WEIR IS INSTALLED, ENSURE THE CREST OF THE WEIR IS AT LEAST 300mm ABOVE GROUND LEVEL.

 14. BACKFILL THE TRENCH AND TAMP THE FILL TO FIRMLY ANCHOR THE BOTTOM OF THE FABRIC AND MESH TO PREVENT WATER FROM FLOWING UNDER THE FENCE.

ADDITIONAL REQUIREMENTS FOR THE INSTALLATION OF SPILL-THROUGH WEIR

- ADDITIONAL REQUIREMENTS FOR THE INSTALLATION OF SFILL—THROUGH WEIR

 15. LOCATE THE SPILL—THROUGH WEIR SUCH THAT THE WEIR CREST WILL BE LOWER THAN THE GROUND LEVEL AT
 EACH END OF THE FENCE.

 16. ENSURE THE CREST OF THE SPILL—THROUGH WEIR IS AT LEAST 300mm THE GROUND ELEVATION.

 17. SECURELY TIE A HORIZONTAL CROSS MEMBER (WEIR) TO THE SUPPORT POSTS/STAKES EACH SIDE OF THE WEIR.

 CUT THE FABRIC DOWN THE SIDE OF EACH POST AND FOLD THE FABRIC OVER THE CROSS MEMBER AND
- 18. INSTALL A SUITABLE SPLASH PAD AND/OR CHUTE IMMEDIATELY DOWN-SLOPE OF THE SPILL-THROUGH WEIR TO CONTROL SOIL EROSION AND APPROPRIATELY DISCHARGE THE CONCENTRATED FLOW PASSING OVER THE WEIR.

MAINTENANCE

- MAINTENANCE.

 19. INSPECT THE SEDIMENT FENCE AT LEAST WEEKLY AND AFTER ANY SIGNIFICANT RAIN. MAKE NECESSARY REPAIRS IMMEDIATELY.

 20. REPAIR ANY TORN SECTIONS WITH A CONTINUOUS PIECE OF FABRIC FROM POST TO POST.

 21. WHEN MAKING REPAIRS, ALWAYS RESTORE THE SYSTEM TO ITS ORIGINAL CONFIGURATION UNLESS AN AMENDED LAYOUT IS REQUIRED OR SPECIFIED.


- 22. IF THE FENCE IS SAGGING BETWEEN STAKES, INSTALL ADDITIONAL SUPPORT POSTS.
- REMOVE ACCUMULATED SEDIMENT IF THE SEDIMENT DEPOSIT EXCEEDS A DEPTH OF 1/3 THE HEIGHT OF THE
- FENCE.

 24. DISPOSE OF SEDIMENT IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.

 25. REPLACE THE FABRIC IS THE SERVICE LIFE OF THE EXISTING FABRIC EXCEEDS 6 MONTHS.

- 26. WHEN DISTURBED AREAS UP-SLOPE OF THE SEDIMENT FENCE ARE SUFFICIENTLY STABILISED TO RESTRAIN
- 20. WHEN DISTRIBED AREAS DESIGNED THE SEDIMENT FERVE ARE SUFFICIENTED STABILISED TO RESTRAIN EROSION, THE FERVE MUST BE REMOVED.

 27. REMOVE MATERIALS AND COLLECTED SEDIMENT AND DISPOSE OF IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.
- 28. REHABILITATE/REVEGETATE THE DISTURBED GROUND AS NECESSARY TO MINIMISE THE EROSION HAZARD.



RETURNS TO BE PROVIDED AT __ 1.5m (MIN) MAXIMUM 20M SPACING WHEN INSTALLED ALONG CONTOUR. OTHERWISE 5-10M MAX DEPENDING UPON SLOPE 3000 MAX WITH A TOP WIRE OTHERWISE 2000 DIRECTION OF FLOW. ALL SUPPORT POSTS TO BE 50X50 HW STAKE OR 1.5KG/M STEEL STAR PICKET SAFFTY CAP PLACED SILT FENCE DOWN-SLOPE OF FABRIC FARRIC BURIFD FABRIC (NOT FILTER CLOTH OR SHADE CLOTH)

SEDIMENT FENCE NOT TO SCALE

75 - 150 NOMINAL STAR PICKETS AT ROCK 0.5m CRS (3 MINIMUM) GEOTEXTILE REMOVABLE LAYER OF - DUMPED ROCK 250 FABRIC TO U/S FACE. REMOVED AND REPLACED (NON-WOVEN WITH MAINTENANCE CLEANS # WIDTH OF WEIR TO **ROCK FILTER DAM**

MATERIALS.

ROCK: 75 TO 150mm NOMINAL DIAMETER, HARD, EROSION RESISTANT ROCK.

HEAVY—DUTY, NEEDLE—PUNCHES, NON—WOVEN FILTER CLOTH ('BIDIM' A24 OR FOUIVALENT).

- INSTALLATION

 1. REFER TO APPROVED PLANS FOR LOCATION AND INSTALLATION DETAILS. IF THERE ARE QUESTIONS OR PROBLEMS WITH THE LOCATION OR METHOD OF INSTALLATION, CONTACT THE ENGINEER OR RESPONSIBLE ON—SITE OFFICER FOR ASSISTANCE.

 2. PRIOR TO PLACEMENT OF THE FILTER DAM, ENSURE THE TYPE AND SIZE OF EACH CHECK DAMS WILL NOT CAUSE A SAFETY HAZARD OR CAUSE WATER TO SPILL OUT OF THE DRAIN.

 3. CONSTRUCT THE FILTER DAM TO THE DIMENSIONS AND PROFILE SHOWN WITHIN THE ADDRAVED DIAM.

- WHERE SPECIFIED, THE FILTER DAM SHALL BE CONSTRUCTED ON A SHEET OF GEOTEXTILE FABRIC USED AS A DOWNSTREAM SPLASH PAD.

- INSPECT EACH FILTER DAM AND THE DRAINAGE CHANNEL AT LEAST WEEKLY AND AFTER
- INSPECT EACH FILTER DAM AND THE DRAINAGE CHANNEL AT LEAST WEERLY AND AFTER RUNOFF-PRODUCING RAINFALL.


 CHECK FOR DISPLACEMENT OF THE FILTER DAM
 CHECK FOR SOIL SCOUR AROUND THE ENDS OF THE FILTER DAM. IF SUCH EROSION IS OCCURRING, CONSIDER EXTENDING THE WIDTH OF THE FILTER DAM TO AVOID SUCH PROBLEMS.

 IF SEVERE SOIL EROSION OCCURS EITHER UNDER OR AROUND THE FILTER DAM, THEN SEFE EVECET ADVICE ON AN ALTERDANTIVE TREATMENT MEASURE
- SEEK EXPERT ADVICE ON AN ALTERNATIVE TREATMENT MEASURE.

 REMOVE AND SEDIMENT ACCUMENT THE FILTER DAM, UNLESS IT IS INTENDED THAT THIS SEDIMENT WILL REMAIN WITHIN THE CHANNEL.
- 6. DISPOSE OF COLLECTED SEDIMENT IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.
- 7. REPLACE GEOFABRIC LAYER ON UPSTREAM FACE WITH A CLEAN LAYER AS REQUIRED.

- WHEN CONSTRUCTION WORK WITHIN THE DRAINAGE AREA ABOVE THE FILTER DAM HAS BEEN COMPLETED, AND THE DISTURBED AREAS AND THE DRAINAGE CHANNEL ARE SUFFICIENTLY STABILISED TO RESTRAIN EROSION, ALL TEMPORARY CHECK DAMS MUST BE
- SUFFICIENTLY STABILISED TO RESTRAIN EROSION, ALL TEMPORARY CHECK DAMS MOST REMOVED.

 REMOVE THE FILTER DAM AND ASSOCIATED SEDIMENT AND DISPOSE OF IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.



TEMPORARY CONSTRUCTION ENTRY / EXIT

NOT TO SCALE

MATERIAL

WELL GRADED, HARD, ANGULAR, EROSION RESISTANT ROCK, NOMINAL DIAMETER OF 50 TO 75mm (SMALL DISTURBANCES) OR 100 TO 150mm (LARGE DISTURBANCES). ALL REASONABLE MEASURES MUST BE TAKEN TO OBTAIN ROCK OF NEAR UNIFORM SIZE.

FOOTPATH STABILISING AGGREGATE: 25 TO 50mm GRAVEL OR AGGREGATE

HEAVY-DUTY, NEEDLE-PUNCHES, NON-WOVEN FILTER CLOTH ('BIDIM' A24 OR EQUIVALENT).

INSTALLATION

- INSTALLATION

 1. REFER TO APPROVED PLANS FOR LOCATION AND DIMENSIONAL DETAILS. IF THERE ARE QUESTIONS OR PROBLEMS WITH THE LOCATION, DIMENSIONS, OR METHOD OF INSTALLATION, CONTACT THE ENGINEER OR RESPONSIBLE ON-SITE OFFICER FOR ASSISTANCE.

 2. CLEAR THE LOCATION OF THE ROCK PAD, REMOVING STUMPS, ROOTS AND OTHER VEGETATION TO PROVIDE A FIRM FOUNDATION SO THAT THE ROCK IS NOT PRESSED INTO SOFT GROUND. CLEAR SUFFICIENT WIDTH TO ALLOW PASSAGE OF LARGE VEHICLES, BUT CLEAR ONLY THAT NECESSARY FOR THE EXIT. DO NOT CLEAR ADJACENT AREAS UNTIL THE REQUIRED EROSION AND SEDIMENT CONTROL DEVICES ARE IN PLACE.

 3. IF THE EXPOSED SOIL IS SOFT, PLASTIC OR CLAYEY, PLACE A SUB-BASE OF CRUSHED ROCK OR A LAYER OF HEAVY-DUTY FILTER CLOTH TO PROVIDE A FIRM FOUNDATION.

 4. PLACE THE ROCK PAD FORNING A MINIMUM 200mm THICK LAYER OF CLEAN, OPEN-VOID ROCK.

 5. IF THE ASSOCIATED CONSTRUCTION SITE IS UP-SLOPE OF THE ROCK PAD, THUS CAUSING STORMWATER RUNOFF TO FLOW TOWARDS THE ROCK PAD TO DIVERT SUCH RUNOFF TO A SUITABLE SEDIMENT TRAP.

 6. THE LENGTH OF THE ROCK PAD SHOULD BE AT LEAST 15M WHERE PRACTICABLE, AND AS WISE AS THE FOLL WIDTH OF THE ENTRY OR EXIT AND AT LEAST 15M WHERE PRACTICABLE, AND AS WISE AS THE FULL WIDTH OF THE ENTRY OR EXIT AND AT LEAST 15M. THE ROCK PAD SHOULD COMMENCE AT THE EDGE OF THE OFF-SITE SEALED ROAD OR PAYEMENT.

 7. FLARE THE END OF THE ROCK PAD WHERE IT MEETS THE PAVEMENT SO THAT THE WHEELS OF TURNING VEHICLES DO NOT TRAVEL OVER UNFROTECTED SOIL.

 8. IF THE FOOTPATH IS OPEN TO PEDESTRIAN MOVEMENT, THE COVER THE COARSE ROCK WITH FINE AGGREGATE OR GRAVEL, OR OTHERWISE TAKE WHATEVER MEASURES ARE NEEDED TO MAKE THE AREA SAFE.

 MAINTENANCE

MAINTENANCE

- MAINTENANCE

 9. INSPECT ALL SITE ENTRY AND EXIT POINTS PRIOR TO FORECAST RAIN, DAILY DURING EXTENDED PERIODS OF RAINFALL, AFTER RUNNOFF-PRODUCING RAINFALL, OR OTHERWISE AT FORTNICHTLY INTERVALS.

 10. IF SAND, SOIL, SEDIMENT OR MUD IS TRACKED OR WASHED ONTO THE ADJACENT SEALED ROADWAY, THEN SUCH MATERIAL MUST BE PHYSICALLY REMOVED, FIRST USING A SQUARE-EDGED SHOVEL, AND THEN A STIFF-BRISTLED BROOM, AND THEN BY A MECHANICAL VACUUM UNIT, IF AVAILABLE.

 11. IF NECESSARY FOR SAFETY REASONS, THE ROADWAY SHALL ONLY BE WASHED CLEAN AFTER ALL REASONABLE EFFORTS HAVE BEEN TAKEN TO SHOVEL AND SWEEP THE MATERIAL FROM THE ROADWAY.


 12. WHEN THE VOIDS BETWEEN THE ROCK BECOMES FILLED WITH MATERIAL AND THE EFFECTIVENESS OF THE ROCK PAD IS REDUCED TO A POINT WHERE SEDIMENT IS BEING TRACKED OFF THE SITE. A NEW 100MM LAYER OF ROCK MUST BE EXTENDED.

 13. ENSURE ANY ASSOCIATED DRAINAGE CONTROL MEASURES (e.g. FLOW CONTROL BERM) ARE MAINTAINED IN ACCORDANCE WITH THEIR DESIRED OPERATIONAL CONDITIONS.

 14. DISPOSE OF SEDIMENT AND DEBRIS IN A MANNER THAT WILL NOT CREATE AN EROSION OR POLLUTION

- 14. DISPOSE OF SEDIMENT AND DEBRIS IN A MANNER THAT WILL NOT CREATE AN EROSION OR POLLUTION

- THE ROCK PAD SHOULD BE REMOVED ONLY AFTER IT IS NO LONGER NEEDED AS A SEDIMENT TRAP. REMOVE MATERIALS AND COLLECTED SEDIMENT AND DISPOSE OF IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.
- RE-GRADE AND STABILISE THE DISTURBED GROUND AS NECESSARY TO MINIMISE THE EROSION HAZARD.



DIVERSION DRAINS

MAINTENANCE

SHOULD BE CHECKED WEEKLY

EXCESSIVE SEDIMENT SHOULD BE REMOVED TO AVOID PONDING


REPAIR ANY SLUMPS OR DAMAGE

1. THE SPACING OF CATCH DRAINS DOWN EXPOSED SLOPES SHOULD NOT EXCEED THE DISTANCE DEFINED BY:

MAXIMUM SPACING ≈ 48 [LOG(H)] - 25 METRES

■ 71 - 48 [LOG(% SLOPE)] METRES WHERE: H IS THE HORIZONTAL SLOPE COMPONENT AS DEFINED BY H(H):1(V) AND (% SLOPE)= <u>100</u>

APPROVED FOR CONSTRUCTION







CLIENT

NTS

MF CIVIL SIGNOFF APPROVAL

MG

ESIGNED

WYLANDRA ESTATE STAGE 1 **EROSION AND SEDIMENT CONTROL NOTES**

CONMAT PTY LTD

160-010-C120

ALL DIMENSIONS IN METRES UNLESS NOTED OTHERWISE

SCALE


^A3


Α


DATE: 17/06/24 RPEQ: 0508


MG

MF










CL Design Height 454.766




Datum 456.0

Ch 220.000 CL Design Height 456.511


PRINT IN COLOUR

APPROVED FOR CONSTRUCTION











		DRAWN	N
6	A3	DRAWN APPROVED	ı
0.6	A3	CIVIL SIGNOFF	APPRO

	MG		DESIGNED	MG	
VED	MF		DESIGN APPROVED	MF	
GNOFF A	APPROVAL				
		Jan	lant:	/00 /04	2222 05005
			DAIE: 20,	/06/24	RPEQ: 05085

:F	CONMAT PTY LTD		
	WYLANDRA ESTATE STAGE 1		
F	DRAIN 1		
	CROSS SECTIONS		
)	160-010-C123	A3	REVISION A










CLIENT



DRAWN	MG		DESK
DRAWN APPROVED	MF		DESI
CIVIL SIGNOFF	APPROVAL		
		Jan	lant

MG	DESIGNED	MG	PROJECT REF CONMAT PTY LTD			
MF	DESIGN APPROVED	MF	WYLANDRA ESTATE STAGE 1			
APPROVAL	AFFROVED		DRAIN 2			
TI V	N.+.		CROSS SECTIONS			
Jan 11	DATE: 26/06	6/24 RPEQ: 05085	160-010-C124	A3	REVIS	

PRINT IN COLOUR

CONMAT PTY LTD

APPROVED FOR CONSTRUCTION

A3

S						l
REVISIONS						İ
Æ						
	Α	26/06/24	INITIAL ISSUE			
	NO.	DATE	DESCRIPTION	DESIGN	APPROVED	Ì






				SCALE					
1:200	0	_	2		4		6	А3	
			НОІ	RIZON	TAL		_		
1:20	0	0.1	0.2	0.3	0.4	0.5	0.6	А3	
		_	VI	RTIC	AL				
ALL	DIMEN	CIONIC	IN MET	DEC III	II ECC I	NOTED	OTHER	MICE	


DRAWN	MG		DESIG
DRAWN APPROVED	MF		DESI APPI
CIVIL SIGNOFF	APPROVAL	Jan	Jant

- NATURAL SURFACE

MG	DESIGNED M	IG	PROJECT REF CONMAT PTY LTD
MF	DESIGN IV	1F	WYLANDRA ESTATE STAGE 1
DFF APPROVAL	AFFROVED		DRAIN 3
TI N	1.7		CROSS SECTIONS
Jan 11	Jan	A 2000 05005	160-010-C125



CHAINAGE	EASTING	NORTHING	BRG. IN	BRG. OUT	RADII IN	RADII OUT
0.000	332360.015	8113771.524		304°11'02.12"		
50.094	332318.575	8113799.669	304°11'02.12"	304°11'02.12"		20.000
82.928	332314.105	8113828.595	38°14'41.19"	38°14'41.19"	20.000	
198.779	332385.819	8113919.581	38°14'41.19"	38°14'41.19"		20.000
230.655	332414.265	8113922.619	129°33'46.55"	129°33'46.55"	20.000	
299.390	332467.255	8113878.840	129°33'46.55"			



DETENTION BASIN - LONGITUDINAL SECTION

PRINT IN COLOUR

160-010-C127

APPROVED FOR CONSTRUCTION

Α

ı							
l							l
l	Š						1
l	REVISIONS						1
l	æ						1
١		Α	12/02/25	INITIAL ISSUE			ı
L		NO.	DATE	DESCRIPTION	DESIGN	APPROVED	L




	OBEN	
(1)	CONICONSTRUCTION	


				SCA	LE				
1:2000	0	10	20	30	40	50	60	A3	
			HOI	RIZC	NTAL				
1:200	0	_	2		4		6	A3	
			VE	RTI	ICAL				
ALL	DIMENS	SIONS II	N MET	RES	UNLESS	NOTED	OTHER	WISE	

DRAWN	MG		DESIGNED	MF
DRAWN APPROVED	MF		DESIGN APPROVED	JM
CIVIL SIGNOFF	APPROVAL			
		Jan	lant:	

DATE: 12/02/25 RPEQ: 05085

CONMAT PTY LTD WYLANDRA ESTATE STAGE 1 DETENTION BASIN LONGITUDINAL SECTION ^A3







Wylandra Estate Stage 1

Operational Works Design Report

File No: 160-010

February 2025

Client: CONSTRUCTION MATERIALS





Prepared by:

ERSCON PTY. LTD. T/as ERSCON Consulting Engineers PO Box 7890 CAIRNS QLD 4870

Telephone: (07) 4242 8479



DOCUMENT ISSUE RECORD

Revision Code	Date Revised	Revision Details	Author	Checked	Approved
Α	20/06/24	Operational Works Application	MG	MF	JM
В	17/02/25	Operational Works Application	MG	MF	JM

© 2025 ERSCON PTY LTD

This document is and shall remain the property of ERSCON Pty Ltd. This document may only be used for the purposes for which it was commissioned in accordance with the Terms of Engagement. Unauthorised use of this document in any form whatsoever is prohibited.

This report has been prepared on behalf of and for the exclusive use of the Client and is subject to all provisions of the agreement between ERSCON Pty Ltd and the Client. ERSCON Pty Ltd accepts no liability or responsibility whatsoever for reliance upon this report by any third party.



Table of Contents

<u>1</u>	<u>SUMMARY</u>	4
1.1	DEVELOPMENT APPLICATION DETAILS	4
1.2		
1.3		
<u>2</u>	SITE DETAILS	<u> 5</u>
2.1	SITE DESCRIPTION	5
2.2	SURROUNDING LAND USES	7
<u>3</u>	PROPOSED DEVELOPMENT DETAILS	8
<u>4</u>	DEVELOPMENT APPLICATION FORM 1	9
<u>5</u>	SUBDIVISION CONDITIONS	10
<u>6</u>	STORMWATER DRAINAGE	11
6.1	DESIGN METHOD	11
6.2	MINOR DRAINAGE	11
6.2.	.1 Hydrological Design Philosophy	11
6.2.	.2 Hydrological Analysis	11
6.3	MAJOR DRAINAGE	12
6.3.	.1 Overland Flow	12
6.3.	.2 FLOOD IMMUNITY	12
6.4	STORMWATER OUTLETS	12
6.5	WATER QUALITY	13
6.6	DETENTION BASIN	20
<u>7</u>	POTABLE WATER RETICULATION	21
7.1	DESIGN METHOD	21
7.2	P GENERAL LAYOUT	21
7.2.	.1 ALIGNMENT	21
7.2.	.2 Cover	21
7.2.	.3 FITTINGS	22
7.3	B DESIGN	22
7.3.	.1 Maximum Hour Demand	22
7.3.	.2 FIRE FIGHTING DEMAND	22
<u>8</u>	SEWERAGE RETICULATION	23
9	ROAD PAVEMENT DESIGN	24
9.1	DESIGN METHOD	24
9.1.	.1 Design Life	24
9.1.	.2 Subgrade	24
9.1.	.3 FLEXIBLE PAVEMENT DESIGN	24



10 ELECTRICAL, COMMUNICATIONS, AND GAS RETICULATION			
<u>11 SC</u>	DIL AND WATER MANAGEMENT	26	
	EROSION AND SEDMENT CONTROL STANDARDS		
11.1.1	DUTY OF CARE	26	
11.2	CONCEPT REPORT	26	
11.2.1	SITE CONDITIONS	26	
11.2.2	CONTROL MEASURES	26	
	WATER QUALITY STRATEGY		
	WATER QUALITY MONITORING		
11.3 E	EROSION AND SEDIMENT CONTROL PLAN	27	
11.3.1	ENVIRONMENTAL RESPONSIBILITIES OF KEY STAFF	28	
11.3.2	EROSION POTENTIAL	30	
11.3.3	EVALUATION OF THE PROJECT	30	
11.3.4	BEST MANAGEMENT PRACTICE		
11.3.5	EROSION AND SEDIMENT CONTROL PLAN		
11.3.6	IMPLEMENTATION, MONITORING AND REVIEW		
11.3.7	IMPLEMENTATION STRATEGIES	31	
11.3.8	MONITORING REQUIREMENTS	33	
11.3.9	REPORTING	33	
11.3.10	Audit	33	
11.3.11	EMERGENCY PROCEDURES	33	
11.3.12	CORRECTIVE ACTION	33	
	ENVIRONMENTAL SITE INDUCTION		
	ENVIRONMENTAL REPORTING		
11.3.15	Environmental Audits	34	

APPENDIX A – Design Drawings

APPENDIX B – Q100 Sketches

APPENDIX C – Statement of Compliance

APPENDIX D – Hydrological Analysis

APPENDIX E – Hydraulic Analysis

APPENDIX F – Decision Notice

APPENDIX G – EPANet



1 **SUMMARY**

1.1 DEVELOPMENT APPLICATION DETAILS

Proposed development:

Type of approval sought:
Site address:
Real property description:
Site area:
Assessment manager:
Owner details:
Applicant details:

Land development at Wylandra Estate, Mareeba. Works include earthworks, road works, water connections, and stormwater drainage.

Operational Works

Off Wylandra Drive, Mareeba

Lot 224 on SP276715

74,548 m²

Mareeba Shire Council

Conmat Pty Ltd Conmat Pty Ltd

C/-ERSCON PTY. LTD.

PO BOX 7890 CAIRNS QLD 4870

1.2 PLANNING INSTRUMENT DETAILS

Planning scheme:	Mareeba Shire Council Planning Scheme 2016	
Zone:	Medium Density Residential	
Local plan:	Nil	
Level of assessment:	Code Assessment	
Applicable codes:	Nil	

1.3 REFERRAL AGENCIES

Referral agency and role

Nil



2 SITE DETAILS

2.1 SITE DESCRIPTION

The site is located off Wylandra Drive, Mareeba. This application seeks operational works approval to complete construction of a 14-lot land development as approved for re-configuration by Council.

Table 1: Site description

Table 1: Site description				
Site characteristic	Description			
Existing land use	The existing land was used for farming.			
Existing structures	There is an existing intersection with a temporary drainage outlet that flows into the lots. Existing drainage overland drains are also present to the East of the lots.			
Frontage and access	Access will be provided via the new road off Wylandra Drive.			
Topography and views	The elevation change is 7m from RL 461.5m to 454.5m and slopes from the South-East towards the North-West at a grade of 1-2%.			
Existing vegetation	The existing land is predominantly overgrown grassed areas with scattered trees.			
Existing waterways	Drainage pathways are located along the eastern lot boundary and discharge into pathways near the north boundary. These then flow from east to west towards Chinaman Creek and Ray Road.			





Figure 1: Aerial View of Site Identification Source: DA Mapping System




Figure 2: Satellite View of Site Identification Source: QLD Globe



2.2 SURROUNDING LAND USES

Table 2: Surrounding land uses

Surrou	Surrounding land uses						
North	Existing residential area						
South	Airport and Existing residential area						
East	Existing residential area and farmland						
West	Existing residential area						



3 PROPOSED DEVELOPMENT DETAILS

The purpose of this application is the development of 14 new allotments, including all municipal services (excluding sewer) and access road. This stage is designed in accordance with Council's conditions, and relevant specifications and standards.

Table 3: Summary of development aspects

Building or operational work	
Operational work	Construction of 14 new rural residential allotments including roadworks, bulk earthworks, water, and stormwater connections.
Value of proposed work	Approx \$1,062,000



4 DEVELOPMENT APPLICATION FORM 1

DA Form 1 – Development application details

Approved form (version 1.6 effective 2 August 2024) made under section 282 of the Planning Act 2016.

This form **must** be used to make a development application **involving code assessment or impact assessment**, except when applying for development involving only building work.

For a development application involving **building work only**, use *DA Form 2 – Building work details*.

For a development application involving **building work associated with any other type of assessable development** (i.e. material change of use, operational work or reconfiguring a lot), use this form (*DA Form 1*) and parts 4 to 6 of *DA Form 2 – Building work details*.

Unless stated otherwise, all parts of this form **must** be completed in full and all required supporting information **must** accompany the development application.

One or more additional pages may be attached as a schedule to this development application if there is insufficient space on the form to include all the necessary information.

This form and any other form relevant to the development application must be used to make a development application relating to strategic port land and Brisbane core port land under the *Transport Infrastructure Act 1994*, and airport land under the *Airport Assets (Restructuring and Disposal) Act 2008*. For the purpose of assessing a development application relating to strategic port land and Brisbane core port land, any reference to a planning scheme is taken to mean a land use plan for the strategic port land, Brisbane port land use plan for Brisbane core port land, or a land use plan for airport land.

Note: All terms used in this form have the meaning given under the Planning Act 2016, the Planning Regulation 2017, or the Development Assessment Rules (DA Rules).

PART 1 - APPLICANT DETAILS

 \boxtimes No – proceed to 3)

1) Applicant details	
Applicant name(s) (individual or company full name)	Wylandra Properties Pty Ltd
Contact name (only applicable for companies)	
Postal address (P.O. Box or street address)	C/ Freshwater Planning Pty Ltd
	17 Barronview Drive
Suburb	Freshwater
State	QLD
Postcode	4870
Country	Australia
Contact number	0402729004
Email address (non-mandatory)	FreshwaterPlanning@outlook.com
Mobile number (non-mandatory)	
Fax number (non-mandatory)	
Applicant's reference number(s) (if applicable)	F24/20 OPW
1.1) Home-based business	
Personal details to remain private in accordar	nce with section 264(6) of Planning Act 2016
2) Owner's consent	
2.1) Is written consent of the owner required for t	his development application?

Yes – the written consent of the owner(s) is attached to this development application



PART 2 – LOCATION DETAILS

Note: P	ation of the p Provide details be Guide: Relevant	elow and							t application. For further information, see <u>DA</u>
	treet address		ot on pla	in					
	eet address				ots must be liste	d). or			
Street address AND lot on plan for an adjoining or adjacent property of the premises (appropriate for development in water but adjoining or adjacent to land e.g. jetty, pontoon. All lots must be listed).									
	Unit No.	Stree	t No.	Stree	t Name and	Туре			Suburb
- \				Ray	Road				Mareeba
a)	Postcode	Lot N	0.	Plan	Type and Nu	ımber ((e.g. R	P, SP)	Local Government Area(s)
	4880	224		SP27	76715				Mareeba Shire Council
	Unit No.	Stree	t No.	Stree	t Name and	Туре			Suburb
b)	Postcode	Lot N	0.	Plan	Type and Nu	ımber ((e.g. R	P, SP)	Local Government Area(s)
e.	oordinates o g. channel dred lace each set o	ging in N	Noreton B	ay)		nt in rem	note are	as, over part of a	a lot or in water not adjoining or adjacent to land
C	ordinates of	premis	es by lo	ngitud	e and latitud	е			
Longit	ude(s)		Latitud	e(s)		Datum	n		Local Government Area(s) (if applicable)
							GS84		
						GE	DA94		
						Otl	her:		
Co	ordinates of	premis	es by ea	asting	and northing				
Eastin	g(s)	North	ing(s)		Zone Ref.	Datum	n		Local Government Area(s) (if applicable)
					<u>54</u>		GS84		
					<u></u> 55 □		DA94 		
					□ 56	☐ Otl	her:		
	dditional prer								
atta	ditional prem ached in a so t required						plicat	ion and the d	etails of these premises have been
4) Ider	ntify any of th	ne follo	wing tha	at appl	y to the pren	nises ar	nd pro	vide any rele	vant details
☐ In c	or adjacent to	a wat	er body	or wa	tercourse or	in or at	bove a	an aquifer	
Name	of water bod	ly, wat	ercourse	e or ac	juifer:				
On	strategic po	rt land	under th	ne <i>Tra</i>	nsport Infras	tructure	e Act	1994	
Lot on	plan descrip	tion of	strategi	ic port	land:				
	of port author		_	•		-			
	a tidal area								
_	Name of local government for the tidal area (if applicable):								
Name of port authority for tidal area (if applicable)									

On airport land under the Airport Assets (Restructuring	and Disposal) Act 2008
Name of airport:	
☐ Listed on the Environmental Management Register (EM	IR) under the Environmental Protection Act 1994
EMR site identification:	
Listed on the Contaminated Land Register (CLR) under	r the Environmental Protection Act 1994
CLR site identification:	
5) Are there any existing easements over the premises?	
Note: Easement uses vary throughout Queensland and are to be identified how they may affect the proposed development, see <u>DA Forms Guide.</u>	ed correctly and accurately. For further information on easements and
	e included in plans submitted with this development
□ No	

PART 3 – DEVELOPMENT DETAILS

Section 1 – Aspects of development

<u>'</u>	· ·				
6.1) Provide details about the	e first development aspect				
a) What is the type of develo	pment? (tick only one box)				
☐ Material change of use	Reconfiguring a lot	Operational work	☐ Building work		
b) What is the approval type	? (tick only one box)				
□ Development permit	☐ Preliminary approval	Preliminary approval that	t includes a variation approval		
c) What is the level of assess	sment?				
	Impact assessment (requir	res public notification)			
d) Provide a brief description lots):	of the proposal (e.g. 6 unit apart	ment building defined as multi-unit d	welling, reconfiguration of 1 lot into 3		
Construction of a 14 lot Rura	al Residential Subdivision inclu	ıding roads, stormwater and v	vater reticulation.		
e) Relevant plans Note: Relevant plans are required to Relevant plans.	to be submitted for all aspects of this	development application. For further	information, see <u>DA Forms quide:</u>		
Relevant plans of the pro	posed development are attach	ned to the development applic	ation		
6.2) Provide details about the	e second development aspect				
a) What is the type of develo	pment? (tick only one box)				
☐ Material change of use	Reconfiguring a lot	Operational work	☐ Building work		
b) What is the approval type	? (tick only one box)				
Development permit	☐ Preliminary approval	Preliminary approval that	t includes a variation approval		
c) What is the level of assess	sment?				
☐ Code assessment	☐ Impact assessment (require	res public notification)			
d) Provide a brief description lots):	n of the proposal (e.g. 6 unit apart	tment building defined as multi-unit d	welling, reconfiguration of 1 lot into 3		
Relevant plans.	be submitted for all aspects of this c				
Relevant plans of the proposed development are attached to the development application					



	velopment ar		this development applicati		
that would be required u	ınder Part 3 S	Section 1 of	this form have been attache	ed to this development ap	oplication
6.4) Is the application for St	ate facilitated	l developme	ent?		
Yes - Has a notice of de					
⊠ No					
Section 2 – Further deve	lopment de	etails			
7) Does the proposed devel	•		ve any of the following?		
Material change of use	Yes -	- complete d	division 1 if assessable agai	inst a local planning instr	ument
Reconfiguring a lot	Yes -	- complete d	division 2		
Operational work	🛚 Yes -	- complete d	division 3		
Building work	Yes -	- complete <i>l</i>	DA Form 2 – Building work	details	
Division 1 – Material chang	je of use				
Note : This division is only required to local planning instrument.	o be completed i	f any part of the	e development application involves	s a material change of use asso	essable against a
8.1) Describe the proposed	material cha	nae of use			
Provide a general description			e planning scheme definitio	n Number of dwelling	Gross floor
proposed use			h definition in a new row)	units (if applicable)	area (m²) (if applicable)
8.2) Does the proposed use	involve the ι	use of existi	ng buildings on the premise	s?	
Yes					
□ No					
8.3) Does the proposed dev	elopment rel	ate to tempo	orary accepted developmen	t under the Planning Reg	gulation?
Yes – provide details be	low or include	e details in a	schedule to this developm	ent application	
□ No					
Provide a general description	on of the temp	orary acce	oted development	Specify the stated pe	
				under the Planning F	Regulation
D	1.4				
Division 2 – Reconfiguring Note: This division is only required to		only part of the	a development application involved	roconfiguring a lot	
9.1) What is the total number				reconligating a lot.	
		9			
9.2) What is the nature of th	ne lot reconfic	uration? (tic	k all applicable boxes)		
Subdivision (complete 10)			_	by agreement (complete 1	11)
Boundary realignment (c	complete 12)		_	n easement giving acces	
	5/11pi010 12)		from a constructed road		.5 15 4 151



10.1) For this dovolor						
io.i) For this develop	pment, how	many lots are l	being created	d and what	is the intended	use of those lots:
Intended use of lots of	created	Residential	Comm	ercial	Industrial	Other, please speci
Number of lots create	ed					
ن نام طری می داد ۱۵ م	aian ha ata	and?				
0.2) Will the subdivis						
☐ No How many stages wil	ll the works	include?				
Vhat stage(s) will this pply to?						
Dividing land into parts?	parts by a	greement – how	many parts	are being c	reated and wha	at is the intended use of t
ntended use of parts	created	Residential	Comm	ercial	Industrial	Other, please speci
Number of parts crea	atod .					
Number of parts crea	ileu					
2) Boundary realign	ment					
2.1) What are the cu	urrent and	proposed areas	for each lot	comprising	the premises?	
	Current	lot			Pro	posed lot
Lot on plan description Are		roo (m²)	1	Lot on plan description		Area (m²)
ot on plan description	on Ai	rea (m²)	l l	Lot on plan	accomplicit	Alea (III)
ot on plan descriptic	on Ai	ea (III-)	L	Lot on plan	accomplicit	Alea (III)
ot on plan descriptic	on Ai	ea (III-)		Lot on plan	ассоприон	Alea (III)
				or on plan	ассоприон	Alea (III)
Lot on plan description				or on plan	ассоприон	Alea (III)
2.2) What is the rea	son for the	boundary realig	gnment?		·	
2.2) What is the reads (2.2) What is the dim	son for the	boundary realig	gnment?		·	d/or any proposed easem
2.2) What is the readal 3) What are the dimentach schedule if there are existing or	son for the	boundary realig	gnment?	ements beir	ng changed and	
2.2) What is the readant at the dimension at the compart of the co	son for the ensions ar	boundary realig	gnment? existing easo Purpose of the	ements beir	ng changed and	d/or any proposed easem
12.2) What is the read 13) What are the dimental actions are the dimental actions are the dimental actions and the schedule if there are	son for the ensions ar	boundary realig	gnment? existing easo Purpose of the	ements beir	ng changed and	d/or any proposed easem
2.2) What is the readal 3) What are the dimensional schedule if there are existing or roposed?	son for the rensions ar re more than Width (m)	boundary realig	gnment? existing easo Purpose of the	ements beir	ng changed and	d/or any proposed easem
2.2) What is the readal 3) What are the dimensional action of the second and the second are second as a second as a second are second as	son for the mensions ar re more than Width (m) mal work quired to be a	boundary realig	existing ease Purpose of t pedestrian acc	ements beir he easeme	ng changed and	d/or any proposed easent ldentify the land/lot(s) benefitted by the easer
2.2) What is the readable is the schedule if there are the dimensional actions and the schedule if there are the schedule if there are the schedule if there are the schedule if there are the schedule if there are the schedule if there are the schedule if there are the schedule in the s	son for the mensions ar re more than Width (m) mal work quired to be a	boundary realigned nature of any two easements) Length (m) completed if any paraperational work	existing ease Purpose of t pedestrian acc	ements beir he easeme	ng changed and nt? (e.g.	d/or any proposed easem Identify the land/lot(s) benefitted by the easen
2.2) What is the readant attach schedule if there as existing or roposed? Tision 3 – Operation is only readant. This division is only readant. Road work	son for the mensions ar re more than Width (m) mal work quired to be a	boundary realigned nature of any two easements) Length (m) completed if any paraperational work	existing ease Purpose of t pedestrian acc	ements beir he easeme	ng changed and nt? (e.g.	Identify the land/lot(s) benefitted by the easel onal work.
2.2) What is the readant and the schedule if there are reposed? Trision 3 – Operation at the division is only readant. This division is only readant. Road work. Drainage work	son for the mensions ar re more than Width (m) mal work quired to be a	boundary realigned nature of any two easements) Length (m) completed if any paraperational work	existing ease Purpose of to pedestrian account of the developing? Stormwater Earthworks	ements beir he easeme	ng changed and nt? (e.g.	Identify the land/lot(s) benefitted by the easer onal work.
2.2) What is the readable is the readable if there are existing or proposed? Vision 3 — Operation is only readable. This division is only readable. Road work. Road work. Drainage work. Landscaping	son for the rensions are more than Width (m)	boundary realigned nature of any two easements) Length (m) completed if any paraperational work	existing ease Purpose of t pedestrian acc	ements beir he easeme	ng changed and nt? (e.g.	Identify the land/lot(s) benefitted by the easel onal work.
2.2) What is the readable is the readable if there are reposed? vision 3 — Operation is only readable if the nation is only readable. This division is only readable. Road work Drainage work Landscaping Other — please sp	son for the densions are more than Width (m)	boundary realig	existing ease Purpose of the developer? Stormwater Earthworks Signage	ements beir	ng changed and nt? (e.g. on involves operation Water in Sewage Clearing	Identify the land/lot(s) benefitted by the easer onal work.
2.2) What is the readable is the readable if there are existing or proposed? Vision 3 — Operation is only readable. This division is only readable. Road work. Road work. Drainage work. Landscaping	son for the mensions are more than Width (m) which work quired to be a ure of the concepts.	boundary realigned nature of any two easements) Length (m) completed if any parapoperational work	existing ease Purpose of to pedestrian according to the developing? Stormwater Earthworks Signage	ements beir	ng changed and nt? (e.g. on involves operation Water in Sewage Clearing	Identify the land/lot(s) benefitted by the easer onal work.



14.3) What is the monetary value of the proposed operational work? (include GST, materials and labour) \$1,062,000 (Includes GST)

PART 4 – ASSESSMENT MANAGER DETAILS

15) Identify the assessment manager(s) who will be assessing this development application
Mareeba Shire Council
16) Has the local government agreed to apply a superseded planning scheme for this development application?
 Yes – a copy of the decision notice is attached to this development application The local government is taken to have agreed to the superseded planning scheme request – relevant documents attached
⊠ No

PART 5 – REFERRAL DETAILS

17) Does this development application include any aspects that have any referral requirements?
Note: A development application will require referral if prescribed by the Planning Regulation 2017.
No, there are no referral requirements relevant to any development aspects identified in this development application – proceed to Part 6
Matters requiring referral to the Chief Executive of the Planning Act 2016:
☐ Clearing native vegetation ☐ Contaminated land (unexploded ordnance)
Environmentally relevant activities (ERA) (only if the ERA has not been devolved to a local government)
Fisheries – aquaculture
Fisheries – declared fish habitat area
Fisheries – marine plants
Fisheries – waterway barrier works
Hazardous chemical facilities
Heritage places – Queensland heritage place (on or near a Queensland heritage place)
☐ Infrastructure-related referrals – designated premises
Infrastructure-related referrals – state transport infrastructure
☐ Infrastructure-related referrals – State transport corridor and future State transport corridor
☐ Infrastructure-related referrals – State-controlled transport tunnels and future state-controlled transport tunnels
☐ Infrastructure-related referrals – near a state-controlled road intersection
☐ Koala habitat in SEQ region – interfering with koala habitat in koala habitat areas outside koala priority areas
☐ Koala habitat in SEQ region – key resource areas
Ports – Brisbane core port land – near a State transport corridor or future State transport corridor
Ports – Brisbane core port land – environmentally relevant activity (ERA)
Ports – Brisbane core port land – tidal works or work in a coastal management district
Ports – Brisbane core port land – hazardous chemical facility
Ports – Brisbane core port land – taking or interfering with water
Ports – Brisbane core port land – referable dams
Ports – Brisbane core port land – fisheries
Ports – Land within Port of Brisbane's port limits (below high-water mark)
SEQ development area
SEQ regional landscape and rural production area or SEQ rural living area – tourist activity or sport and recreation activity
SEQ regional landscape and rural production area or SEQ rural living area – community activity
SEQ regional landscape and rural production area or SEQ rural living area – indoor recreation
SEQ regional landscape and rural production area or SEQ rural living area – urban activity
SEQ regional landscape and rural production area or SEQ rural living area – combined use
SEQ northern inter-urban break – tourist activity or sport and recreation activity



 □ SEQ northern inter-urban break – community activity □ SEQ northern inter-urban break – indoor recreation □ SEQ northern inter-urban break – urban activity 							
 SEQ northern inter-urban break – combined use Tidal works or works in a coastal management district Reconfiguring a lot in a coastal management district or for a canal Erosion prone area in a coastal management district Urban design 							
☐ Water-related development – removing quarry material☐ Water-related development – referable dams	 Water-related development – taking or interfering with water Water-related development – removing quarry material (from a watercourse or lake) Water-related development – referable dams Water-related development – levees (category 3 levees only) 						
Matters requiring referral to the local government:							
 ☐ Airport land ☐ Environmentally relevant activities (ERA) (only if the ERA II) ☐ Heritage places – Local heritage places 	nas been devolved to local government)						
Matters requiring referral to the Chief Executive of the dis Infrastructure-related referrals – Electricity infrastructure	•	on entity:					
Matters requiring referral to: • The Chief Executive of the holder of the licence, if • The holder of the licence, if the holder of the licence ☐ Infrastructure-related referrals − Oil and gas infrastructure.	is an individual						
Matters requiring referral to the Brisbane City Council: Ports – Brisbane core port land							
Matters requiring referral to the Minister responsible for a Ports – Brisbane core port land (where inconsistent with the land) Ports – Strategic port land							
Matters requiring referral to the relevant port operator , if a Ports – Land within Port of Brisbane's port limits (below to	• • • • • • • • • • • • • • • • • • • •						
Matters requiring referral to the Chief Executive of the rel Ports – Land within limits of another port (below high-water)							
Matters requiring referral to the Gold Coast Waterways A Tidal works or work in a coastal management district (in	_						
Matters requiring referral to the Queensland Fire and Em Tidal works or work in a coastal management district (in		perths))					
40\\\\							
18) Has any referral agency provided a referral response for ☐ Yes − referral response(s) received and listed below are ☐ No							
Referral requirement	Referral agency	Date of referral response					
Identify and describe any changes made to the proposed of referral response and this development application, or inclusive (if applicable).							

PART 6 - INFORMATION REQUEST

19) Information request under the	ne DA Rules							
		sary for this development applic	cation					
 I agree to receive an information request if determined necessary for this development application I do not agree to accept an information request for this development application 								
Note: By not agreeing to accept an information request I, the applicant, acknowledge:								
that this development application will be assessed and decided based on the information provided when making this development application and the assessment manager and any referral agencies relevant to the development application are not obligated under the DA Rules to accept any additional information provided by the applicant for the development application unless agreed to by the relevant parties								
Part 3 under Chapter 1 of the DA	Rules will still apply if the application is a	n application listed under section 11.3	of the DA Rules or					
,	Rules will still apply if the application is fo	r state facilitated development						
Further advice about information reques	sts is contained in the <u>DA Forms Guide</u> .							
PART 7 – FURTHER DI	ETAILS							
20) Are there any associated de	evelopment applications or currer	t approvals? (e.g. a preliminary app	oroval)					
∑ Yes – provide details below	or include details in a schedule to	this development application						
□ No								
List of approval/development application references	Reference number	Date	Assessment manager					
☐ Approval ☐ Development application	RAL/24/0009	28 June, 2024	Mareeba Shire Council					
Approval Development application								
Bevelopment application								
21) Has the portable long service operational work)	ce leave levy been paid? (only app.	icable to development applications inve	olving building work or					
Yes – a copy of the receipted	d QLeave form is attached to this	development application						
assessment manager decide	vide evidence that the portable loes the development application. I	acknowledge that the assessm	nent manager may					
	Il only if I provide evidence that the and construction work is less that	•	evy has been paid					
Amount paid	Date paid (dd/mm/yy)	QLeave levy number (A	A, B or E)					
\$								
22) Is this development applicat notice?	tion in response to a show cause	notice or required as a result o	f an enforcement					
Yes – show cause or enforce	ement notice is attached							
⊠ No								

23) Further legislative requirements					
Environmentally relevant a	ctivities _				
23.1) Is this development application also taken to be an application for an environmental authority for an Environmentally Relevant Activity (ERA) under section 115 of the <i>Environmental Protection Act</i> 1994?					
Yes – the required attachment (form ESR/2015/1791) for an application for an environmental authority accompanies this development application, and details are provided in the table below					
⊠ No					
	tal authority can be found by searchir to operate. See <u>www.business.qld.gc</u>	ng "ESR/2015/1791" as a search term ov.au for further information.	at <u>www.qld.gov.au</u> . An ERA		
Proposed ERA number:		Proposed ERA threshold:			
Proposed ERA name:					
☐ Multiple ERAs are applicable to this development application and the details have been attached in a schedule to this development application.					
Hazardous chemical faciliti	<u>es</u>				
23.2) Is this development app	lication for a hazardous che	mical facility?			
Yes – Form 536: Notification	on of a facility exceeding 10%	% of schedule 15 threshold is a	ttached to this development		
No No					
	for further information about hazardo	ous chemical notifications.			
Clearing native vegetation					
23.3) Does this development application involve clearing native vegetation that requires written confirmation that the chief executive of the <i>Vegetation Management Act 1999</i> is satisfied the clearing is for a relevant purpose under section 22A of the <i>Vegetation Management Act 1999</i> ?					
☐ Yes – this development ap Management Act 1999 (s: ☐ No	- -	firmation from the chief execu	tive of the Vegetation		
 Note: 1. Where a development application for operational work or material change of use requires a s22A determination and this is not included the development application is prohibited development. 2. See https://www.qld.gov.au/environment/land/vegetation/applying for further information on how to obtain a s22A determination. 					
Environmental offsets					
		ped activity that may have a signal Offsets Act 2014?	gnificant residual impact on		
Yes – I acknowledge that an environmental offset must be provided for any prescribed activity assessed as having a significant residual impact on a prescribed environmental matter					
Note: The environmental offset section environmental offsets.	on of the Queensland Government's	website can be accessed at www.qld	<u>.gov.au</u> for further information on		
Koala habitat in SEQ Regio	<u>n</u>				
23.5) Does this development application involve a material change of use, reconfiguring a lot or operational work which is assessable development under Schedule 10, Part 10 of the Planning Regulation 2017?					
 ☐ Yes – the development application involves premises in the koala habitat area in the koala priority area ☐ Yes – the development application involves premises in the koala habitat area outside the koala priority area 					
No Note: If a koala habitat area determination has been obtained for this premises and is current over the land, it should be provided as part of this development application. See koala habitat area guidance materials at www.desi.gld.gov.au for further information.					



23.6) Does this development application involve taking or interfering with underground water through an artesian or subartesian bore, taking or interfering with water in a watercourse, lake or spring, or taking overland flow water under the <i>Water Act 2000</i> ?
 Yes – the relevant template is completed and attached to this development application and I acknowledge that a relevant authorisation or licence under the <i>Water Act 2000</i> may be required prior to commencing development No
Note: Contact the Department of Resources at www.resources.gld.gov.au for further information.
DA templates are available from <u>planning.statedevelopment.qld.gov.au</u> . If the development application involves:
 Taking or interfering with underground water through an artesian or subartesian bore: complete DA Form 1 Template 1 Taking or interfering with water in a watercourse, lake or spring: complete DA Form1 Template 2 Taking overland flow water: complete DA Form 1 Template 3.
<u>Waterway barrier works</u> 23.7) Does this application involve waterway barrier works?
☐ Yes – the relevant template is completed and attached to this development application☒ No
DA templates are available from <u>planning.statedevelopment.qld.qov.au</u> . For a development application involving waterway barrier works, complete DA Form 1 Template 4.
Marine activities
23.8) Does this development application involve aquaculture, works within a declared fish habitat area or removal, disturbance or destruction of marine plants?
 Yes – an associated resource allocation authority is attached to this development application, if required under the Fisheries Act 1994 No
Note: See guidance materials at www.daf.qld.gov.au for further information.
Quarry materials from a watercourse or lake
23.9) Does this development application involve the removal of quarry materials from a watercourse or lake under the <i>Water Act 2000?</i>
☐ Yes – I acknowledge that a quarry material allocation notice must be obtained prior to commencing development ☐ No
Note: Contact the Department of Resources at www.resources.gld.gov.au and www.business.gld.gov.au for further information.
Quarry materials from land under tidal waters
23.10) Does this development application involve the removal of quarry materials from land under tidal water under the <i>Coastal Protection and Management Act 1995?</i>
☐ Yes – I acknowledge that a quarry material allocation notice must be obtained prior to commencing development ☐ No
Note: Contact the Department of Environment, Science and Innovation at www.desi.gld.gov.au for further information.
Referable dams
23.11) Does this development application involve a referable dam required to be failure impact assessed under section 343 of the <i>Water Supply (Safety and Reliability) Act 2008</i> (the Water Supply Act)?
Yes – the 'Notice Accepting a Failure Impact Assessment' from the chief executive administering the Water Supply Act is attached to this development application
No Note: See guidance materials at www.resources.gld.gov.au for further information.

Water resources



Tidal work or development within a coastal management district					
23.12) Does this development application involve tidal work or development in a coastal management district?					
 Yes – the following is included with this development application: □ Evidence the proposal meets the code for assessable development that is prescribed tidal work (only required if application involves prescribed tidal work) □ A certificate of title ☑ No Note: See guidance materials at www.desi.qld.gov.au for further information. 					
Queensland and local heritage places					
23.13) Does this development application propose development on or adjoining a place entered in the Queensland heritage register or on a place entered in a local government's Local Heritage Register? Yes – details of the heritage place are provided in the table below					
Note: See guidance materials at www.desi.qld.gov.au for information requirements regarding development of Queensland heritage places. For a heritage place that has cultural heritage significance as a local heritage place and a Queensland heritage place, provisions are in place under the Planning Act 2016 that limit a local categorising instrument from including an assessment benchmark about the effect or impact of, development on the stated cultural heritage significance of that place. See guidance materials at www.planning.statedevelopment.qldgov.au for information regarding assessment of Queensland heritage places.					
Name of the heritage place: Place ID:					
Decision under section 62 of the Transport Infrastructure Act 1994					
23.14) Does this development application involve new or changed access to a state-controlled road?					
 Yes – this application will be taken to be an application for a decision under section 62 of the <i>Transport Infrastructure Act 1994</i> (subject to the conditions in section 75 of the <i>Transport Infrastructure Act 1994</i> being satisfied) No 					
Walkable neighbourhoods assessment benchmarks under Schedule 12A of the Planning Regulation					
23.15) Does this development application involve reconfiguring a lot into 2 or more lots in certain residential zones (except rural residential zones), where at least one road is created or extended?					
 Yes – Schedule 12A is applicable to the development application and the assessment benchmarks contained in schedule 12A have been considered No Note: See guidance materials at www.planning.statedevelopment.gld.gov.au for further information. 					
PART 8 – CHECKLIST AND APPLICANT DECLARATION					
24) Development application checklist					
I have identified the assessment manager in question 15 and all relevant referral requirement(s) in question 17 Note: See the Planning Regulation 2017 for referral requirements					
If building work is associated with the proposed development, Parts 4 to 6 of <u>DA Form 2 – Building work details</u> have been completed and attached to this development application Yes Not applicable					
Supporting information addressing any applicable assessment benchmarks is with the development application					
Note: This is a mandatory requirement and includes any relevant templates under question 23, a planning report Yes					

schemes, State Planning Policy, State Development Assessment Provisions). For further information, see DA

Note: Relevant plans are required to be submitted for all aspects of this development application. For further

The portable long service leave levy for QLeave has been paid, or will be paid before a

Relevant plans of the development are attached to this development application

Forms Guide: Planning Report Template.

information, see <u>DA Forms Guide: Relevant plans.</u>

development permit is issued (see 21)



☐ Yes

25) Applicant declaration				
25) Applicant declaration				
By making this development appropriet	plication, I declare that all in	nformation in this development	application is true and	
Where an email address is provided in Part 1 of this form, I consent to receive future electronic communication from the assessment manager and any referral agency for the development application where written informati is required or permitted pursuant to sections 11 and 12 of the <i>Electronic Transactions Act 2001</i>				
Note: It is unlawful to intentionally provide fa				
Privacy – Personal information col assessment manager, any relevant which may be engaged by those er All information relating to this devel published on the assessment manapersonal information will not be dis Regulation 2017 and the DA Rules such disclosure is in accordance Act 2016 and the Planning Regulation 2017; or required by other legislation (incompublic Records Act 2002.	t referral agency and/or buintities) while processing, as lopment application may be ager's and/or referral agency closed for a purpose unrelative except where: we with the provisions about ulation 2017, and the accessibilities and the Right to Information 2019.	Iding certifier (including any prosessing and deciding the development and public available for inspection and public where the Planning Act 2016, For public access to documents costs rules made under the Planning action Act 2009); or	fessional advisers forment application. Urchase, and/or Planning Intained in the Planning and Act 2016 and	
ART 9 – FOR COMPLET JSE ONLY	TION OF THE ASSI	ESSMENT MANAGER	– FOR OFFICE	
Date received:		A. [
Date received.	Reference number(s	5):		
Date received.	Reference number(s	5):		
Notification of engagement of altern	,	,		
	,	,		
Notification of engagement of altern	native assessment manage	,		
Notification of engagement of altern	native assessment manage	,		
Notification of engagement of altern Prescribed assessment manager Name of chosen assessment mana	native assessment manage	,		
Notification of engagement of alternative Prescribed assessment manager Name of chosen assessment manager Date chosen assessment manager	native assessment manage ager engaged ment manager	,		
Notification of engagement of alternative Prescribed assessment manager Name of chosen assessment manager Date chosen assessment manager Contact number of chosen assessment manager Relevant licence number(s) of chosen	native assessment manage ager engaged ment manager	,		
Notification of engagement of alternative Prescribed assessment manager Name of chosen assessment manager Date chosen assessment manager Contact number of chosen assessment manager Relevant licence number(s) of chosen	native assessment manager ager r engaged ment manager sen assessment	,		
Notification of engagement of alternative Prescribed assessment manager. Name of chosen assessment manager. Date chosen assessment manager. Contact number of chosen assessment manager. Relevant licence number(s) of chosen manager. QLeave notification and payment.	native assessment manager ager r engaged ment manager sen assessment	,		
Notification of engagement of alternative Prescribed assessment manager. Name of chosen assessment manager. Date chosen assessment manager. Contact number of chosen assessment manager. Relevant licence number(s) of chosen manager. QLeave notification and payment. Note: For completion by assessment manager.	native assessment manager ager r engaged ment manager sen assessment	,		
Notification of engagement of alternative Prescribed assessment manager Name of chosen assessment manager Date chosen assessment manager Contact number of chosen assessment manager Relevant licence number(s) of chosen and payment Mote: For completion by assessment manager Description of the work	native assessment manager ager engaged ment manager sen assessment	,		

Name of officer who sighted the form



5 SUBDIVISION CONDITIONS



6 STORMWATER DRAINAGE

6.1 DESIGN METHOD

The stormwater design has been carried out using the Rational Method, in accordance with the Queensland Urban Drainage Manual (QUDM). Rainfall values from FNQROC Development Manual D4 (05/23) have been utilised. The majority of the hydrological and hydraulic computations undertaken during the development of the stormwater drainage system have been performed utilising the stormwater design module of Version 14 of 12d Model.

In accordance with the QUDM recommendations, the major system design has been calculated based on a 100-year recurrence interval, using a combination of underground and overland flow. Minor flows in rural residential streets are carried entirely by the underground pipe system, which is designed based on a 5-year recurrence interval, in accordance with the requirements of QUDM and FNQROC. Road crossings have been designed to a 10-year recurrence interval for rural areas in accordance with QUDM and FNQROC.

Runoff has been calculated using Rainfall intensities that have been obtained from FNQROC Development Manual - D4 **Stormwater Drainage** - Chart 18 and checked against the Australian Government's - Bureau of Meteorology - Design Rainfall Data System (2016) for the area.

Gully pit capacities have been estimated using FNQROC Section D4 Appendix B "Kerb Inlet Capacity Charts". Roadway flow widths have been calculated using Manning's equation for both major and minor flows.

As a rural residential subdivision, pits have been spaced at intervals to ensure road flows do not exceed the reserve, typical of the adjacent development.

6.2 MINOR DRAINAGE

6.2.1 Hydrological Design Philosophy

The minor drainage system consists of a combination of grass open drains and underground drainage infrastructure consisting of pits and pipes.

The major drainage system involves overland flow on both the street surfaces, open drains and underground system. The major drainage system has a capacity of Q100 plus 300mm freeboard, as required by QUDM.

6.2.2 Hydrological Analysis

12d Model requires various data to be input by the operator for it to perform hydrological computations as detailed below.

Coefficients of Runoff have been determined in accordance with Section 5.04 of QUDM assuming an Urban Residential Development Category. Rainfall intensities have been obtained from the Australian Government's - Bureau of Meteorology - Design Rainfall Data System (2016) for the area.



Times of Concentration have been determined in accordance with Section 4.6.11 of QUDM, specifically the Recommended Standard Inlet Times detailed in Table 4.6.2. Larger catchment Tc has been calculated on an average slope calculation using the Bransby- Williams' equation in accordance with QUDM.

The Hydrological Analysis for a Q5 and Q100 event have been undertaken including pit flow, catchment, bypass and flow widths for the pit layout are shown in the calculation tables contained in Appendix C. Stormwater longitudinal sections showing pipe grades and a graphical representation of the Hydraulic Grade Line are referred to in **Appendix A**.

Results of the Hydraulic Analysis of the stormwater drainage system including pit and pipe head losses and pipe discharge are detailed in the calculation tables contained in **Appendix E**.

Pipe sizes and invert levels have been determined through the utilisation of 12d Model with the stipulation of a minimum pipe cover of 600mm. The K values utilised by 12d Model in the determination of pit head losses are based on the QUDM K value charts from Table 7.16.5.

6.3 MAJOR DRAINAGE

6.3.1 Overland Flow

In accordance with the requirements of QUDM, the major drainage system, which incorporates overland flow from the cane fields to the south, along the street network and open drains, has been designed for a recurrence interval of 100 years. A portion of the total runoff will be carried by the minor drainage system in the underground pipes and the remainder of the runoff is conveyed by the streets and park drains to the lawful point of discharge.

Depth by velocity calculations for half the road flow have been undertaken and all pits produce satisfactory results regarding pedestrian safety (dv < 0.6m²/s).

6.3.2 Flood Immunity

The open drains have been designed to have the capacity to accept a 1% AEP (1 in 100 ARI) with 300mm freeboard. This ensures that a Q100 flood event is below the floor level of residences.

The minor stormwater network can contain a 18% AEP (1 in 5 ARI) with adequate freeboard to the invert. The 1% AEP (1 in 100 ARI) has acceptable flooded widths of the road network and diverts excess flows to the open drains. Refer to **Appendix B** for flooded width plans for Q100 event.

6.4 STORMWATER OUTLETS

Stormwater outlets have been designed to be in council owned land (drainage easements). Outlets have been designed to have outlet scour protection and energy dissipation through rock outlet pads. The outflow from the drains will be directed towards the north-west where it is anticipated future stages will incorporate Detention Basins.



Upstream flows have been calculated for the existing channels and crossroad drainage culverts to ensure the existing drains have capacity for these flows and minimise the risk of disturbance to property.

Rear of allotment cut off drains have been designed to direct existing overland flows adjacent Stage 1 into the existing open drain system.

6.5 WATER QUALITY

The design addresses the "State Planning Policy 4/10 Healthy Waterways" as below:

Part A – Urban Stormwater Management

Protecting Water Quality

Performance Outcome P01

The development is compatible with the land use constraints of the site for achieving stormwater design objectives.

Acceptable outcome A01.1

The nature, design and stormwater management of the development is in accordance with design objectives stated in Chapter 4 (section 4.9) of the State Planning Policy Guideline for Healthy Waters (the guideline)

And

Prepare a site stormwater quality management plan (SQMP) that:

- a. Is consistent with any local area stormwater management planning;
 and
- b. Provides for achievable stormwater quality treatment measures reflecting land use constraints, such as soil type, landscape features (including landform), nutrient hazardous areas, acid sulfate soil, and rainfall erosivity.

Outcome achieved – Stormwater design has been undertaken to incorporate as much of the existing flow paths and dams as practical. All stormwater outlets are directed towards or directly into existing stormwater drainage paths/gullies. Stormwater flows exiting pipe networks have been designed with outlet scour and energy dissipation to reduce velocities to minimise impacts to existing ground. Previous development has shown that outlet drains have naturally re-vegetated to provide additional protection.



The entry of contaminants into, and transport of contaminants, in stormwater is avoided and minimized.

Acceptable outcome A02.1

Any development application incorporates:

- Stormwater management measures to achieve relevant design objectives outlined in Chapter 4 of the guideline
- Management of nutrients of concern and acid sulfate soils.

And

Prepare a site stormwater quality management plan (SQMP) that:

- a. Accounts for development type, construction phase, local landscape, climatic conditions and design objectives in accordance with the guideline; and
- b.Is consistent with the Queensland Acid Sulfate Soil Technical Manual.

Outcome achieved – The site is not expected to be subject to Acid Sulfate Soils. Should Acid Sulfate Soils be encountered, appropriate measures will be undertaken in accordance with Queensland Acid Sulfate Soil Technical Manual. An appropriate Erosion and Sediment Control (ESC) plan will be implemented during and post construction as part of the SQMP.

Performance Outcome P03

Construction activities for the development avoid or minimize adverse impacts on stormwater quality.

Acceptable outcome A03.1

Any development application for the development is accompanied by an erosion and sediment control plan (ESCP) prepared in accordance with the guideline that demonstrates release of sediment laden stormwater is avoided for the nominated design storm, and minimized when the nominated design storm is exceeded by addressing design objectives in the guideline, Chapter 4, for:

- · Drainage control;
- Erosion control;
- Sediment control: and
- Water quality outcomes.



Addressing the design objectives may include enhancing the achievement of some objectives if achievement of other objectives is impractical.

And

Acceptable outcome A03.2

Erosion and sediment control practices including any proprietary erosion and sediment control products are designed, installed, constructed, operated, monitored and maintained, and any other erosion and sediment control practices are carried out, in accordance with local conditions and appropriate recommendations from a suitable qualified person.

0

The ESCP demonstrates how stormwater quality will be managed in accordance with an acceptable regional or local guideline so that target contaminants are treated to a design objective at least equivalent to Acceptable Outcome A03.1

Outcome achieved - An appropriate Erosion and Sediment Control (ESC) plan will be implemented during and post construction as part of the SQMP. The ESC is designed for the application of best practices to erosion and sediment control during and post construction. Stormwater flows exiting pipe networks have been designed with outlet scour and energy dissipation to reduce velocities to minimize impacts to existing ground.

Protection of Natural flows

Performance Outcome P04

Construction and operation activities for the development avoid or minimize changes to waterway hydrology from adverse impacts of altered stormwater quality and flow.

Acceptable outcome A04.1

Development incorporates stormwater flow control measures to achieve at least the design objectives set out in Chapter 4 of the guideline. Both the construction and operational phases for the development comply with advice and the design objectives in Chapter 4 of the guideline including management of frequent flows, peak flows, and construction phase hydrological impacts.

Outcome achieved – Stormwater flows have been designed to be directed to existing stormwater flow paths, with post-development catchments remaining similar to pre-



development. Stormwater outlets have been designed with energy dissipation to reduce velocities of flows out letting from piped networks. The existing flow regime to existing dams is generally unchanged.

Part C – Non-tidal artificial waterways ('the waterway')

Protecting Water Quality in existing natural waterways

Performance Outcome P01

The waterway is not designed only for stormwater flow management or stormwater quality management.

Acceptable outcome A01.1

The waterway is designed and managed for any of the following end use purposes:

- Amenity including aesthetics, landscaping, and recreation;
- · Flood management;
- Stormwater harvesting as part of an integrated water cycle management plan;
- · Aquatic habitat.

And

The end use purpose is designed and operated in a way that protects water environmental values.

Outcome achieved – The waterway end use purposes have not changed from the predevelopment case. Flows that were directed towards the existing dams in the predevelopment case are still current post-development. Flows to the larger gullies also remain generally the same. No new dams are proposed as part of the development, and no flows to existing flow paths are proposed to be significantly altered.



The waterway is located in a way that is compatible with the land use constraints of the site for protecting water environmental values in existing natural waterways.

Acceptable outcome A02.1

Where relevant:

- a. Environmental values in downstream waterways are protected;
- b. Any groundwater recharge areas are not affected;
- c. The location of the waterway incorporates low lying areas of a catchment connected to an existing waterway;
- d. Any existing areas of ponded water are included.

And

Acceptable outcome A02.2

Waterways are located:

- a. Outside natural wetlands and any associated buffer areas; and
- b. To avoid disturbing soils or sediments and
- c. To avoid altering the natural hydrologic regime in acid sulfate soil and nutrient hazardous areas.

Outcome achieved – The catchments and flow directions on site remain generally the same between pre and post development. No additional dams are proposed, with the existing gullies being maintained toward existing dams and piped flows out letting to these. The larger gullies are also maintained with piped networks out letting toward these.



The waterway is located in a way that is compatible with existing tidal waterways.

Acceptable outcome A03.1

Where the waterway is located adjacent to, or connected to, a tidal waterway by means of a weir, lock, pumping system or similar:

- a. There is sufficient flushing or a tidal range of >0.3m; or
- b. Any tidal flow alteration does not adversely impact on the tidal waterway; or
- c. There is no introduction of salt water into freshwater environments.

Outcome achieved – Not adjacent tidal waterways.

Performance Outcome P04

The construction phase for the waterway is compatible with protecting water environmental values in existing natural waterways.

Acceptable outcome A04.1

Erosion and sediment control measures are incorporated during construction to achieve design objectives set out in Chapter 4 of the guideline.

Outcome achieved – Erosion and sediment control has been designed in accordance with best practices. The construction contractor will also be responsible for preparing an erosion and sediment control plan in reference to the civil design ESC to ensure appropriate controls are in place during and after construction.

Performance Outcome P05

Stormwater overflows from the waterway provide for the achievement of water quality objectives in existing natural waterways

Acceptable outcome A05.1

Stormwater run-off that may enter the nontidal waterway is pre-treated in accordance with the guideline design objectives, water quality objectives of local waterways, and any relevant local area stormwater management plan.

Outcome achieved – Stormwater has been designed to be captured and conveyed to the existing stormwater flow paths as per previous stages of the development. Run-off quality is enhanced by large areas of natural grass and vegetation to prevent sediment runoff.

Designing, managing and operating the non-tidal artificial waterway



The waterway is designed, managed and operated by suitably qualified persons.

Acceptable outcome A06.1

To help achieve water quality objectives in and downstream of the waterway, the waterway is designed, constructed and managed under the responsibility of a suitably qualified registered professional engineer, Queensland with specific experience in establishing and managing artificial waterways.

Outcome achieved – No additional artificial waterways are to be constructed as part of the works. Flows to existing artificial waterways and drainage paths have been designed under the responsibility of an RPEQ.

Performance Outcome P07

The waterway Is managed and operated in ways that demonstrate achievement of water quality objectives in natural waterways.

Acceptable outcome A07.1

Monitoring and maintenance programs adaptively manage water quality in the waterway to achieve relevant water quality objectives downstream of the waterway.

And

Acceptable outcome A07.2

Aquatic weeds are managed in ways that achieve a low percentage of coverage of the water surface area (less than 10%). Pests and vectors (such as mosquitoes) are managed such as by avoiding stagnant water areas, providing for native fish predators, and if necessary, other best practices for monitoring and treating pests.

And

Acceptable outcome A07.3

The waterway is managed and operated by a responsible entity under agreement for the life of the waterway.

The responsibility entity is to implement a deed of agreement for the management and operation of the waterway that:

- a. Identifies the waterway;
- b. States a period of responsibility for the



- entity for the management and operation of the waterway;
- c. States a process for any transfer of responsibility for the waterway;
- d. States required actions under the agreement for monitoring of the water quality of the water and receiving waters;
- e. States required actions under the agreement for maintaining the waterway to achieve the outcomes of this policy and any relevant approval conditions of the development; and
- f. Identifies funding sources for the above including bonds, headworks charges or levies.

Outcome achieved – No additional artificial waterways are to be constructed as part of the works. Existing flow paths remain in place post development and no significant catchment changes are proposed.

6.6 DETENTION BASIN

Since our initial submission of the Stormwater Plan as part of the Operational Works package in June 2024, we have been requested by Council to do further investigations into downstream capacities. We have supplied different options for containing and directing overland flow towards either Coolamon Close or Chinaman Creek Drainage Easements.

On Council's recommendation we were asked to provide a "no worsening" effect on the downstream properties of our development. We have provided a temporary Detention Basin downstream of the Stage 1 works. Specifications and calculations for this basin have been provided in the Stormwater Management Plan.



7 POTABLE WATER RETICULATION

7.1 DESIGN METHOD

All reticulation mains have been designed in accordance with the FNQROC Development Manual for 500 litres/person/day as follows:

• Single Family Dwelling (>1500 m²) = 3.7 EP/Connection

• Average Day Consumption (AD) = 1,850 L/day

• Mean Day Maximum Month (MDMM) = 1.5 x AD = 2,775 L/day

• Maximum Day $= 2.25 \times AD = 4,163 \text{ L/day}$

• Maximum Hour = 1/12 MD = 347 L/hour

= 0.0964 L/s

The following design criterion was assessed:

• Pressure in system to remain above 22m and below 60m during Maximum Hour Demand.

• Pressure in system to remain above 12m during firefighting flows of 15 L/s.

7.2 GENERAL LAYOUT

7.2.1 Alignment

Water mains have been designed on an alignment of 2.0m from the RP boundary as per the Mareeba Shire requirement in Table D6.2 of the FNQROC Development Manual.

7.2.2 Cover

The minimum cover for mains located on the footpath is 600mm and 800mm for a road crossing, whilst complying with a maximum of 1200mm.

The minimum separation between the water main and other services is as follows:

Minimum Clearance for Water Mains ≤ 300mm diameter

Service	Horizontal Clearance (mm)	Vertical Clearance (mm)
Ergon	500	225
Telstra	300	150
Stormwater	300	150
Sewer	1000	500
Water Crossing	300	150

^{*}Based on WSA 03 Table 4.1



7.2.3 Fittings

Road crossings shall be DICL with a minimum diameter of 100mm.

Rider Mains

Properties located on the opposite side of the road to the water main are serviced by a DN63mm MDPE pipe to serve a maximum of 15 allotments.

Hydrants

Fire hydrants shall be located opposite RP boundaries at a maximum spacing of 80m and shall be located on mains 100mm dia. or greater only.

Valves

Valves are installed throughout the system to provide minimum disturbance during maintenance. The maximum number of houses inconvenienced is no greater than 15.

7.3 DESIGN

EPA Net modelling was carried out using the above design information and parameters. Two models were assessed (refer **Appendix G**), the first model simulated Maximum Hour demand "MH", and the second model simulating the system under Fire Fighting conditions "FF". Both EPA Net models used a water supply 'reservoir' with a Head of 35 metres to represent the pressure in the existing 300mm diameter trunk main, this conservative estimate reflects pressure testing conducted at 9 Hellcat Close refer to (**Appendix G**).

The EPA Net simulations confirm all required pressures have been comfortably achieved in the two Stage 1 model scenarios. Preliminary assessment of future stages show there is acceptable capacity in the supply network.

The water main reticulation layout is detailed in the Operational Works drawings. Water Reticulation EPANET calculations are provided in **Appendix G**.

7.3.1 Maximum Hour Demand

The local water network has been modelled with the proposed network and demands added. The network shows that the network complies with pressures between the minimum 22m and maximum 60m pressure requirements at maximum hour demand, in both the interim & ultimate development cases.

7.3.2 Fire Fighting Demand

The assessment undertaken as part of the design works shows that the network is able to operate at the minimum required pressure head of 12m at 15L/s flow, in both the interim & ultimate development cases. With future network upgrades planned for the water reticulation network in the area, this will only further improve the serviceability beyond the minimum as these are undertaken.



8 SEWERAGE RETICULATION

The proposed rural residential lots are to be serviced by on-site effluent disposal systems that are to be approved on a lot-by-lot basis at the time of construction.



9 ROAD PAVEMENT DESIGN

All roadway pavements have been designed in accordance with the FNQROC Development Manual section D3 – Road Pavements.

9.1 DESIGN METHOD

9.1.1 Design Life

A Design Life of 20 years has been adopted for all streets and roads.

9.1.2 Subgrade

California Bearing Ratio (CBR) testing has not been completed as part of the design. The CBR testing is to be evaluated prior to construction by in situ CBR, and 4-day soaked CBR by a NATA registered materials testing authority using the procedures described by the Department of Main Roads and Standards Association of Australia. A value of 7% has been adopted for design purposes.

9.1.3 Flexible Pavement Design

In accordance with Table D3.1 of the FNQROC Development Manual the minimum allowable traffic loading for each pavement type has been reviewed and, in each case, the allowable traffic exceeds the minimum allowable.

The road classification is "Low Density Rural Road" which allows for a sealed carriageway, kerb and channel, and verge. The road reserve width is nominally 20.0m. Table D3.2 of the FNQROC Development Manual requires a minimum pavement thickness of 200mm and a minimum surfacing of 30mm AC.

A copy of the pavement design standard drawings is contained within **Appendix A**.



10 ELECTRICAL, COMMUNICATIONS, AND GAS RETICULATION

Ergon Energy and Telstra have been approached to supply conditions and conduit drawings by the electrical consultant.

There is no provision for gas in this subdivision.



11 SOIL AND WATER MANAGEMENT

A Soil and Water Management Strategy (SWMS) has been produced that identifies policies and development conditions relevant to the site and recommend measures required to satisfy those requirements. In accordance with the FNQROC Section D5. The strategy consists of:

- A Concept Report that identifies the constraints of the site and recommends measures to address those constraints; and
- Soil and Water Management Plan (SWMP) providing measures that can be adopted to address those constraints.

The following documents have been referenced in preparing this SWMP:

- ERSCON Pty Ltd construction drawings;
- FNQROC Development Manual;
- IEAust Soil Erosion and Sediment Control Guidelines;
- NSW DLWC Construction and Sediment Control (Course Notes);
- Queensland Urban Drainage Manual; and
- Australian and New Zealand Guidelines for Freshwater and Marine Water Quality.

11.1 EROSION AND SEDMENT CONTROL STANDARDS

11.1.1 Duty of Care

In accordance with the Environmental Protection Act, 1994 (the Act), all Queenslanders have a legal duty to take all reasonable and practicable measures to minimise or prevent environmental harm.

In accordance with the Integrated Planning Act, 1997, it is a requirement to comply with Council's Planning Scheme and conditions issued in Development Permits.

This SWMP considers environmental harm caused by sediment-laden runoff from the subject site entering stormwater drains and/or waterways.

11.2 CONCEPT REPORT

11.2.1 Site Conditions

The subject site is currently generally well vegetated with medium slopes.

11.2.2 Control Measures

Erosion and sediment control measures are to be designed and constructed in accordance with the FNQROC Development Manual. Specific requirements are provided on drawing 160-001-C118 - C120.



11.2.3 Water Quality Strategy

In accordance with the requirements of the Queensland Urban Drainage Manual, management of water quality involves:

- Identifying and enhancing environmental values;
- Establishing objectives to achieve the required level of protection;
- Establishing water quality management strategies;
- Monitoring and surveillance programs;
- · Research.

11.2.4 Water Quality Monitoring

The soil and water management strategy requires water sampling 50m downstream of the point where stormwater drainage discharges. Sampling is required only after significant rainfall i.e. 10mm.

11.3 EROSION AND SEDIMENT CONTROL PLAN

Erosion and sediment control measures are to be designed and constructed in accordance with the FNQROC Development Manual, as detailed in the Soil and Water Management Strategy, and 160-001-C118-119 "Erosion and Sediment Control Plan" and 160-001-C120 "Erosion and Sediment Control Notes".

The Contractor shall take all reasonable precautions to minimise erosion and prevent sediment-laden runoff from leaving the site. This goal will be monitored to ensure minimal erosion on site and no visible siltation of waterways by implementing effective erosion and sediment control.

The purpose of this SWMP is to ensure the Contractor meets the following objectives:

- Comply with all relevant legislation;
- Ensure erosion and sedimentation is controlled in an appropriate and cost-effective manner:
- Maintain and if possible, enhance the existing environment;
- Reinforce and improve environmental awareness within the workforce and the general community.



11.3.1 Environmental Responsibilities of Key Staff

Inspection Officer

The Inspection Officer is to be nominated by the Contractor.

Project Manager (PM)

The Project Manager will be responsible for:

- Coordinating the response to any major environmental incident and reporting serious or material harm to the Inspection Officer, Council, EPA and/or other agencies as appropriate;
- Monitoring, review and continuous improvement of the SWMP;
- Assess the need and if required ensure the proper completion of all internal and subcontractor audits;
- Ensuring compliance of construction activities with the EP Act and other relevant legislation, codes and specifications;
- Liaison with all external authorities and stakeholders;
- Investigating and addressing complaints in the shortest possible time frame;
- Ensuring appropriate document control is maintained and;
- Supporting and providing advice to the project team.

Contractor Environmental Representative (CER):

The Contractors Environmental Representative will be responsible for:

- The implementation and operation of the environmental control measures as detailed in the SWMP:
- Monitoring the effectiveness of control measures;
- Recording and reporting non-conformances to the SWMP;
- · Recording and reporting environmental complaints and incidents;
- Advising the PM and Inspection Officer of all environmental issues;
- Ensuring all staff on-site receive an appropriate environmental induction;
- Taking all reasonable and practical measures to prevent or minimise environmental harm occurring at jobsites under his/her supervision and;
- Seeking advice from the Project Manager if uncertain of environmental requirements.

Works Supervisor (WS):

The Works Supervisor will assist the CER in the implementation of the SWMP, and the ongoing awareness of environmental issues for the Construction Workforce. The overseer shall:

- Have a full understanding of the SWMP;
- Be fully aware of all environmental issues associated with the project; and
- Be responsible for the maintenance of control measures.


Construction Workforce:

Each member of the construction workforce will be responsible for:

- Ensuring they have a full understanding of their own environmental responsibilities;
- Assist in the implementation and maintenance of environmental protection measures in accordance with the SWMP and as directed by the CER; and
- Immediately reporting environmental complaints and incidents to the Environmental Supervisor.



Environmental Organisation Structure





11.3.2 Erosion Potential

Observations from site inspections concur that the risk of sediment laden runoff leaving site is low. The site is naturally well vegetated.

Short sharp rainfall events will create silt/sediment that can be trapped on site. In the event of catastrophic failure of sediment control structures (due to vandalism or other undefined event) clean up operations would quickly mitigate the impacts.

The risk of long-term environmental impacts due to sedimentation from the proposed works is considered very low if the SWMP is fully implemented.

11.3.3 Evaluation of the Project

Investigation into erosion and sedimentation control has been reviewed as follows:

Timing of the Works:

Construction works are will be timed to coincide with a moderate to low rainfall month. Stormwater and sewer works will be constructed first which provide a low risk in terms of erosion and sediment control. Once these works are completed, an assessment of the potential rainfall will be made in consultation with Council to determine if bulk earthworks and road construction will proceed immediately after.

Works Program:

It is expected the works will be completed as follows:

- Approval to proceed;
- Install erosion sediment control devices and site facilities;
- Strip and grub;
- Install Services;
- Commence bulk earthworks (after assessment of potential rainfall);
- Construct Roads;
- Turf batters;
- · Grass footpath and other exposed areas;
- · Complete works; and
- Hand over.

11.3.4 Best Management Practice

The review of this site has been made in conjunction with the Institute of Engineers Australia "Soil Erosion and Sediment Control Guidelines." All erosion and sedimentation control works are to be completed in accordance with that publication.

The selection methodology for the most appropriate control methods has due regard to costeffectiveness, availability of materials, feasibility, durability, and compatibility. The most significant of the above is compatibility (i.e. has the system been used and proved on previous local works).

Perimeter Channel and Bunds

Diversion Channels and Cut Off Bunds are to be constructed to direct clean water away from the works and through culvert structures. The surrounding landform is steep with good vegetal



cover. Overland flow velocities will be maintained at less than 2.31 m/s, which is considered acceptable (refer IEAust Table A8.5 given full cover).

Permanent Stabilisation Measures

The proposed works do not include hard "engineered" stabilisation methods. It is not considered appropriate (cost effective) to construct "engineered" stabilisation as the existing (where undisturbed) vegetation cover provides appropriate and visually attractive stabilisation.

As part of this SWMP, rehabilitation of vegetation by seeding, drill seeding, turfing and hydro mulching, at an early stage is considered vital to the successful control of erosion (and capture of sedimentation).

Site Office

The site office and plant compound shall be fully fenced with all fuels and hazardous liquids shall be stored in a bunded area 110% the volume of stored liquid. All parking areas shall be maintained in a stable condition including surfacing as required.

Site Entry Points

There shall be only one site entry and exit point. All vehicles must enter and leave the site at these locations only. Site entry points shall also have a wash down area adjacent when stripping, and clearing and grubbing works expose plant and equipment to transportation of weeds.

The following items are proposed for incorporation into the works and details of their use and limitations have been assessed as part of the design process:

- Construction Exits (A5-C3)
- Sediment Fences (A5-C10)
- Catch Drains and Perimeter Banks (A5-A1)
- Rock Check Dams (A5-A2)

11.3.5 Erosion and Sediment Control Plan

For ESCP drawing, refer 160-001-C118 & 119

11.3.6 Implementation, Monitoring and Review

It is the responsibility of the CER to correctly implement and monitor this ESCP. It is also critical that the CER reviews and documents and provide appropriate suggestions for improvements through the project life.

11.3.7 Implementation Strategies

To ensure the objectives of the Erosion and Sediment Control Plan (ESCP) check list of responsibilities and requirements are provided below.

Actions	Locations	Timing	Responsibility
Induct all personnel as appropriate	All	Prior to Disturbance	CER



Flag the limits of disturbance and advise workforce of these limits.	Each stage of excavation.	Prior to disturbance.	CER
Divert clean water around site using lined or vegetated drains.	Perimeter of site.	Prior to disturbance.	CER
Install sediment control devices.	As per ESCP.	Prior to disturbance.	CER
Flag limits of stockpile sites clear of drainage paths and enclose with sediment fence.	As approved	Duration of works	CER
Prevent stormwater from running over exposed batters by installing catch banks/drains and directing into a stabilized batter chute or off site.	All exposed batters.	As work progresses.	WS
Install check dams in bare earth table drains if required.	Bare earth table drains	As soon as practicable.	WS
Topsoil shall be stockpiled and respread over bare areas prior to grassing to assist re-vegetation.	Bare batters and footpaths	After earthworks are completed	WS
As far as possible, the surface of batters and drains should be left in a roughened state to reduce runoff velocity and promote re-vegetation.	Earth batters and drains	As earthworks proceed.	WS
Bare earth batters to be hydro mulched to protect the surfaces using suitable species mix and application rates.	Earth Batters	As works progress or immediately following final trim of an area.	WS
Footpaths and disturbed areas to be seeded within 1 week of final trim	All exposed areas	As works progress	WS
All ESC devices to remain in place until at least 70% vegetation cover	All exposed areas	At completion of project	WS



11.3.8 Monitoring Requirements

Parameter / Item	Locations	Timing	Responsibility
Visually assess condition of erosion and sediment control devices, clean out sediment (if required), and repair any damage.	All job sites	Daily	WS
Visually inspect the turbidity of runoff leaving the site to determine effectiveness of erosion and sediment controls devices.	All job sites.	During and following any significant rainfall/runoff event.	WS
Record turbidity (photo of turbidity tube) of water over topping sediment control devices.	Downstream of structure.	During and following any significant rainfall/runoff event.	CER
Measure turbidity 50m upstream and 50m downstream.	Downstream of site.	Following rainfall event >10mm	CER
Obtain regular weather forecasts from the Bureau of Meteorology to assess risk.	Forecasts for Cairns district.	Daily.	WS

11.3.9 Reporting

The CER shall maintain appropriate records of each inspection and/or action and shall report any non-conformance incidents to the PM and Inspection Officer for action.

11.3.10 Audit

Auditing shall be completed by the PM following a major non-conformance and during random inspections if deemed necessary.

The PM shall report audit findings to the CER for action.

11.3.11 Emergency Procedures

In the event that a significant failure occurs, and that sediment-laden runoff is leaving the site the CER shall immediately protect the erosion source by:

- Covering the affected area with plastic or geofabric if localised;
- Reducing the flow velocities by installing check dams;
- Rock armour channels where velocities and turbulence are excessive;
- Other methods as deemed appropriate;

The PM shall be notified to jointly assess clean up requirements and if further action is required.

11.3.12 Corrective Action

The CER shall record any non-conformance with the EMP(C) on the Non-Conformance Report (NCR) located within Council's Quality System and notify the Inspection Officer.

11.3.13 Environmental Site Induction

All personnel (staff, workforce, sub-contractors, and plant operators) working on site are to receive appropriate induction as to the requirements of this SWMP.



It is the responsibility of the CER to ensure all site personnel receive appropriate awareness training and induction prior to or as soon as practicable after, commencement on site. The induction shall include instruction regarding the following:

- · Environmental objectives and policies;
- Due diligence;
- Environmental duty of care;
- Duties and responsibilities of environmental officers;
- · Key environmental issues relating to this project;
- Project specific requirements contained in the Management Plans;

Where deemed appropriate for short-term personnel (including visitors), the CER may elect to provide a brief environmental explanation/induction and control access to the site.

The CER shall maintain a register, signed by all inductees. The CER shall also monitor the existing workforce to ascertain if additional training is required.

11.3.14 Environmental Reporting

The Inspection Officer shall submit an Environmental Report on a monthly basis that will cover the following items:

- · Results of all monitoring;
- NCR's against the EMP(C) in accordance with the Quality procedures;
- Monthly EMP(C) review and revisions:
- · Results of internal and external audits.

Where an event of potential or actual serious environmental harm is identified, the CER shall immediately inform the PM. The PM shall inform the Inspection Officer (or his representative), Council and the EPA as soon as practicable (but no later than 24 hours).

The PM shall monitor environmental performance throughout the project to determine if and when additional Environmental Audits are required.

11.3.15 Environmental Audits

Environmental Audits of the EMP(C) shall be completed by the PM at the following times:

- Following and event of potential or actual serious environmental harm;
- Prior to submission of "Practical Completion";
- · As deemed necessary.




APPENDIX A


Design Drawings




APPENDIX B

Q100 Design Sketches









APPENDIX C Statement of Compliance

FNQROC DEVELOPMENT MANUAL

Council	Mareeba Shire Council
	(INSERT COUNCIL NAME)

STATEMENT OF COMPLIANCE OPERATIONAL WORKS DESIGN

This form duly completed and signed by an authorised agent of the Designer shall be submitted with the Operational Works Application for Council Approval.

Name of Development Wylandra Estate Stage 1

Location of Development . Wylandra Drive, Mareeba

Applicant Tyronne Corporation

Designer ERSCON Consulting Engineers

It is hereby certified that the Calculations, Drawings, Specifications and related documents submitted herewith have been prepared, checked and amended in accordance with the requirements of the FNQROC Development Manual and that the completed works comply with the requirements therein, **except** as noted below.

Compliance with the requirements of the Operational Works Design Guidelines	Non-Compliance refer to non-compliance report / drawing number
Plan Presentation	
Geotechnical requirements	
Geometric Road Design	
Pavements	
Structures / Bridges	N/A
Subsurface Drainage	
Stormwater Drainage	
Site Re-grading	
Erosion Control and Stormwater Management	
Pest Plant Management	N/A
Cycleway / Pathways	N/A

Landscaping	N/A
Water Source and Disinfection/Treatment Infrastructure (if applicable)	N/A
Water Reticulation, Pump Stations and water storages	
Sewer Reticulation and Pump Stations	N/A
Electrical Reticulation and Street Lighting	N/A
Public Transport	N/A
Associated Documentation/ Specification	
Priced Schedule of Quantities	
Referral Agency Conditions	
Supporting Information (AP1.08)	
Other	

Conscientiously believing the above statements to be true and correct, signed on behalf of:

Designer ...ERSCON Consulting Engineers...... **RPEQ No** ...05085...

Name in Full .John Dale Martin. -

Signature Date .25/06/2024



APPENDIX D Hydrological Analysis

JOB NO: 160-010

JOB: Wylandra Stage 1 Drainage

TITLE: Catchment 1 DATE: 1/05/2024




Time of concentration Calculation (Using Bransby-Williams' Equation)

Proportionality Factor 58 (for Ha)

Length of Flow Path L= 1.099 km Top of Catchment (RL) RL = <mark>22.90</mark> Ha Area of Catchment

Catchment Profile		459 [to utilise graph area bett	
Chainage	RL	RL	Area under Graph (m²)
0	459	0	
500	462	3	750
1000	467	8	2750
1000	467	8	0
1000	467	8	0
1000	467	8	0
1000	467	8	0
1000	467	8	0
1000	467	8	0
1099	468.5	9.5	866


Total area under graph Area below outlet level Area above outlet		4366 0 4366		m^2 m^2 m^2
Height for average slope			7.95	m
Average Slope	S =		0.7	%



Tc= (A ^ 0.1) x (S ^ 0.2)

Tc = 49.7 min

Adopted Tc 50.0 min



Flow Calculation for Upstream Catchment

Catchment 1

Fraction Impervious = $f_i = 0.1$ Table Below (QUDM Table 4.5.3) 1 hour @ 10 year ARI = $^{1}I_{10} = 60.4$ mm/hr (IFD CHARTS) $C_{10} = 0.59$ (QUDM Table 4.5.3)

AEP		63%	39%	18%	10%	5%	2%	1%		
Design ARI		1	2	5	10	20	50	100		
Frequency Factor	F _Y	0.8	0.85	0.95	1	1.05	1.15	1.2		(QUDM Table 4.5.2)
Coefficient of Discharge	C_Y	0.472	0.5015	0.5605	0.59	0.6195	0.6785	0.708		(QUDM Equation 4.3)
Time of Concentration	T _C	50	50	50	50	50	50	50	min	
Rainfall Intensity	^{97min} l ₁₀	39	44	59	68	77	88	96	mm/hr	(IFD CHARTS)
Area	A	22.9	22.9	22.9	22.9	22.9	22.9	22.90	На	
Path A Flow		1.17	1.40	2.09	2.55	3.02	3.78	4.30	m³/s	
Velocity		1.357	1.429	1.599	1.689	1.769	1.879	1.944	m/s	Taken from ERSCON
Height		0.318	0.347	0.419	0.460	0.497	0.551	0.585	m	Super Drain Table

JOB NO: 160-010

JOB: Wylandra Stage 1 Drainage

TITLE: Catchment 2 DATE: 1/05/2024



Proportionality Factor P= 58 (for Ha)


Length of Flow Path Top of Catchment (RL) Area of Catchment 0.580 km 460 m 8.12 Ha L= RL = A =

Catchment Profile	455.7	[to utilise graph area better]

Chainage	RL	RL	Area under Graph (m²)
0	455.7	0	
300	456.2	0.5	75
300	456.2	0.5	0
300	456.2	0.5	0
300	456.2	0.5	0
300	456.2	0.5	0
300	456.2	0.5	0
300	456.2	0.5	0
300	456.2	0.5	0
580	460	4	630

			%
Height for average slope		2.43	m
Total area under graph Area below outlet level Area above outlet	705 0 705		m ² m ²






Tc = (A ^ 0.1) x (S ^ 0.2)

Tc = 32.5 min

Adopted Tc 32.0 min



Flow Calculation for Upstream Catchment

Catchment 2

Fraction Impervious = $f_i = 0.1$ Table Drain (QUDM Table 4.5.3) 1 hour @ 10 year ARI = $^{1}I_{10} = 60.4$ mm/hr (IFD CHARTS) $C_{10} = 0.59$ (QUDM Table 4.5.3)

AEP		63%	39%	18%	10%	5%	2%	1%		
Design ARI		1	2	5	10	20	50	100		
Frequency Factor	F_Y	0.8	0.85	0.95	1	1.05	1.15	1.2		(QUDM Table 4.5.2)
Coefficient of Discharge	C _Y	0.472	0.5015	0.5605	0.59	0.6195	0.6785	0.708		(QUDM Equation 4.3)
Time of Concentration	T _C	32.0	32	32	32	32	32	32.0	min	
Rainfall Intensity	10min I 10	51	57	77	89	100	115	125	mm/hr	(IFD CHARTS)
Area	A	8.12	8.12	8.12	8.12	8.12	8.12	8.12	На	
Path B Flow		0.54	0.65	0.97	1.18	1.40	1.76	2.00	m³/s	
Velocity		1.026	1.082	1.222	1.293	1.359	1.450	1.503	m/s	Taken from ERSCON
Height		0.206	0.224	0.271	0.297	0.322	0.359	0.381	m	Super Drain Table

JOB NO: 160-010

JOB: Wylandra Stage 1 Drainage

TITLE: Catchment 3 DATE: 1/05/2024



P= Proportionality Factor 58 (for Ha)


Length of Flow Path Top of Catchment (RL) Area of Catchment <mark>1.584</mark> km L= RL = 469 m 27.30 Ha

Catchment Profile 454.8 [to utilise graph area better]

			to aimee grapii area zene						
Chainage	RL	RL	Area under Graph (m²)						
0	454.8	0							
250	457.8	3	375						
500	460.8	6	1125						
750	462.9	8.1	1763						
1000	466.7	11.9	2500						
1500	468	13.2	6275						
1500	468	13.2	0						
1500	468	13.2	0						
1500	468	13.2	0						
1584	469.0	14.2	1151						

Total area under graph 13188 m^2 ${\rm m}^{\rm 2}$ Area below outlet level 0 13188 Area above outlet m^2 Height for average slope 16.65 m **Average Slope** s = % 1.1






Tc = (A ^ 0.1) x (S ^ 0.2)

65.3 min

Adopted Tc 65.0 min



Flow Calculation for Upstream Catchment

Catchment 3

Fraction Impervious = $f_i = 0.1$ Table Drain (QUDM Table 4.5.3) $^{1}I_{10} = 60.4$ 1 hour @ 10 year ARI = (IFD CHARTS) mm/hr $C_{10} = 0.59$ (QUDM Table 4.5.3)


AEP		63%	39%	18%	10%	5%	2%	1%		
Design ARI		1	2	5	10	20	50	100		
Frequency Factor	F_Y	0.8	0.85	0.95	1	1.05	1.15	1.2		(QUDM Table 4.5.2)
Coefficient of Discharge	C _Y	0.472	0.5015	0.5605	0.59	0.6195	0.6785	0.708		(QUDM Equation 4.3)
Time of Concentration	T _C	65	65	65	65	65	65	65	min	
Rainfall Intensity	9min I ₁₀	33	37	49	57	65	74	80	mm/hr	(IFD CHARTS)
Area	A	27.3	27.3	27.3	27.3	27.3	27.3	27.30	На	
Path C Flow		1.18	1.41	2.10	2.56	3.03	3.79	4.31	m³/s	
Velocity		1.332	1.393	1.541	1.619	1.689	1.786	1.844	m/s	Taken from ERSCON
Height		0.423	0.457	0.542	0.589	0.632	0.694	0.732	m	Super Drain Table




APPENDIX E

Hydraulic Analysis






















APPENDIX F

Decision Notice



APPENDIX G

EPANet



Network Table - Nodes


Node ID	Base Demand LPS	Demand LPS	Head m	Pressure m
June J-1	1	0.10	494.00	35.00
June J-2	1	0.10	489.87	31.87
June J-7	1	0.10	486.01	28.01
June J-8	1	0.10	484.31	26.31
June J-9	1	0.10	481.70	23.70
June J-10	1	0.10	490.47	32.47
June J-11	1	0.10	490.47	32.47
June J-12	1 0.10		490.47	32.47
June J-13	1	0.10	485.92	27.92
June J-14	1	0.10	481.76	23.76
June FF	290	27.96	481.33	23.33
June J-16	1	0.10	484.31	26.31
June J-17	1	0.10	490.47	32.47
June J-18	1	0.10	490.47	32.47
June J-3	1	0.10	485.16	27.16
June J-4	1	0.10	483.85	25.85
June J-5	1	0.10	482.51	24.51
June J-6	1	0.10	486.64	28.64
June J-19	1	0.10	488.31	30.31
June FH3	1	0.10	485.96	27.96
June FH4	1	0.10	484.31	26.31
June FH5	1	0.10	481.64	23.64
June J-21	1	0.10	481.90	23.90
June J-22	1	0.10	482.46	24.46
June J-23	1	0.10	490.47	32.47
June FH1	1	0.10	490.47	32.47
June J-24	1	0.10	490.47	32.47
June J-25	1	0.10	490.47	32.47

Node ID	Base Demand LPS	Demand LPS	Head m	Pressure m
June FH2	1	0.10	490.46	32.46
Resvr Rv-1	#N/A	-30.66	494.00	0.00

Network Table - Links

Link ID	Length m	Diameter mm	Flow LPS	Velocity m/s
Pipe 1	219.76	150	30.56	1.73
Pipe 7	85.35	100	-1.97	0.25
Pipe 9	84.85	100	-2.45	0.31
Pipe 13	52.64	100	0.19	0.02
Pipe 14	163.57	150	0.10	0.01
Pipe 8	99.94	63	2.06	0.66
Pipe 15	79.60	63	2.35	0.75
Pipe 16	148.31	63	2.26	0.72
Pipe 17	7 165.83 63		2.16	0.69
Pipe 18	103.64	150	-29.50	1.67
Pipe 19	111.76	150	-29.40	1.66
Pipe 20	42.17	150	29.31	1.66
Pipe 21	4.04	150	-26.76	1.51
Pipe 22	132.04	150	-26.66	1.51
Pipe 23	5.48	150	-0.19	0.01
Pipe 24	309.77	150	-0.10	0.01
Pipe 25	3.88	150	28.05	1.59
Pipe 26	23.22	150	27.96	1.58
Pipe 27	151.72	150	26.37	1.49
Pipe 28	46.03	150	26.28	1.49
Pipe 29	16.67	150	26.18	1.48
Pipe 30	68.77	150	-0.10	0.01
Pipe 31	92.82	150	0.19	0.01
Pipe 32	3.18	150	0.29	0.02
Pipe 33	31.76	150	-0.77	0.04
Pipe 34	146.66	150	0.67	0.04
Pipe 35	87.65	150	0.58	0.03
Pipe 36	0.99	150	29.69	1.68

Link ID	Length m	Diameter mm	Flow LPS	Velocity m/s
Pipe 37	39.00	150	-29.59	1.67
Pipe 38	1	300	30.66	0.43



Network Table - Nodes

Node ID	Base Demand LPS	Demand LPS	Head m	Pressure m
June J-1	1	0.10	494.00	35.00
June J-2	1	0.10	493.96	35.96
June J-7	1	0.10	493.94	35.94
June J-8	1	0.10	493.94	35.94
June J-9	1	0.10	493.93	35.93
June J-10	1	0.10	493.96	35.96
June J-11	1	0.10	493.96	35.96
June J-12	1	0.10	493.96	35.96
June J-13	1	0.10	493.94	35.94
June J-14	1	0.10	493.93	35.93
June J-15	1	0.10	493.93	35.93
June J-16	1	0.10	493.94	35.94
June J-17	1	0.10	493.96	35.96
June J-18	1	0.10	493.96	35.96
June J-3	1	0.10	493.93	35.93
June J-4	1	0.10	493.93	35.93
June J-5	1	0.10	493.93	35.93
June J-6	1	0.10	493.94	35.94
June J-19	1	0.10	493.95	35.95
June FH3	1	0.10	493.94	35.94
June FH4	1	0.10	493.94	35.94
June FH5	1	0.10	493.93	35.93
June J-21	1	0.10	493.93	35.93
June J-22	1	0.10	493.93	35.93
June J-23	1	0.10	493.96	35.96
June FH1	1	0.10	493.96	35.96
June J-24	1	0.10	493.96	35.96
June J-25	1	0.10	493.96	35.96
June FH2	1	0.10	493.96	35.96
Resvr Rv-1	#N/A	-2.80	494.00	0.00

Network Table - Links

Link ID	Length m	Diameter mm	Flow LPS	Velocity m/s
Pipe 1	219.76	150	2.70	0.15
Pipe 7	85.35	100	0.20	0.03
Pipe 9	84.85	100	-0.28	0.04
Pipe 13	52.64	100	0.19	0.02
Pipe 14	163.57	150	0.10	0.01
Pipe 8	99.94	63	-0.10	0.03
Pipe 15	79.60	63	0.19	0.06
Pipe 16	148.31	63	0.09	0.03
Pipe 17	165.83	63	-0.01	0.00
Pipe 18	103.64	150	-1.64	0.09
Pipe 19	111.76	150	-1.54	0.09
Pipe 20	42.17	150	1.45	0.08
Pipe 21	4.04	150	-1.07	0.06
Pipe 22	132.04	150	-0.97	0.05
Pipe 23	5.48	150	-0.19	0.01
Pipe 24	309.77	150	-0.10	0.01
Pipe 25	3.88	150	0.19	0.01
Pipe 26	23.22	150	0.10	0.01
Pipe 27	151.72	150	0.68	0.04
Pipe 28	151.02	150	0.59	0.03
Pipe 29	54.70	150	0.49	0.03
Pipe 30	68.77	150	-0.10	0.01
Pipe 31	92.82	150	0.19	0.01
Pipe 32	3.18	150	0.29	0.02
Pipe 33	31.76	150	-0.77	0.04
Pipe 34	146.66	150	0.67	0.04
Pipe 35	87.65	150	0.58	0.03
Pipe 36	0.99	150	1.83	0.10
Pipe 37	39.00	150	-1.74	0.10
Pipe 38	1	300	2.80	0.04

P05-F-DD01 Document Transmittal

Project: Wylandra Estate Stage 1

Attention: Patrick McNamee



www.erscon.com.au

Company: Tyrone Corp Pty Ltd

12 12 12 Month From: **ERSCON Consulting Engineers** Year 24 24

Dwg/Doc Number	Dwg/Doc Title			Revision												
160-010-C101	Cover Sheet, Locality Plan and Drawing List	1	3	Α							В				Т	
160-010-C102	General Notes	1	1	Α							Α				T	
160-010-C103	Existing Layout	1	2	Α							Α				T	
160-010-C104	General Layout (Sheet 1 of 2)	1	3	Α							Α				T	
160-010-C105	General Layout (Sheet 2 of 2)	1	3	Α							Α				T	
160-010-C106	Road Longitudinal Section (Sheet 1 of 2)	1	3	Α							Α				T	
160-010-C107	Road Longitudinal Section (Sheet 2 of 2)	1	3	Α							Α				T	
160-010-C108	Typical Road Cross Section and Details	1	2	Α							Α				T	
160-010-C109	Intersection Details	1	3	Α							В				T	
160-010-C110	Grading Plan (Sheet 1 of 2)	1	3	Α							В				T	
160-010-C111	Grading Plan (Sheet 2 of 2)	1	3	Α							В				T	
160-010-C112	Water Plan (Sheet 1 of 2)	1	3	Α							Α				T	
160-010-C113	Water Plan (Sheet 2 of 2)	1	3	Α							Α				T	
160-010-C114	Stormwater Q5 Minor and Drainage Plan (Sheet 1 of 2)	1	3	Α							В				T	
160-010-C115	Stormwater Q5 Minor and Drainage Plan (Sheet 2 of 2)	1	3	Α							Α				T	
160-010-C116	Drain Longitudinal Section	1	3	Α							В				T	
160-010-C117	Stormwater Q5 Minor Longitudinal Section		1	Α							Α				T	
160-010-C118	Erosion and Sediment Control Plan (Sheet 1 of 2)	1	3	Α							Α				T	
160-010-C119	Erosion and Sediment Control Plan (Sheet 2 of 2)	1	3	Α							Α				T	
160-010-C120	Erosion and Sediment Control Notes	1		Α							Α				T	
160-010-C121-125	Cross Sections	1		Α							Α				T	
160-010-C126	Detention Basin Plan	1		Α							Α				T	
160-010-C127	Detention Basin Long Section	1		Α							Α				T	
160-010-C128	Detention Basin Cross Section (Sheet 1 of 2)	1		Α							Α				T	
160-010-C129	Detention Basin Cross Section (Sheet 2 of 2)	1		Α							Α				T	
		1		Α												
060-010-SK09	Catchment Plan				1										T	
160-010-R001	Wylandra Operational Works Application			Α							В				T	
160-010-R002	Wylandra Stormwater Management Plan			Α							В				T	
160-101-SK12	Options 2 - Drainage Park					1									T	
160-010-SK13	Total Catchments					1									T	
161-010-R003	Stage 1 Extra overland Flow generated report						Α	В	С	D					T	
Minutes No 3	Minutes No 3 (24 October 2024)					1									T	

Company Name	Attention	Number of Copies											
Tyrone Corp	Patrick McNamee	1	1		1	1	1	1	1	1	1		
Tyrone Corp	Peter McNamee	1	1			1	1	1	1	1	1		
	Monique Quirk		1			1							
ConMat	Roy Lavis	1	1		1	1	1	1	1	1	1		
ConMat	Steven Lavis	1	1			1	1	1	1	1	1		

A - Approval	T - Tender Issue	R - As Requested		Reason for Issue												
P - Preliminary	C - Constructon Issue	FI - For Information	Р	Р		FI	FI	FI	FI	FI	FI	FI				

A - Original	С - Сору	P - PDF		Format Issued												
M - Model	D - Acad Drawing	O - Other	Р	Р		Р	Р	Р	Р	Р	Р	Р				

P05-F-DD01 Document Transmittal

M- Mail	C - To be Collected	E - E-Mail	Method of Delivery											
H - Hand Delivery	CO - Courier	O - Other	Е	Ε		Е	Е	Е	Е	Е	Е	Е		